



WATER SERVICES
ASSOCIATION OF AUSTRALIA

GRAVITY SEWERAGE CODE OF AUSTRALIA

Regional New South Wales Edition
Version 1



WATER
DIRECTORATE

WSA 02-2014-3.1

Contents

List of Figures.....	33
List of Tables.....	37
FRONTMATTER.....	2
GENERAL.....	2
ACKNOWLEDGEMENTS.....	2
ABOUT WSAA.....	3
ACKNOWLEDGEMENT OF COUNTRY.....	3
DISCLAIMER.....	3
COPYRIGHT.....	3
ALL RIGHTS RESERVED	3
FOREWORD.....	3
PREFACE.....	4
THE NEED FOR TECHNICAL DOCUMENTATION.....	4
The Benefits of National Codes.....	5
Innovation.....	5
HYPOTHETICAL EXAMPLE OF THE USE OF THE GRAVITY SEWERAGE CODE.....	6
Concept Plan.....	6
Agency/Development Agreement.....	6
Project Manager.....	6
Design.....	7
Specification.....	7
Constructor.....	7
Testing.....	7
The WSAA Website.....	7
INTRODUCTION.....	7
SCOPE OF CODE.....	7
CODE OF PURPOSE.....	8
MANDATORY AND INFORMATIVE.....	8
APPENDICES.....	9
PRODUCT SPECIFICATIONS.....	9
General.....	9
Quality Assurance.....	9
Products and Material Information and Guidance.....	9
Water Industry Standards.....	10
WORK HEALTH AND SAFETY (WHS) LAWS.....	10
NATIONAL STANDARD FOR CONSTRUCTION WORK.....	10
SAFE DESIGN OF STRUCTURES.....	11
PROPOSED AMENDMENTS.....	12
USING STANDARD DRAWINGS IN CONJUNCTION WITH THE CODE.....	12
GLOSSARY, ABBREVIATIONS AND REFERENCES.....	41
I GLOSSARY OF TERMS.....	41
II ABBREVIATIONS.....	56
III REFERENCED DOCUMENTS.....	59
PART 1: PLANNING AND DESIGN.....	64
1 GENERAL.....	64

1.1 SCOPE.....	64
1.2 PLANNING AND DESIGN.....	64
1.2.1 Objectives.....	64
1.2.2 Scope and requirements.....	64
1.2.3 Servicing strategies.....	65
1.2.4 Functional design requirements.....	65
1.2.5 Concept plan format.....	66
1.2.6 Critical infrastructure protection.....	67
1.2.6.1 General.....	67
1.2.6.2 Asset categorisation.....	67
1.2.6.3 All hazards – Infrastructure protection.....	68
1.2.7 Detailed design.....	68
1.2.7.1 Designer's needs and responsibilities.....	68
1.2.7.2 Requirements to be addressed.....	68
1.2.7.3 Design outputs.....	69
1.2.7.4 Safety in design.....	70
1.3 CONSULTATION WITH OTHER PARTIES.....	70
1.3.1 Design life.....	70
1.3.2 Instrumentation and control systems.....	70
2 SYSTEM PLANNING.....	74
2.1 GENERAL.....	74
2.2 SEWER SYSTEM PHILOSOPHY AND DEFINITION.....	74
2.2.1 Disaggregation.....	74
2.2.2 Level 1 Total system.....	75
2.2.3 Level 2 Transportation subsystems.....	75
2.2.4 Level 3 operating units.....	75
2.2.4.1 Sewers.....	75
2.2.4.2 Sewage pumping stations (SPSs).....	76
2.2.4.3 Storage.....	76
2.3 PLANNING PRINCIPLES.....	76
2.3.1 Planning horizon.....	76
2.3.2 Concept plan.....	76
2.3.3 Catchment analysis.....	76
2.3.4 Provision for future gauging needs.....	77
2.4 PLANNING PARAMETERS.....	77
2.4.1 Loading per serviced lot.....	77
2.4.2 Estimating future catchment loads.....	78
2.4.3 Estimating existing system loads.....	78
2.4.4 Climate change impacts.....	78
2.4.5 Environmental, cultural and heritage impacts.....	79
2.4.6 Geotechnical investigations.....	79
2.4.7 Contaminated sites.....	79
2.4.8 Operations and maintenance considerations.....	80
2.4.9 Sewer mining.....	80
2.5 SEWAGE QUALITY.....	80
2.5.1 Septicity.....	80

2.5.2 Australian sewage quality management guidelines.....	82
2.6 PLANNING REVIEW.....	82
3 FLOW ESTIMATION.....	83
3.1 GENERAL.....	83
3.2 DESIGN FLOW ESTIMATION.....	83
3.3 DESIGN FLOW ESTIMATION METHOD.....	83
3.3.1 General.....	83
3.3.2 Traditional design flow estimation method.....	84
3.3.3 Design flow estimation incorporating existing systems.....	84
3.3.4 Design flow estimation—Partially pumped systems.....	84
3.3.5 Flow schedule.....	84
4 PRODUCTS AND MATERIALS.....	85
4.1 GENERAL.....	85
4.2 IDENTIFICATION OF SEWER SYSTEMS.....	85
4.3 SERVICABILITY OF SEWER SYSTEMS.....	88
4.4 PROTECTION AGAINST DEGRADATION.....	88
4.5 DUCTILE IRON GRAVITY SEWERS.....	88
4.5.1 Product Specifications.....	88
4.5.2 Sizes and configurations.....	89
4.5.3 Cement mortar lining.....	89
4.5.4 Sleeving.....	90
4.5.5 Screw-on flanges for DI pipes.....	90
4.5.6 Flanged joints.....	90
4.5.7 Coatings.....	91
4.6 PVC GRAVITY SEWERS.....	92
4.6.1 Product Specifications.....	92
4.6.2 Sizes and configurations.....	92
4.7 POLYETHYLENE GRAVITY SEWERS.....	92
4.7.1 Product Specifications.....	92
4.7.2 Sizes and configurations.....	93
4.8 POLYPROPYLENE GRAVITY SEWERS.....	93
4.8.1 Product Specifications.....	93
4.8.2 Sizes and configurations.....	94
4.9 GRP GRAVITY SEWERS.....	94
4.9.1 Product Specifications.....	94
4.9.2 Sizes and configurations.....	94
4.10 PLASTICS-LINED CONCRETE GRAVITY SEWERS.....	94
4.10.1 Product Specifications.....	94
4.10.2 Sizes and configurations.....	95
4.11 VITRIFIED CLAY SEWERS.....	95
4.11.1 Product Specifications.....	95
4.11.2 Sizes and configurations.....	95
4.12 STEEL GRAVITY SEWERS.....	95
4.12.1 Product Specifications.....	95
4.12.2 Sizes and configurations.....	96
4.12.3 Joints.....	96

4.12.4 Field welding.....	96
4.12.5 Flanged joints.....	96
4.13 MAINTENANCE STRUCTURES.....	96
4.13.1 Product Specifications.....	96
4.13.2 Classification and application.....	97
4.13.3 Sizes and configurations.....	98
4.14 MARKING TAPES.....	98
4.14.1 Product Specifications.....	98
4.14.2 Application.....	99
4.15 ACCESS COVERS AND FRAMES.....	99
4.15.1 Product Specifications.....	99
4.15.2 Application.....	99
4.15.3 Cast ductile iron access covers and frames.....	99
4.15.4 Polymeric access covers and frames.....	100
4.15.5 Not Used.....	100
4.15.6 Size and configuration.....	100
4.15.7 Marking of access covers and frames.....	101
4.16 VENT SHAFTS.....	101
4.16.1 Product Specifications.....	101
4.16.2 Application.....	101
5 DETAIL DESIGN.....	102
5.1 DETAIL DESIGN PROCESS.....	102
5.2 DETAIL DESIGN CONSIDERATIONS.....	103
5.2.1 Catchment design.....	103
5.2.2 Design accuracy.....	103
5.2.3 Sewer layout.....	103
5.2.4 Location of sewers.....	104
5.2.4.1 General.....	104
5.2.4.2 Sewers located along side boundaries.....	105
5.2.4.3 Sewers located along rear boundaries.....	105
5.2.4.4 Sewers located in small lots (lot area $\leq 450 \text{ m}^2$).....	105
5.2.4.5 Sewers servicing industrial /commercial lots.....	106
5.2.4.6 Branch and trunk sewers.....	106
5.2.5 Trenchless techniques for pipe installation.....	106
5.2.6 Near-horizontal boreholes and tunnels.....	107
5.2.6.1 General.....	107
5.2.6.2 Design requirements.....	107
5.2.6.3 Silt traps.....	109
5.2.7 Environmental, cultural and heritage considerations.....	109
5.2.7.1 General.....	109
5.2.7.2 Urban salinity.....	110
5.2.7.3 Acid sulphate soils.....	110
5.2.7.4 Vegetation.....	111
5.2.7.5 Coastal zones.....	111
5.2.8 Easements.....	112
5.2.9 Disused sewers.....	113

5.2.10 Special design considerations.....	113
5.3 HORIZONTAL ALIGNMENT OF SEWERS.....	113
5.3.1 General.....	113
5.3.2 Roads, reserves and open space.....	113
5.3.3 Railway reserves.....	114
5.3.4 Waterways.....	114
5.3.5 Maintenance structures and vent shafts.....	115
5.3.6 Changes in direction using an MH.....	115
5.3.7 Changes in direction using an MS or MC.....	116
5.3.8 Not used.....	116
5.3.8.1 Not used.....	116
5.3.8.2 Not used.....	116
5.3.8.3 Not used.....	116
5.4 OBSTRUCTIONS AND CLEARANCES.....	116
5.4.1 General.....	116
5.4.2 Surface obstructions.....	116
5.4.3 Clearance from transmission towers and power lines.....	117
5.4.4 Clearance from structures.....	117
5.4.5 Underground obstructions and services.....	117
5.4.5.1 General.....	117
5.4.5.2 Clearance requirements.....	118
5.4.6 Marker posts.....	118
5.5 PIPE SIZING AND GRADING.....	119
5.5.1 General.....	119
5.5.2 Environmental protection requirements.....	119
5.5.3 Minimum air space.....	119
5.5.4 Minimum pipe sizes for maintenance purposes.....	119
5.5.5 Maximum ET for reticulation sewers.....	120
5.5.5.1 General.....	120
5.5.5.2 Design assumptions.....	121
5.5.6 Limitation on sewer size reduction.....	122
5.5.7 Minimum grades for self-cleansing.....	122
5.5.7.1 General.....	122
5.5.7.2 Reticulation sewers.....	123
5.5.7.3 Property connection sewers and end-of-line sewers.....	124
5.5.8 Minimum grades for slime control.....	124
5.5.9 Maximum grades.....	124
5.5.9.1 Branch and trunk sewers.....	124
5.5.9.2 Reticulation sewers.....	125
5.6 VERTICAL ALIGNMENT OF SEWERS.....	125
5.6.1 General.....	125
5.6.2 Long section design plan.....	125
5.6.3 Minimum cover over sewers.....	126
5.6.4 Lot servicing requirements.....	126
5.6.4.1 General.....	126
5.6.4.2 Serviced area requirements for residential lots.....	127

5.6.4.3	5.6.4.3 Serviced area requirements for industrial and commercial lots.....	127
5.6.4.4	5.6.4.4 Partial lot service.....	127
5.6.4.5	5.6.4.5 Servicing of basements.....	128
5.6.4.6	5.6.4.6 Servicing of developed lots.....	128
5.6.5	5.6.5 Minimum depth of sewer connection point.....	128
5.6.5.1	5.6.5.1 General.....	128
5.6.5.2	5.6.5.2 Soffit requirement.....	128
5.6.5.3	5.6.5.3 Physical losses in customer sanitary drains.....	129
5.6.5.4	5.6.5.4 Depth of connection point.....	130
5.6.6	5.6.6 Grading through MHs.....	130
5.6.6.1	5.6.6.1 General.....	130
5.6.6.2	5.6.6.2 Internal fall through MHs joining sewers of same diameter.....	131
5.6.6.3	5.6.6.3 Internal falls through MHs joining sewers of different diameters.....	131
5.6.6.4	5.6.6.4 Major sewer junctions.....	132
5.6.6.5	5.6.6.5 Large falls at MHs.....	132
5.6.6.6	5.6.6.6 Avoiding hydraulic jumps due to steep grades.....	132
5.6.6.6.1	5.6.6.6.1 GENERAL.....	132
5.6.6.6.2	5.6.6.6.2 BRANCH AND TRUNK SEWERS.....	133
5.6.6.6.3	5.6.6.6.3 RETICULATION SEWERS.....	133
5.6.6.7	5.6.6.7 Avoiding deep channels in MHs due to steep grades.....	134
5.6.7	5.6.7 Not Used.....	135
5.6.8	5.6.8 Not Used.....	135
6	6 PROPERTY CONNECTION.....	136
6.1	6.1 GENERAL.....	136
6.2	6.2 LIMITATIONS OF CONNECTION TO SEWERS.....	136
6.3	6.3 METHODS OF THE PROPERTY CONNECTION.....	136
6.3.1	6.3.1 General.....	136
6.3.2	6.3.2 IO interface method.....	136
6.3.3	6.3.3 Buried interface method.....	137
6.3.4	6.3.4 Typical layouts of sewers and general arrangements for property connection sewers.....	137
6.3.5	6.3.5 Maximum depth of property connection point.....	137
6.4	6.4 NUMBER OF PROPERTY CONNECTION POINTS.....	138
6.4.1	6.4.1 Single occupancy lots.....	138
6.4.2	6.4.2 Multiple occupancy lots.....	138
6.5	6.5 LOCATION OF PROPERTY CONNECTION POINTS.....	138
6.5.1	6.5.1 General.....	138
6.5.2	6.5.2 Vacant lots.....	138
6.5.3	6.5.3 Lots with existing buildings.....	139
6.6	6.6 PROPERTY CONNECTION SEWERS.....	139
6.6.1	6.6.1 General.....	139
6.6.2	6.6.2 'Type 7 spur' or 'Y' property sewer connections.....	140
6.7	6.7 LENGTH OF PROPERTY CONNECTION SEWERS.....	141
7	7 MAINTENANCE STRUCTURES.....	142
7.1	7.1 TYPES OF MAINTENANCE STRUCTURES.....	142
7.2	7.2 LOCATIONS OF MAINTENANCE STRUCTURES.....	142
7.3	7.3 SPACING OF MAINTENANCE STRUCTURES.....	143

7.3.1 General.....	143
7.3.2 Maintenance structure spacing—Reticulation sewers.....	145
7.3.3 Maintenance structure spacing—Branch and trunk sewers.....	146
7.4 SPECIAL CONSIDERATIONS FOR LOCATION OF MAINTENANCE STRUCTURES.....	146
7.5 SPECIAL CONSIDERATIONS FOR CONNECTION OF NEW SEWERS TO EXISTING SEWERS.....	146
7.6 MAINTENANCE HOLES (MHs).....	147
7.6.1 General.....	147
7.6.2 Types of MH construction.....	147
7.6.3 Design parameters for MHs.....	148
7.6.4 Design requirements for connection of sewers to MHs.....	148
7.6.4.1 Pre-cast concrete MH base units.....	148
7.6.4.2 Cast in-situ concrete MH base units.....	150
7.6.4.3 Rocker pipes.....	152
7.6.5 Connection of property connection sewers into MHs.....	153
7.6.6 MH drops.....	153
7.6.7 Diameters of MHs.....	157
7.6.8 MH base layout.....	157
7.6.9 Ladders, step irons and landings.....	158
7.7 MAINTENANCE SHAFTS (MSs) / MAINTENANCE CHAMBERS (MCs).....	158
7.7.1 General.....	158
7.7.2 Design parameters for MCs, MSs and TMSs.....	158
7.7.3 Connections to MCs, MSs and TMSs.....	159
7.7.3.1 Connections to PE MSs and TMSs.....	160
7.7.3.2 Connections to pre-cast concrete MC base units.....	161
7.7.3.3 Connections to PP MCs and MSs.....	162
7.7.4 High-level connections to MCs, MSs and TMSs.....	162
7.7.4.1 High-level connections into a pre-cast concrete MC.....	164
7.7.4.2 High-level connections into a PE MC and MS.....	165
7.7.4.3 High-level connections into a PVC-U MS.....	166
7.7.4.4 High-level connections into a PP MC and MS.....	167
7.8 INSPECTION SHAFTS (ISs).....	170
7.8.1 General.....	170
7.8.2 Terminal inspection shaft (Type A).....	171
7.8.3 Vertical drop inspection shaft (Type B).....	171
7.8.4 Intermediate inspection shaft (Type C).....	171
7.8.5 Ends of pipe.....	172
7.8.5.1 Temporary ends of pipe.....	172
7.8.5.2 Permanent ends of pipe.....	172
7.9 MAINTENANCE STRUCTURE COVERS.....	172
7.9.1 General.....	172
7.9.2 Cross-fall on MH covers.....	174
7.9.3 Modifications to existing maintenance holes.....	175
7.10 SEWERS FROM JUNCTIONS.....	175
7.11 OTHER MAINTENANCE STRUCTURES AT INTERFACE OF PROPERTY CONNECTION SEWERS AND SANITARY DRAINS.....	176

8 ANCILLIARY STRUCTURES.....	177
8.1 GENERAL.....	177
8.2 WATER SEALS, BOUNDARY TRAPS, WATER-SEALED MHs AND GAS CHECK MHs.....	177
8.2.1 Boundary traps on sanitary drains.....	178
8.2.1.1 General.....	178
8.2.1.2 Responsibility for installation of boundary traps.....	178
8.2.2 Water seals, water-sealed MHs and gas check MHs.....	179
8.2.2.1 General.....	179
8.2.2.2 Water seals on reticulation sewers entering branch or trunk sewers.....	179
8.2.2.3 Water seals on branch sewers entering trunk sewers.....	179
8.2.3 Water-sealed MHs and gas check MHs.....	179
8.2.3.1 General.....	179
8.2.3.2 Water-sealed MHs.....	180
8.2.3.3 Gas check MHs.....	180
8.3 VERTICAL AND NEAR VERTICAL SEWERS.....	181
8.3.1 General.....	181
8.3.2 Design parameters for bored, exposed and encased vertical and near vertical sewers.....	181
8.4 VENTILATION.....	181
8.4.1 General.....	181
8.4.2 Design parameters for ventilation and location of vent shafts.....	182
8.4.3 Design details for ventilation lines, vent shafts and cowls.....	182
8.5 VORTEX INLETS AND WATER CUSHIONS.....	183
8.6 INVERTED SYPHONS.....	184
8.6.1 General.....	184
8.6.2 Design parameters for inverted syphons.....	184
8.7 EMERGENCY RELIEF STRUCTURES.....	185
8.7.1 General.....	185
8.7.2 Design parameters for ERSs.....	186
8.7.2.1 General.....	186
8.7.2.2 Configuration.....	186
8.7.2.3 Overflow pipe.....	187
8.7.2.4 Overflow level.....	187
8.8 FLOW MEASURING DEVICES.....	188
8.8.1 General.....	188
8.8.2 Within the sewer system.....	188
8.8.3 At a sewage pumping station.....	189
8.9 WET WEATHER STORAGE.....	189
8.9.1 General.....	189
8.9.2 Design considerations.....	189
9 STRUCTURAL DESIGN.....	191
9.1 GENERAL.....	191
9.2 PRODUCTS AND MATERIALS.....	191
9.3 STRUCTURAL CONSIDERATIONS.....	191
9.3.1 Pipes.....	191
9.3.2 Design factors affecting buried flexible and rigid pipes.....	192
9.3.3 Maintenance structures.....	192

9.3.3.1 Concrete requirements for cast in-situ MHs.....	193
9.3.3.2 Concrete requirements for precast MHs.....	193
9.3.3.3 Epoxy mortars for precast MHs.....	194
9.3.3.4 Internal corrosion protection of MHs.....	194
9.3.3.5 Pipe connections to MHs.....	195
9.4 LOADINGS.....	195
9.4.1 External forces.....	195
9.4.2 Native soil strength.....	196
9.4.3 Embedment zone dimensions.....	197
9.4.4 Pipe embedment.....	197
9.4.5 Buoyancy.....	198
9.4.6 Flotation.....	199
9.5 FOUNDATION DESIGN AND GROUNDWATER CONTROL.....	199
9.5.1 Migration of fines.....	200
9.6 GEOTECHNICAL CONSIDERATIONS.....	200
9.6.1 General.....	200
9.6.2 Pipelines in engineered or controlled fill.....	203
9.6.3 Pipelines in non-engineered fill.....	204
9.6.4 Filling along route of pipeline.....	204
9.6.5 Mine subsidence.....	204
9.6.6 Slip areas.....	205
9.6.7 Water-charged ground.....	205
9.7 SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS.....	205
9.7.1 General.....	205
9.7.2 Requirements.....	206
9.8 ABOVE GROUND CROSSINGS.....	208
9.9 PIPE COVER.....	208
9.10 BULKHEADS AND TRENCHSTOPS.....	208
9.11 TRENCH DRAINAGE.....	209
10 DESIGN REVIEW AND DRAWINGS.....	211
10.1 DESIGN REVIEW.....	211
10.2 DESIGN DRAWINGS.....	211
10.2.1 General.....	211
10.2.2 Composition of Design Drawings.....	211
10.2.3 Scale.....	212
10.2.4 Real property information.....	212
10.2.5 Sewers.....	212
10.2.6 Structures.....	213
10.2.7 Longitudinal sections (profiles).....	213
10.2.8 Title block notation and standard notes.....	214
10.2.9 Other.....	214
10.3 SEWER SYSTEM ACRONYMS.....	215
10.4 SPECIFICATIONS.....	215
10.5 RECORDING OF WORK AS CONSTRUCTED INFORMATION.....	216
PART 2: CONSTRUCTION.....	218
11 GENERAL.....	218

11.1 SCOPE.....	218
11.1.1 Resolution of complaints.....	218
11.2 INTERPRETATION.....	218
12 GENERAL CONSTRUCTION.....	220
12.1 GENERAL.....	220
12.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING.....	220
12.3 CONTRACT INTERFACES.....	220
12.4 CUSTOMER FOCUS.....	220
12.4.1 General.....	220
12.4.2 Resolution of complaints.....	221
12.5 PROTECTION OF PROPERTY AND ENVIRONMENT.....	221
12.5.1 Protection of other services.....	221
12.5.2 Road reserves or other thoroughfares.....	222
12.5.2.1 Road opening permits.....	222
12.5.2.2 Treatment of pavements and other surfaces.....	222
12.5.2.3 Cleanliness of roads, paths, accesses and drainage paths.....	222
12.5.2.4 Storage of products, materials, equipment and excavated material.....	222
12.5.2.5 Obstruction of street drainage.....	222
12.5.3 Private and public lands.....	223
12.5.4 Protection of the environment and heritage areas.....	223
12.5.4.1 General.....	223
12.5.4.2 Collection and disposal of wastes.....	223
12.5.4.3 Protection of adjacent lands and vegetation.....	223
12.5.4.4 Control of water pollution.....	224
12.5.4.5 Contaminated soils.....	226
12.5.4.6 Control of noise and atmospheric pollution.....	226
12.5.4.7 Equipment and machinery use in bush fire prone areas.....	226
12.6 DISUSED SEWERS.....	226
12.7 OPERATION OF SEWERAGE NETWORK.....	227
12.8 ALTERATION OF EXISTING SERVICES.....	227
12.9 SURVEY MARKS.....	227
12.10 CONSTRUCTION TOLERANCES.....	227
12.11 LATENT CONDITIONS.....	227
13 PRODUCTS AND MATERIALS.....	229
13.1 APPROVED PRODUCTS AND MATERIALS.....	229
13.2 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS.....	229
13.3 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS.....	229
13.3.1 General.....	229
13.3.2 Transportation.....	230
13.3.3 Unloading and handling.....	230
13.3.4 On-site storage.....	230
13.3.5 Plastics-lined concrete products.....	231
13.3.6 Coiled plastics pipe.....	231
13.4 CONCRETE WORKS.....	231
13.5 SUPPLY OF WATER TO THE WORKS.....	232
14 EXCAVATION.....	233

14.1 PRECAUTIONS.....	233
14.2 LIMITS OF CLEARING AND EXCAVATION.....	233
14.3 PROTECTION OF TREES.....	233
14.3.1 General precautions.....	233
14.3.2 Protection of roots.....	233
14.4 BLASTING.....	234
14.5 SUPPORT OF EXCAVATIONS.....	234
14.6 DRAINAGE AND DEWATERING.....	234
14.7 EXCAVATION ACROSS IMPROVED SURFACES.....	235
14.8 TRENCH EXCAVATION.....	235
14.8.1 General.....	235
14.8.2 Construction of embankment.....	235
14.8.3 Clearances for on-site works.....	236
14.9 REFILL OF EXCESSIVE EXCAVATION.....	236
14.10 FOUNDATIONS AND FOUNDATION STABILISATION.....	236
14.11 SURPLUS EXCAVATED MATERIAL.....	237
14.12 EXCAVATION AND PIPELAYING USING TRENCHLESS TECHNIQUES.....	237
15 BEDDING FOR PIPES AND MAINTENANCE STRUCTURES.....	238
15.1 TRENCH FLOOR PREPARATION.....	238
15.2 BEDDING MATERIALS.....	238
15.2.1 Placement of bedding.....	238
15.3 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS.....	238
15.4 BEDDING FOR MAINTENANCE CHAMBERS, MAINTENANCE SHAFTS, INSPECTION SHAFTS AND BENDS.....	239
15.5 BEDDING FOR MAINTENANCE HOLES.....	239
16 PIPE LAYING AND JOINTING.....	240
16.1 INSTALLATION OF PIPES.....	240
16.1.1 General.....	240
16.1.2 Cleaning, inspection and joint preparation.....	240
16.1.3 Coiled plastics pipes.....	240
16.1.4 Laying.....	240
16.2 HORIZONTAL AND VERTICAL DEFLECTION OF SEWERS.....	241
16.2.1 General.....	241
16.2.2 Methods of deflection.....	241
16.2.3 Not Used.....	242
16.2.4 Not Used.....	242
16.2.5 Not Used.....	242
16.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES.....	242
16.4 FLOTATION CONTROL.....	242
16.5 TRENCH STOPS.....	242
16.6 BULKHEADS.....	242
16.7 PROPERTY CONNECTION SEWERS.....	242
16.8 DEAD ENDS.....	243
16.9 MARKING OF PROPERTY CONNECTION SEWERS AND DEAD ENDS.....	243
16.10 CORROSION PROTECTION OF CAST IRON.....	243
16.11 MARKERS.....	243

16.11.1 Not Used.....	243
16.11.2 Detectable marking tape.....	243
16.12 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE.....	244
16.13 AQUEDUCTS.....	244
16.14 BRIDGE CROSSINGS.....	244
16.15 PLASTICS-LINED RC PIPE JOINTING.....	244
16.15.1 General.....	244
16.15.2 Plastics lining work protection.....	244
16.15.3 Field jointing.....	245
16.15.4 Plastics lining ancillary work.....	245
16.15.4.1 Alignment of lining keys.....	245
16.15.4.2 Provision of seepage channels.....	245
16.15.4.3 Use of jointing accessories and adhesives.....	245
16.16 WELDING OF STEEL PIPELINES.....	245
16.16.1 General.....	245
16.16.2 Field welding of flanges.....	245
16.16.3 Reinstatement of cement mortar lining.....	246
16.16.4 Reinstatement of external corrosion protection at joints using a tape system.....	246
16.16.4.1 General.....	246
16.16.4.2 Surface preparation.....	246
16.16.4.3 Priming surfaces.....	246
16.16.4.4 Mastic filler.....	247
16.16.4.5 Tape application.....	247
16.16.5 Reinstatement of external corrosion protection at joints using a heat-shrinkable sleeve system.....	248
16.16.5.1 Surface preparation.....	248
16.16.5.2 Preheat pipe.....	249
16.16.5.3 Priming surfaces.....	249
16.16.5.4 Mastic filler.....	249
16.16.5.5 Heat-shrinkable sleeve preparation.....	249
16.16.5.6 Heat-shrinkable sleeve application.....	249
16.17 WELDING OF PE PIPELINES.....	249
16.17.1 General.....	249
16.17.2 Welder qualifications.....	250
16.17.3 Connections to pipes of other materials.....	250
16.18 FLANGE JOINTS.....	250
17 MAINTENANCE HOLES (MHs).....	251
17.1 GENERAL.....	251
17.2 CONCRETE MHs.....	251
17.2.1 Concrete MH base.....	251
17.2.2 Pre-cast concrete MH systems.....	251
17.2.3 Cast in-situ concrete MH.....	252
17.2.4 Benching and channels.....	252
17.2.5 Concreting for thermoplastics-lined works.....	252
17.2.5.1 Concrete work planning.....	252
17.2.5.2 Fixing of thermoplastics lining for concrete work.....	253

17.2.5.3 Concrete placement and formwork removal.....	253
17.2.6 Internal coating of concrete MHs.....	253
17.3 GLASS REINFORCED PLASTICS (GRP) MHs.....	253
17.4 POLYETHYLENE (PE) MHs.....	253
17.5 POLYPROPYLENE (PP) MHs.....	253
17.6 TRENCH DRAINAGE AROUND MHs.....	253
17.7 COVERS.....	254
17.8 CONNECTIONS TO MHs.....	254
17.9 MH DROPS.....	254
17.10 LADDERS, STEP IRONS AND LANDINGS.....	254
18 MAINTENANCE CHAMBERS (MC), MAINTENANCE SHAFTS (MS AND TMS) AND INSPECTION OPENINGS (IO) OR INSPECTION SHAFTS (IS).....	255
18.1 GENERAL.....	255
18.2 SEALING CAPS.....	255
18.3 COVERS.....	255
18.4 CONNECTIONS TO MCs, MSs AND TMSs.....	255
19 PIPE EMBEDMENT AND SUPPORT.....	256
19.1 GENERAL.....	256
19.2 EMBEDMENT MATERIALS.....	256
19.3 COMPACTION OF EMBEDMENT.....	256
19.3.1 Methods.....	256
19.3.2 Compaction trials / Pre-qualification of embedment compaction method.....	257
19.3.2.1 General.....	257
19.3.2.2 Test method.....	257
19.3.2.3 Interpretation and applicability.....	257
19.3.3 Compaction control.....	257
19.4 SPECIAL BEDDING AND EMBEDMENTS / GEOTEXTILE SURROUND AND PILLOW.....	257
19.5 REMOVAL OF TRENCH SUPPORTS.....	258
19.6 CONCRETE EMBEDMENT AND ENCASEMENT.....	258
20 FILL.....	259
20.1 TRENCH FILL.....	259
20.1.1 General.....	259
20.1.2 Material requirements.....	259
20.1.2.1 Trafficable areas.....	259
20.1.2.2 Non-trafficable areas.....	260
20.1.3 Placement.....	260
20.1.4 Compaction of trench fill.....	260
20.2 EMBANKMENT FILL.....	261
20.3 DRIVES AND TUNNEL FILL.....	261
21 ACCEPTANCE TESTING.....	262
21.1 GENERAL.....	262
21.2 VISUAL INSPECTION—ABOVE-GROUND.....	262
21.3 COMPACTION TESTING.....	263
21.3.1 General.....	263
21.3.2 Compaction testing requirements.....	264
21.3.2.1 General.....	264

21.3.3 Embedment compaction testing.....	265
21.3.3.1 Applicable pipe sizes.....	265
21.3.3.2 Frequency and location of embedment tests.....	265
21.3.3.3 Retesting.....	265
21.3.4 Trench fill compaction testing.....	265
21.3.4.1 Trafficable test zone.....	265
21.3.4.2 Non-trafficable test zone.....	265
21.3.4.3 Test method.....	265
21.3.4.4 Frequency and location of tests.....	266
21.3.4.5 Retesting.....	266
21.3.5 Other fill compaction testing.....	266
21.3.5.1 General.....	266
21.3.5.2 Trafficable test zone.....	266
21.3.5.3 Non-trafficable test zone.....	266
21.3.5.4 Frequency and location of tests.....	266
21.3.5.5 Retesting.....	267
21.4 AIR PRESSURE AND VACUUM TESTING OF SEWERS.....	267
21.4.1 General.....	267
21.4.2 Air testing methods for sewers.....	267
21.4.2.1 Vacuum testing.....	267
21.4.2.2 Low pressure air testing.....	268
21.4.3 Testing of sewers >DN 1500.....	269
21.4.3.1 General.....	269
21.4.3.2 Method of test.....	269
21.4.4 Testing of non-pressure PE sewers.....	269
21.4.5 Testing of concrete MHs.....	269
21.4.5.1 General.....	269
21.4.5.2 Test method.....	270
21.5 INFILTRATION TESTING.....	271
21.6 DEFLECTION (OVALITY) TESTING OF FLEXIBLE SEWERS.....	271
21.6.1 General.....	271
21.6.2 Ovality proving tools.....	272
21.6.3 Flexible sewers \leq DN 300.....	272
21.6.4 Flexible sewers >DN 300.....	272
21.6.4.1 General.....	272
21.6.4.2 Flexible sewers >DN 300 and <DN 750.....	273
21.6.4.3 Flexible sewers \geq DN 750.....	274
21.7 MEASUREMENT OF SEWER GRADE.....	274
21.8 INTERNAL INSPECTION.....	274
21.9 INSPECTION AND TESTING OF THERMOPLASTICS LINED CONCRETE SEWERS AND MHs.....	274
21.9.1 Visual inspection.....	274
21.9.2 Spark testing.....	275
21.9.3 Locking key pull-out tests.....	275
21.10 PRESSURE TESTING OF INVERTED SYPHONS.....	275
21.10.1 General.....	275

21.10.2 Hydrostatic system test pressure.....	276
21.10.3 Satisfactory pressure test.....	276
21.10.4 WELD TESTING OF PE PIPES.....	276
22 TOLERANCES ON AS-CONSTRUCTED WORK.....	277
22.1 HORIZONTAL TOLERANCES.....	277
22.1.1 Sewers and on-line structures.....	277
22.1.2 Property connection sewers.....	277
22.2 VERTICAL TOLERANCES.....	277
22.2.1 Sewers and structures.....	277
22.2.2 Property connection risers and inspection openings.....	277
22.2.3 Grade.....	278
22.2.4 Verticality ("plumb").....	278
22.3 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS.....	278
22.4 TOLERANCES ON CAST IN-SITU CONCRETE STRUCTURES AND SLABS.....	279
23 CONNECTION TO EXISTING SEWERS.....	280
24 RESTORATION.....	281
24.1 GENERAL.....	281
24.2 PAVEMENTS.....	281
24.3 LAWNS.....	281
24.4 GRASSED AREAS.....	282
24.5 BUSHLAND.....	282
24.6 PROVISION FOR AND RECTIFICATION OF SETTLEMENT.....	282
24.7 MAINTENANCE OF RESTORED SURFACES.....	282
25 WORK AS CONSTRUCTED DETAILS.....	283
PART 3: STANDARD DRAWINGS.....	285
26 INTRODUCTION.....	285
26.1 GENERAL.....	285
26.2 DRAWING COMMENTARY.....	285
27 LIST OF DRAWINGS.....	286
28 COMMENTARY ON SEW-1100 SERIES – PIPELINE LAYOUT.....	289
28.1 GENERAL.....	289
28.2 SEW-1100, SEW-1101 AND SEW-1102 – DESIGN LAYOUTS.....	289
28.3 SEW-1103 – TYPICAL ARRANGEMENTS.....	289
28.4 SEW-1104 AND SEW-1105 – PROPERTY CONNECTION DETAILS.....	289
28.5 SEW-1106 AND SEW-1107 – PROPERTY CONNECTION DETAILS – METHODS.....	290
28.6 SEW-1108 – PROPERTY CONNECTION DETAILS – Y BRANCH AND AROUND OBSTRUCTIONS.....	291
28.7 SEW-1109 – PROPERTY CONNECTION DETAILS – PRIVATE PROPERTY.....	291
29 COMMENTARY ON SEW-1200 SERIES – EMBEDMENT AND TRENCH FILL.....	293
29.1 GENERAL.....	293
29.2 SEW-1201 – EMBEDMENT AND TRENCHFILL – TYPICAL ARRANGEMENTS.....	294
29.3 SEW-1202 – STANDARD EMBEDMENT FLEXIBLE AND RIGID PIPES.....	295
29.4 SEW-1203 – SPECIAL EMBEDMENT INADEQUATE FOUNDATIONS.....	295
29.5 SEW-1204 – SPECIAL EMBEDMENT SUPPORT USING PILES.....	295
29.6 SEW-1205 – SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS.....	295
29.7 SEW-1206 – BULKHEADS AND TRENCHSTOP.....	296

29.8 SEW-1207 – TRENCH DRAINAGE TYPICAL SYSTEMS.....	296
29.9 SEW-1208 – VERTICALS AND NEAR VERTICALS EXPOSED AND CONCEALED METHODS.....	296
30 COMMENTARY ON SEW-1300 SERIES – MAINTENANCE STRUCTURES.....	297
30.1 GENERAL.....	297
30.2 SEW-1300 – SEWERS ≤DN 300 PRECAST MH TYPES P1 AND P2.....	297
30.3 SEW-1301 – CAST IN-SITU MH TYPES C1 AND C2.....	297
30.4 SEW-1302 – MH PIPE CONNECTION DETAILS.....	297
30.5 SEW-1303 – SEWERS ≤DN 300 MH CHANGE IN LEVEL ARRANGEMENTS.....	298
30.6 SEW-1304 AND SEW-1305 – MH CHANNEL ARRANGEMENTS AND DETAILS.....	298
30.7 SEW-1306 – ALTERNATIVE MH DROP CONNECTIONS.....	298
30.8 SEW-1307 – STEP IRONS.....	298
30.9 SEW-1308– TYPICAL MH COVER ARRANGEMENTS.....	299
30.10 SEW-1309, SEW-1310, SEW-1311 AND SEW-1312– SPECIAL MHs.....	299
30.11 SEW-1311 AND SEW-1312– DEEP MHs.....	300
30.12 SW SEW-1313 – MH connection details PE and PP pipe.....	300
30.13 SEW-1314, SEW-1315, SEW-1316 AND SEW-1317 – MAINTENANCE SHAFTS.....	300
30.14 SEW-1350– TERMINAL MAINTENANCE SHAFT / RODDING POINT AT DEAD END OF PROPERTY CONNECTION SEWER.....	300
31 COMMENTARY ON SEW-1400 SERIES – SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS.....	301
31.1 GENERAL.....	301
31.2 SEW-1400 – SYPHON ARRANGEMENT.....	301
31.3 SEW-1401, SEW-1402-V AND SEW-1403 – BURIED CROSSINGS.....	301
31.4 SEW-1404, SEW-1405 AND SEW-1406 – AERIAL CROSSINGS.....	302
31.5 SEW-1407 AND SEW-1408 – VENTILATION SYSTEMS.....	302
31.6 SEW-1409, SEW-1410 AND SEW-1411 – WATER SEAL ARRANGEMENTS.....	302
31.7 SEW-1412 – EMERGENCY RELIEF STRUCTURES.....	303
31.8 SEW-1452– FLOW GAUGING MH.....	303
32 COMMENTARY ON SEW-1500 SERIES – INSERTIONS AND REPAIR SYSTEMS.....	304
32.1 GENERAL.....	304
32.2 SEW-1500 - CUT-IN METHODS.....	304
32.3 SEW-1501 – INSERTION OF JUNCTIONS.....	304
32.4 SEW-1502 – CONSTRUCTION OF MHs AND MSs OVER EXISTING SEWERS.....	304
32.5 SW SEW-1550-S, SEW-1551-S AND SEW-1552-S – INSTALLATION OF JUNCTIONS IN EXISTING SEWERS.....	305
33 LISTING OF STANDARD DRAWINGS.....	306
PIPELINE LAYOUT.....	306
Design Layouts.....	306
Pipelaying.....	309
Property Connection Details.....	310
EMBEDMENT / TRENCHFILL AND SUPPORT SYSTEMS.....	316
Soil Classification Guidelines And.....	316
Embedment and Trenchfill.....	317
Standard Embedment.....	318
Special Embedment.....	319

Trench Drainage.....	322
Verticals & Near Verticals.....	324
ACCESS STRUCTURES.....	325
Maintenance Holes.....	325
Maintenance Shafts.....	339
Terminal Maintenance Shaft.....	343
SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS.....	344
Buried Crossings.....	344
Aerial Crossings.....	348
Ventilation Systems.....	351
Water Seal Arrangements.....	353
Emergency Relief Structures.....	356
Ventilation Systems.....	357
CONNECTIONS TO EXISTING SYSTEMS.....	361
Insertions & Repair Systems.....	361
Install SS Junction Clamp, Pipework and Riser for Single Property Connection.....	364
Cut-in Junction, Pipework and Riser for Single Property Connection.....	366
APPENDICES.....	367
APPENDIX A — GENERIC INFRASTRUCTURE PROTECTION GUIDANCE.....	367
A1 INFRASTRUCTURE PROTECTION TREATMENTS - SELECTION AND DEFINITION.....	367
A2 RISK MANAGEMENT - INFRASTRUCTURE PROTECTION RISK ASSESSMENTS.....	367
A3 INFRASTRUCTURE PROTECTION DESIGN CONSIDERATIONS.....	367
A4 INFRASTRUCTURE PROTECTION TREATMENTS.....	368
A5 SECURITY DESIGN CONCEPTS.....	368
A6 ENVIROMENTAL DESIGN CONSIDERATIONS.....	368
A7 SEWER FAILURE IMPACT ASSESSMENT.....	369
A8 WATER AGENCY'S ENVIRONMENTAL AESTHETICS GUIDANCE.....	370
APPENDIX B — ESTIMATION OF EQUIVALENT POPULATION (EP).....	378
B1 GENERAL.....	378
B2 ESTIMATION METHOD.....	378
B2.1 Residential component.....	378
B2.1.1 Single occupancy lots.....	378
B2.1.2 Multiple occupancy lots—Medium density residential.....	378
B2.1.3 Multiple occupancy lots—High-density / multi-storey residential.....	379
B2.2 Commercial and special use components.....	379
B2.3 Industrial component.....	379
B2.3.1 General.....	379
APPENDIX C — FLOW ESTIMATION FOR DEVELOPMENT AREAS.....	381
C1 GENERAL.....	381
C2 PEAK DRY WEATHER (SANITARY) FLOW.....	381
C3 GWI CALCULATION.....	383
C4 RDI CALCULATION.....	383
C5 WORKED EXAMPLE FOR A RESIDENTIAL DEVELOPMENT.....	386
C5.1 <i>Description</i>	386
C5.2 <i>Peak dry weather flow (PDWF)</i>	386
C5.3 <i>Ground water infiltration (GWI)</i>	386

C5.4 Rainwater dependent inflow and infiltration (RDI).....	387
C5.5 Design flow.....	387
APPENDIX D — PROTECTION AGAINST DEGRADATION.....	389
D1 GENERAL.....	389
D2 PROTECTION AGAINST INTERNAL CORROSION.....	389
D3 PROTECTION AGAINST EXTERNAL AGGRESSIVE ENVIRONMENT.....	389
D4 PROTECTION AGAINST EXTERNAL CONTAMINATED GROUND.....	390
APPENDIX E — GUIDELINES FOR VENTILATION OF RETICULATION SEWERS.....	392
E1 INTRODUCTION.....	392
E2 VENTING OF RETICULATION SEWERS.....	393
E2.1 Consideration at the Planning Stage.....	393
E2.2 Location and spacing of educt and induct vents.....	393
E3 EDUCT VENT SHAFTS.....	394
E3.1 Types.....	394
E3.2 Design requirements.....	394
E3.2.1 Material selection.....	394
E3.2.2 General.....	394
E3.3 Educt vent cowls.....	395
E3.4 Installation limitations.....	395
E3.4.1 Guy-wire vents.....	395
E3.4.2 Post type vents.....	395
E3.4.3 Wall vents.....	395
E4 INDUCT VENT SHAFTS.....	395
E5 STANDARD DRAWINGS.....	396
APPENDIX F — TRENCHLESS TECHNOLOGIES.....	397
F1 GENERAL.....	397
F2 HORIZONTAL DIRECTIONAL DRILLING (HDD).....	397
F3 MICRO-TUNNELLING.....	397
F4 UNGUIDED BORING/THRUST BORING/AUGER BORING.....	398
F5 PIPE JACKING.....	398
F6 MINI-TUNNELLING.....	398
APPENDIX G — USE OF BENDS, FITTINGS AND MAINTENANCE SHAFTS/CHAMBERS.....	402
G1 GENERAL.....	402
G2 MAINTENANCE SHAFT AND MAINTENANCE CHAMBER BASE CONFIGURATIONS.....	404
G2.1 STANDARD MAINTENANCE SHAFT CONFIGURATIONS.....	404
G2.2 STANDARD MAINTENANCE CHAMBER CONFIGURATIONS.....	407
G3 NOTATION AND SYMBOLS FOR MAINTENANCE SHAFTS/CHAMBERS AND VARIABLE BENDS.....	409
G4 USE OF BENDS IN RETICULATION SEWERS.....	409
G4.1 VARIABLE-BEND USAGE.....	410
G4.1.1 General.....	410
G4.1.2 Variable bends - DWV PVC-U Pipes.....	410
G4.1.3 Minimum bend radii – DWV PVC-U bends.....	411
G4.1.4 Variable bend deflection limits – DWV PVC-U variable bends.....	411
G4.1.5 Polyethylene (PE) sweep bends.....	413
G4.1.6 Minimum bend radii - polyethylene (PE) sweep bends.....	414

G4.1.7 Typical PE sweep bend assembly.....	414
G4.2 MANUFACTURED-BEND USAGE.....	414
APPENDIX H — PROPERTY CONNECTION TYPES.....	415
H1 SCOPE.....	415
H2 TYPE 1 - PROPERTY CONNECTION SEWERS.....	415
H3 TYPE 2 - RISER PROPERTY CONNECTION SEWERS.....	416
H4 TYPE 3 - SLOPING RISER PROPERTY CONNECTION SEWERS.....	418
H5 TYPE 4 - VERTICAL RISER FOR PROPERTY CONNECTION SEWERS.....	418
H6 TYPE 5 - SLOPING RISER FOR PROPERTY CONNECTION SEWERS.....	419
H7 TYPE 6 - VERTICAL JUNCTION FOR PROPERTY CONNECTION SEWERS.....	419
H8 TYPE 7 - SPUR PROPERTY CONNECTION SEWERS.....	421
APPENDIX I — MAXIMUM DEPTH TO INVERT FOR STANDARD SUPPORT TYPES.....	423
I1 GENERAL.....	423
I2 STRUCTURAL DESIGN.....	423
I2.1 Flexible buried pipelines.....	423
I2.2 Precast concrete pipes pipelines.....	423
I2.3 Trench width dimensions.....	424
I3 EMBEDMENT MATERIAL.....	424
I4 TRENCH FILL.....	424
I5 COMPACTION.....	425
I6 MAXIMUM DEPTH TO INVERT FOR STANDARD SUPPORT TYPE.....	425
APPENDIX J — PIPELINES IN SLIP AND POTENTIALLY UNSTABLE AREAS.....	430
J1 INTRODUCTION.....	430
J2 SLIP AND UNSTABLE AREAS.....	430
J2.1 FACTORS INFLUENCING STABILITY OF SLOPES.....	431
J2.1.1 Soil and rock condition.....	431
J2.1.2 Angle of slope.....	431
J2.1.3 Groundwater and surface water.....	431
J2.1.4 Domestic development.....	431
J2.1.5 Vegetation.....	431
J2.1.6 Road construction.....	431
J3 IDENTIFICATION OF POTENTIALLY UNSTABLE AREAS.....	432
J4 PRECAUTIONS.....	432
J4.1 GRAVITY SEWERS AND PRESSURE MAINS.....	432
J4.1.1 Gravity sewers.....	432
J4.1.2 Pressure mains	433
J4.2 ALTERNATIVE SEWERAGE SYSTEMS AND CONSTRUCTION TECHNIQUES.....	435
J4.3 SHALLOW TRENCH OR ABOVE-GROUND CONSTRUCTION.....	435
J4.4 DESIGN FOR POSSIBLE GROUND MOVEMENT.....	436
J4.5 CONSIDER GROUNDWATER AND DRAINAGE.....	436
J4.6 PRECAUTIONS DURING CONSTRUCTION.....	437
APPENDIX K — OVALITY TESTING OF PVC AND GRP GRAVITY SEWERS DEFAULT PROVING TOOL DIAMETERS.....	439
K1 GENERAL.....	439
K2 REQUIREMENTS.....	439

APPENDIX L — SPECIFICATION FOR INTERNAL INSPECTION OF NEWLY CONSTRUCTED OR REHABILITATED SEWERS.....	441
L1 INTRODUCTION.....	441
L2 INSPECTION REQUIREMENTS.....	441
L3 QUALIFICATIONS OF INSPECTORS AND ACCEPTANCE ASSESSORS.....	441
L4 WORK AS CONSTRUCTED.....	442
L5 REPORTING SUMMARIES.....	442
L6 ACCEPTANCE INSPECTION REPORTS.....	443
L7 MATERIALS.....	444
L8 STEEL REINFORCED CONCRETE PIPE.....	444
L9 DEFORMATION OF FLEXIBLE CONDUITS.....	444
L10 LATERAL INSPECTION.....	445
L11 INSPECTION AT THE END OF DEFECTS LIABILITY PERIOD.....	445
L12 MANUFACTURING DEFECTS.....	445
L13 RISK ASSESSMENT AND RECTIFICATION.....	445
L14 ACCEPTANCE PARAMETERS.....	446
Definitions.....	458

List of Figures

Figure 2.1 DISAGGREGATION MODEL FOR TRANSPORTATION SUBSYSTEMS.....	74
Figure 3.1 FLOW COMPONENTS IN A GRAVITY SYSTEM.....	83
Figure 4.1 FLANGE FASTENER TIGHTENING SEQUENCE.....	90
Figure 5.1 PHYSICAL LOSSES IN CUSTOMER SANITARY DRAINS.....	129
Figure 5.2 DEPTH OF POINT OF CONNECTION AND USE OF RISERS.....	130
Figure 5.3 EXCESSIVELY DEEP CHANNELS CAUSED BY STEEP GRADES.....	134
Figure 5.4 INCOMING LEVEL ADJUSTED TO PREVENT DEEP CHANNEL.....	134
Figure 6.1 NOT USED.....	137
Figure 6.2 NOT USED.....	137
Figure 6.3 NOT USED.....	137
Figure 6.4 NOT USED.....	137
Figure 6.5 NOT USED.....	137
Figure 6.6 NOT USED.....	138
Figure 6.7 'TYPE 7 'SPUR' OR 'Y' PROPERTY SEWER CONNECTIONS - BURIED INTERFACE METHOD.....	140
Figure 7.1 SINGLE MS OR MC BETWEEN CONSECUTIVE MHS.....	145
Figure 7.2 NOT USED.....	145
Figure 7.3 NO MS OR MC BETWEEN LAST MH AND IS, TMS OR MCs.....	145
Figure 7.4 NOT USED.....	145
Figure 7.5 TYPICAL PRE-CAST MH BASE WITH PRE-FORMED BENCHING.....	149
Figure 7.6 TYPICAL PRE-CAST CONCRETE MH BASE WITH CONICAL BENCHING.....	149
Figure 7.7 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR VC, RC AND DI RRJ SEWERS.....	150
Figure 7.8 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR PVC RRJ SEWERS.....	150
Figure 7.9 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR PVC-U SCJ.....	151
Figure 7.10 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR VC AND GRP SLEEVED COUPLED SEWERS.....	151
Figure 7.11 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR PROFILE WALL PP SEWERS.....	151
Figure 7.12 TYPICAL CAST IN-SITU CONCRETE MH BASE FOR SOLID WALL PE SEWERS.....	152

Figure 7.13 TYPICAL CAST IN-SITU CONCRETE MH WITH EXTERNAL DROP PIPE (PVC-U DWV RRJ SEWER PIPE SHOWN).....	154
Figure 7.14 TYPICAL PRE-CAST CONCRETE MH WITH EXTERNAL DROP PIPE (PVC-U DWV RRJ SEWER PIPE SHOWN).....	155
Figure 7.15 TYPICAL CAST IN-SITU CONCRETE MH WITH INTERNAL DROP PIPE (PVC-U DWV SEWER PIPE SHOWN).....	156
Figure 7.16 TYPICAL MH BASE DESIGN.....	157
Figure 7.17 TYPICAL ARRANGEMENTS FOR THE CONNECTION OF PE SEWERS.....	160
Figure 7.18 TYPICAL ARRANGEMENTS FOR THE CONNECTION OF A PE MS TO PE SEWERS.....	161
Figure 7.19 TYPICAL PVC-U CAP ASSEMBLY AND FITTINGS.....	161
Figure 7.20 TYPICAL ARRANGEMENT FOR THE CONNECTION TO A PRE-CAST CONCRETE MC.....	162
Figure 7.21 TYPICAL PP MC AND MS CONNECTION DETAILS.....	162
Figure 7.22 TYPICAL TMS WITH PROPERTY CONNECTION AHEAD.....	164
Figure 7.23 TYPICAL PRE-CAST MC WITH HIGH-LEVEL CONNECTION.....	165
Figure 7.24 TYPICAL PE MC OR MS DROP DETAIL DIMENSIONS.....	166
Figure 7.25 TYPICAL PVC-U MS DROP DETAIL DIMENSIONS.....	167
Figure 7.26 TYPICAL PP MC/MS WITH HIGH-LEVEL CONNECTION.....	168
Figure 7.27 TYPICAL EXTERNAL SEWER DROP STRUCTURE TYPE A - 45° SLOPE JUNCTION.....	169
Figure 7.28 TYPICAL EXTERNAL SEWER DROP STRUCTURE TYPE B - 90° SLOPE JUNCTION.....	170
Figure 7.29 TERMINAL INSPECTION SHAFT – TYPE A.....	171
Figure 7.30 VERTICAL DROP INSPECTION SHAFT – TYPE B.....	171
Figure 7.31 INTERMEDIATE INSPECTION SHAFT – TYPE C.....	172
Figure 7.32 ACCESS REQUIREMENTS FOR SEWERS FROM JUNCTIONS.....	176
Figure 8.1 APPLICATION OF WATER SEAL ARRANGEMENTS.....	177
Figure 8.2 TYPICAL BOUNDARY TRAP AND SHAFT.....	178
Figure 8.3 NOT USED.....	179
Figure 8.4 NOT USED.....	180
Figure 8.5 NOT USED.....	180
Figure 8.6 NOT USED.....	180
Figure 8.7 NOT USED.....	180
Figure 8.8 NOT USED.....	180
Figure 8.9 NOT USED.....	180
Figure 8.10 NOT USED.....	180
Figure 8.11 NOT USED.....	185
Figure 8.12 NOT USED.....	185
Figure 8.13 NOT USED.....	188
Figure 8.14 NOT USED.....	188
Figure 8.15 NOT USED.....	188
Figure 9.1 TYPICAL ARRANGEMENT FOR BURIED FLEXIBLE PIPELINES.....	196
Figure 9.2 TYPE 1 SUPPORT FOR RIGID PIPES ONLY.....	197
Figure 9.3 TYPE 2 SUPPORT FOR RIGID PIPES ONLY.....	198
Figure 9.4 TYPE 3 SUPPORT FOR FLEXIBLE AND RIGID PIPES.....	198
Figure 9.5 TYPE 4 EMBEDMENT SUPPORT WITH GEOTEXTILE FILTER FABRIC FOR FLEXIBLE AND RIGID PIPES.....	200
Figure 9.6 TYPE 5 AND 6 SUPPORT UTILISING CONCRETE FOUNDATION.....	201

SEW-1303 Sewers \leq DN 300 Changes in Level Details.....	328
SEW-1304 For Sewers \leq DN 300 Typical Channel Arrangements.....	329
SEW-1305 Typical Channel Details.....	330
SEW-1306 Alternative Drop Connections.....	331
SEW-1307 Step Irons.....	332
SEW-1308 Typical MH Cover Arrangements.....	333
SEW-1309 Sewers DN 375 to DN 750.....	334
SEW-1310 Permanent Formwork \geq DN 375.....	335
SEW-1311 Depth to invert 6 m to 15 m.....	336
SEW-1312 DEPTH TO INVERT $>$ 15M.....	337
SEW-1313 MH Connection Details DN 110 to DN 450 PE Pipe.....	338
SEW-1314 Typical Installation.....	339
SEW-1315 MS & Variable Bend Installations.....	340
SEW-1316 TMS and Connection Installations.....	341
SEW-1317 Typical MS Cover Arrangements.....	342
SEW-1350 Rodding Point at End of Property.....	343
SEW-1400 Syphon Arrangement.....	344
SEW-1401 Railways.....	345
SEW-1402 Major Roadways.....	346
SEW-1403 Bored & Jacked Encasing Pipe Details.....	347
SEW-1404 Aqueduct.....	348
SEW-1405 Aqueduct Protection Grille.....	349
SEW-1406 Bridge Crossing Concepts.....	350
SEW-1407 Induct Vent.....	351
SEW-1408 Educt Vent.....	352
SEW-1409 Mains Type.....	353
SEW-1410 Maintenance Hole System.....	354
SEW-1411 Twin Maintenance Hole System.....	355
SEW-1412 Typical Arrangement DN 150 to DN 375.....	356
SEW-1451 Educt Ventshaft Base Block Details.....	357
SEW-1452 Channel, Inlet and Outlet Details.....	358
SEW-1455 CIRCULAR R.C. PIERS IN NON-FLOOD CONDITIONS FOR DN 150 TO 750 SEWERS.....	359
SEW-1456 EDUCT VENT SHAFT AND HOLDING DOWN BOLT DETAILS.....	360
SEW-1500 Cut-in Methods for Pipes.....	361
SEW-1501 Insertion of Junctions.....	362
SEW-1502 Maintenance Structures.....	363
SEW-1550 Stainless Steel Junction in Unlined VC and PVC Sewer.....	364
SEW-1551 Stainless Steel Junction in Lined VC Sewer.....	365
SEW-1552 Cut-in Junction in Unlined VC and PVC Sewer.....	366
Figure C.1 FLOW COMPONENTS IN A GRAVITY SYSTEM.....	381
Figure C.2 "d" FACTOR VERSUS EP – EP $<$ 50000.....	382
Figure C.3 "d" FACTOR VERSUS AREA - AREAS $<$ 1000 Ha.....	382
Figure G.1 TYPICAL VARIABLE BEND ADAPTORS.....	410
Figure G.2 TYPICAL VARIABLE BEND ASSEMBLY.....	411
Figure H.1 TYPE 1 RUN-IN PROPERTY CONNECTION SEWER.....	416
Figure H.2 TYPE 2 RISER PROPERTY CONNECTION SEWER.....	417

Figure H.3 TYPE 3 SLOPING RISER PROPERTY CONNECTION SEWER.....	418
Figure H.4 TYPE 4 VERTICAL JUMP-UP PROPERTY CONNECTION SEWER.....	418
Figure H.5 TYPE 5 SLOPING RISER FOR PROPERTY CONNECTION SEWER.....	419
Figure H.6 TYPE 6 VERTICAL JUNCTION FOR PROPERTY CONNECTION SEWER.....	420
Figure H.7 TYPE 7A SPUR RUN-IN PROPERTY CONNECTION SEWER.....	421
Figure H.8 TYPE 7B SPUR JUMP-UP PROPERTY CONNECTION SEWER.....	422
Figure H.9 TYPE 7C VERTICAL SPUR PROPERTY CONNECTION SEWER.....	422
Figure J.1 Example of Typical Talus Slopes.....	430
Figure J.2 CUT AND FILL SCENARIO.....	433
Figure J.3 POTENTIALLY UNSTABLE/LANDSLIP AREAS MONITORING PITS FOR DN 100 AND DN 150 RETICULATION MAINS IN ROAD RESERVES.....	434
Figure J.4 Example of an above ground constructed gravity sewerage system.....	435
Figure J.5 Groundwater.....	436
Figure J.6 Groundwater drainage.....	437
Figure L.1 Summary Report Template (blue text is example only).....	442

List of Tables

Table 1.1 ASSET CATEGORIES.....	67
Table 1.2 TYPICAL ASSET DESIGN LIFE.....	70
Table 1.3 PLANNING AND DESIGN APPROACH.....	71
Table 4.1 COLOUR IDENTIFICATION OF COMPONENTS IN RETICULATION SEWER SYSTEMS.....	85
Table 4.2 LIMITATIONS OF SEWAGE CHEMISTRY CONSTITUENTS FOR USE OF DIFFERENT TYPES OF CEMENT.....	89
Table 5.1 MAXIMUM LIMIT OF DEVIATION IN LEVEL AND LINE OF BOREHOLES AND TUNNELS.....	108
Table 5.2 MAXIMUM ALLOWABLE DEFLECTIONS THROUGH AN MH1.....	115
Table 5.3 CLEARANCES BETWEEN SEWERS AND OTHER UNDERGROUND SERVICES.....	118
Table 5.4 MINIMUM PIPE SIZES FOR RETICULATION AND PROPERTY CONNECTION SEWERS.....	119
Table 5.5 MAXIMUM CAPACITIES FOR GRAVITY SEWERS FOR VARIOUS LOCATIONS.....	120
Table 5.6 MANNING COEFFICIENT.....	123
Table 5.7 DESIGN MINIMUM GRADES.....	123
Table 5.8 MINIMUM GRADES FOR PROPERTY CONNECTION SEWERS.....	124
Table 5.9 MINIMUM GRADES FOR END-OF-LINE SEWERS.....	124
Table 5.10 MINIMUM COVER OVER SEWERS1.....	126
Table 5.11 MINIMUM INTERNAL FALL THROUGH AN MH JOINING RETICULATION SEWERS OF SAME DIAMETER.....	131
Table 5.12 LIMITATIONS ON LARGE FALLS AT MHs USING INTERNAL AND EXTERNAL DROPS.....	132
Table 5.13 STEEP SEWERS REQUIRING SPECIAL TREATMENT.....	133
Table 7.1 ACCEPTABLE MAINTENANCE STRUCTURE OPTIONS FOR RETICULATION AND PROPERTY CONNECTION SEWERS.....	143
Table 7.2 EXTERNAL MH DROP PIPE STRUCTURE.....	152
Table 7.3 ROCKER PIPE DIMENSIONS.....	153
Table 7.4 MINIMUM DROP HEIGHT DETAILS FOR PP.....	170
Table 7.5 GUIDE TO SELECTION OF MAINTENANCE STRUCTURE ACCESS COVERS, CLASS AND FINISHED SURFACE LEVELS.....	173
Table 8.1 REQUIREMENTS FOR VORTEX INLETS AND WATER CUSHIONS.....	183
Table 8.2 NOT USED.....	187

Table 9.1 SPECIAL CLASS CONCRETE GRADE SCC40 - CAST IN-SITU MHS.....	193
Table 9.2 STRUCTURAL CONCRETE GRADE SCC40 AND SCC50- PRE-CAST MHS.....	194
Table 9.3 REQUIREMENTS FOR BULKHEADS AND TRENCHSTOPS.....	209
Table 21.1 FLEXIBLE PIPES – MINIMUM COMPACTION EMBEDMENT, TRENCH FILL AND EMBANKMENT OF FLEXIBLE PIPES.....	263
Table 21.2 RIGID PIPES – MINIMUM COMPACTION EMBEDMENT, TRENCH FILL AND EMBANKMENT.....	264
Table 21.3 PRESSURE AND VACUUM AIR TESTING ACCEPTANCE TIMES FOR 7 kPa PRESSURE CHANGE.....	268
Table 21.4 CONCRETE MH TESTING FREQUENCY.....	270
Table 21.5 MINIMUM TEST TIMES FOR CONCRETE MHs.....	270
Table 21.6 MAXIMUM ALLOWABLE SHORT-TERM PIPE DEFLECTIONS.....	273
Table 22.1 SEWER GRADE TOLERANCES.....	278
Table 22.2 PROPERTY CONNECTION SEWER GRADE TOLERANCES.....	278
Table 28.1 MINIMUM RETICULATION AND PROPERTY CONNECTION SEWER SIZES.....	290
Table 29.1 MAXIMUM PARTICLE SIZE.....	295
Table A.1 ASSET CATEGORISATION AND INDICATIVE PROTECTIVE TREATMENT SCHEDULE.....	371
Table B.1 EQUIVALENT POPULATIONS FOR SYNCHRONOUS* DISCHARGES *Peaks coinciding with normal residential occupancies.....	379
Table C.1 LEAKAGE SEVERITY COEFFICIENT (C).....	384
Table C.2 APPROXIMATE VALUES OF I(1,39.35%) FOR VARIOUS LOCATIONS.....	385
Table C.3 CONTAINMENT FACTOR VERSUS AEP.....	386
Table F.1 GENERAL PERFORMANCE CHARACTERISTICS OF BOREHOLE AND TUNNELLING TECHNOLOGIES.....	399
Table G.1 OPERATIONAL, MAINTENANCE AND TESTING LIMITATIONS OF MC, MS AND TMS.....	402
Table G.2 MAINTENANCE SHAFT BASE CONFIGURATION.....	404
Table G.3 MAINTENANCE CHAMBER BASE CONFIGURATION.....	407
Table G.4 MINIMUM BEND RADII OF DWV PVC-U VARIABLE BENDS.....	411
Table G.5 DEFLECTION LIMITS OF DN 150 DWV PVC-U VARIABLE BENDS.....	411
Table G.6 VARIABLE BEND CUTTING TABLE DN150 DWV PVC-U PIPE.....	412
Table G.7 MINIMUM WALL BEND RADII OF PE SWEEP BENDS.....	414
Table H.1 MINIMUM RETICULATION AND PROPERTY CONNECTION SEWER SIZES.....	415
Table H.2 MINIMUM RISE FOR TYPE 1 PROPERTY CONNECTION SEWERS.....	416
Table H.3 MINIMUM RISE FOR TYPE 2 PROPERTY CONNECTION SEWERS.....	417
Table H.4 MINIMUM RISE FOR TYPE 4 PROPERTY CONNECTION SEWERS.....	418
Table H.5 MINIMUM RISE FOR TYPE 6 VERTICAL JUNCTIONS.....	420
Table I.1 MAXIMUM DEPTH TO INVERT FOR PVC SEWERS.....	426
Table I.2 MAXIMUM DEPTH TO INVERT FOR PVC SEWERS (including W7 & T44 wheel loads).....	426
Table I.3 MAXIMUM DEPTH TO INVERT FOR PP SEWERS.....	426
Table I.4 MAXIMUM DEPTH TO INVERT FOR PP SEWERS (including W7 & T44 wheel loads).....	427
Table I.5 MAXIMUM DEPTH TO INVERT FOR FW-GRP SEWERS.....	427
Table I.6 MAXIMUM DEPTH TO INVERT FOR FW-GRP SEWERS (including W7 & T44 wheel loads).....	427
Table I.7 MAXIMUM DEPTH TO INVERT FOR PE100.....	428
Table I.8 MAXIMUM DEPTH TO INVERT FOR PE100 SEWERS (including W7 & T44 wheel loads).....	428
Table K.1 PROVER OUTSIDE DIAMETER FOR PVC AND GRP PIPES.....	439
Table L.1 General Comment GC.....	445

Table L.2 ACCEPTANCE PARAMETERS FOR RIGID SEWERS – VITRIFIED CLAY, STEEL REINFORCED CONCRETE.....	446
Table L.3 ACCEPTANCE PARAMETERS FOR FLEXIBLE SEWER PIPES – PLASTICS (PVC, PE, PP, GRP), DUCTILE IRON AND STEEL.....	451
Table L.4 ACCEPTANCE CRITERIA - CONFIGURATION OF PIPEWORK AND FITTINGS – ALL SEWERS.....	455