



WATER SERVICES
ASSOCIATION OF AUSTRALIA

SEWERAGE CODE OF AUSTRALIA

Sydney Water Edition – Version 4 – 2017

Sydney
WATER



WATER SERVICES ASSOCIATION
of Australia

Sewerage Code of Australia

WSA 02—2002-2.2

Sydney Water Edition Version 4

Previous edition WSA 02—1999
Previous Sydney Water edition 3 July 2009

CONTENTS

PREFACE

INTRODUCTION

PART 0: GLOSSARY OF TERMS AND ABBREVIATIONS

I Glossary of Terms

II Abbreviations

III Referenced Documents

IV Other References

PART 1: PLANNING AND DESIGN

Contents

1 General

2 System Planning

3 Flow Estimation

4 Detail Design

5 Property Connection

6 Maintenance Structures

7 Ancillary Structures

8 Structural Design

9 Design Review and Drawings

Appendix A Estimation of Equivalent Population (EP)

Appendix B Flow Estimation for Undeveloped Areas

Appendix C Gauging of Sewer Overflows, Flows, Levels and Velocities

Appendix D Computer Flow Modelling

Appendix E Analysis of Flow Gauging Results from Existing Systems

PART 2: PRODUCTS AND MATERIALS

Contents

10 Products and Materials Overview

Appendix F Quality Assurance of Products and Materials

PART 3: CONSTRUCTION

Contents

11 General

12 Quality

13 General Construction

14 Products and Materials

15	Excavation
16	Bedding for Pipes and Maintenance Structures
17	Pipe Laying and Jointing
18	Maintenance Holes (MHs)
19	Maintenance Shafts (MS and TMS) and Inspection Shafts (IS)
20	Pipe Embedment and Support
21	Fill
22	Acceptance Testing
23	Tolerances on As-Constructed Work
24	Connections to Existing Sewers
25	Restoration
26	Work As Constructed Details
	Appendix G Ovality Testing of Gravity Sewers - Default Prover Diameters for PVC and GRP Pipes

PART 4: STANDARD DRAWINGS

Contents

27	Introduction
28	Listing of Standard Drawings
29	Commentary on SEW 1100 Series – Pipeline Layout
30	Commentary on SEW 1200 Series – Embedment and Trench Fill
31	Commentary on SEW 1300 Series – Maintenance Structures
32	Commentary on SEW 1400 Series – Special Crossings / Structures Arrangements
33	Commentary on SEW 1500 Series – Insertion and Repair Systems

STANDARD DRAWINGS

	SEW-1100 Series Drawings – Pipeline Layout
	SEW-1200 Series Drawings – Embedment, Trench Fill and Support Systems
	SEW-1300 Series Drawings – Access Structures
	SEW-1400 Series Drawings – Special Crossings / Structures Arrangements
	SEW-1500 Series Drawings – Connections to Existing Systems

SYDNEY WATER APPENDICES

SW 1	Environmental Management
SW 2	Sewers in Slip and Potentially Unstable Areas
SW 3	Drafting Requirements
SW 4	Pipe Sizing and Grading Tables



WATER SERVICES ASSOCIATION
of Australia

Sewerage Code of Australia

WSA 02—2002-2.2

Sydney Water Edition

Version 4

Part 1: Planning and Design

CONTENTS

1 GENERAL

- 1.1 SCOPE
- 1.2 PURPOSE AND APPLICATION
- 1.3 PLANNING AND DESIGN RESPONSIBILITIES AND INTERFACES
 - 1.3.1 General
 - 1.3.2 Planning responsibilities
 - 1.3.3 Design responsibilities
 - 1.3.4 Consultation with other parties
- 1.4 SEWER SYSTEM DESIGN APPROACH
 - 1.4.1 System design life
 - 1.4.2 Objectives of the system design
 - 1.4.3 Design output
 - SW 1.4.4 Safety in design

2 SYSTEM PLANNING

- 2.1 SEWERAGE SYSTEM PHILOSOPHY AND DEFINITION
 - 2.1.1 Disaggregation
 - 2.1.2 Level 1 Total system
 - 2.1.3 Level 2 Transportation subsystems
 - 2.1.4 Level 3 Operating units
 - 2.1.4.1 Sewers
 - 2.1.4.2 Sewage pumping stations (SPSs)
 - 2.1.4.3 Storage
- 2.2 PLANNING PRINCIPLES
 - 2.2.1 Planning horizon
 - 2.2.2 Concept Plan
 - 2.2.3 Catchment analysis
 - 2.2.4 Provision for future gauging needs
 - 2.2.5 Terrorism
- 2.3 PLANNING PARAMETERS
 - 2.3.1 Loading per serviced property
 - 2.3.2 Assessment of future loads
 - 2.3.3 Assessment of existing system loads
 - 2.3.4 Environmental considerations
 - 2.3.5 Geotechnical investigations
 - 2.3.6 Operations and maintenance considerations
- 2.4 SEWAGE QUALITY
 - 2.4.1 Septicity
 - 2.4.2 Sewage quality / Trade waste management
- 2.5 PLANNING REVIEW

3 FLOW ESTIMATION

- 3.1 DESIGN FLOW ESTIMATION
- 3.2 DESIGN FLOW ESTIMATION METHOD
 - 3.2.1 General
 - 3.2.2 Conventional design flow estimation method
 - 3.2.3 Design flow estimation incorporating existing systems
 - 3.2.4 Design flow estimation—Partially pumped systems
 - 3.2.5 Flow schedule
 - SW 3.2.5.1 Sydney Water Flow Schedule for conventional design approach
 - SW 3.2.5.2 Sydney Water Flow Schedule for Leaktight sewer design approach
 - SW 3.2.5.3 Sewer Layout and Flow Diagram
 - SW 3.2.5.4 Sewerage Flow Schedule Summary

4 DETAIL DESIGN

- 4.1 DETAIL DESIGN PROCESS
- 4.2 DETAIL DESIGN CONSIDERATIONS
 - 4.2.1 Catchment design
 - 4.2.2 Design accuracy
 - 4.2.3 Sewer layout
 - SW 4.2.3.2 Preferred gravity sewer location
 - SW 4.2.3.3 Alternative locations
 - SW 4.2.3.4 Industrial areas
 - SW 4.2.3.5 Sewers in basements
 - 4.2.4 Environmental considerations
 - 4.2.4.1 General
 - 4.2.4.2 Urban salinity
 - 4.2.4.3 Vegetation
 - 4.2.4.4 Contaminated sites
 - 4.2.4.5 Coastal / Tidal zones
 - 4.2.5 Easements
 - 4.2.6 Disused sewers
 - 4.2.7 Special design considerations
- 4.3 HORIZONTAL ALIGNMENT OF SEWERS
 - 4.3.1 General
 - 4.3.2 Roads, reserves and open space
 - 4.3.3 Railway reserves
 - 4.3.4 Public and private property
 - 4.3.5 Changes in direction using an MH
 - 4.3.6 Dead-ends
 - 4.3.7 Horizontal curves in sewers
 - SW 4.3.7.1 General
 - SW 4.3.7.2 Reticulation sewers
 - SW 4.3.7.3 Branch and trunk sewers
 - SW 4.3.7.4 Sewers \geq DN 900
- 4.4 OBSTRUCTIONS AND CLEARANCES
 - 4.4.1 General
 - 4.4.2 Surface obstructions
 - 4.4.3 Clearance from transmission towers and power lines
 - 4.4.4 Clearance from structures
 - 4.4.5 Underground obstructions and services
 - 4.4.5.1 General
 - 4.4.5.2 Clearance requirements
- 4.5 PIPE SIZING AND GRADING
 - 4.5.1 General
 - 4.5.2 Environmental protection requirements
 - 4.5.3 Minimum air space for ventilation
 - 4.5.4 Minimum pipe sizes for maintenance purposes
 - 4.5.5 Maximum EP for reticulation sewers
 - 4.5.6 Limitation on sewer size reduction
 - 4.5.7 Minimum grades for self-cleansing
 - 4.5.7.1 General
 - 4.5.7.2 Reticulation sewers
 - 4.5.7.3 Property connection sewers and ends of lines
 - 4.5.8 Minimum grades for slime control
 - 4.5.9 Maximum grades for septicity
 - 4.5.9.1 Branch and trunk sewers
 - 4.5.9.2 Reticulation sewers
- 4.6 VERTICAL ALIGNMENT OF SEWERS
 - 4.6.1 General
 - 4.6.2 Long section design plan
 - 4.6.3 Minimum cover over sewers

- 4.6.4 Lot servicing requirements
 - 4.6.4.1 General
 - 4.6.4.2 Serviced area requirements for residential lots
 - 4.6.4.3 Serviced area requirements for industrial and commercial lots
 - 4.6.4.4 Partial lot service
 - 4.6.4.5 Servicing of basements
- 4.6.5 Minimum depth of sewer connection point
 - 4.6.5.1 General
 - 4.6.5.2 Soffit requirement
 - SW 4.6.5.2.1 Surcharge areas
 - SW 4.6.5.2.2 service levels on private plumbing and below ground fixtures/basements
 - SW 4.6.5.2.3 boundary trap areas
 - 4.6.5.3 Physical losses in customer sanitary drains
 - 4.6.5.4 Depth of connection point
- 4.6.6 Grading through MHs
 - 4.6.6.1 General
 - 4.6.6.2 Internal fall through MHs joining sewers of same diameter
 - 4.6.6.3 Internal falls through MHs joining sewers of different diameters
 - 4.6.6.4 Large falls at MHs
 - 4.6.6.5 Effect of steep grades—hydraulic jumps
- 4.6.7 Vertical curves
- 4.6.8 Compound curves
- 4.7 CORROSION PREVENTION
 - 4.7.1 General
 - 4.7.2 Internal corrosion
 - 4.7.3 External corrosion
- 4.8 STEEL SEWERS
 - 4.8.1 Sizes and configurations
 - 4.8.2 Joints
 - 4.8.3 Field welding
 - 4.8.4 Flanged joints

5 PROPERTY CONNECTION

- 5.1 GENERAL
- 5.2 LIMITATIONS OF CONNECTION TO SEWERS
- 5.3 METHODS OF THE PROPERTY CONNECTION
 - 5.3.1 General
 - 5.3.2 IO interface method
 - 5.3.3 Buried interface method
 - SW 5.3.4 Modified buried interface method
- 5.4 MAXIMUM DEPTH OF PROPERTY CONNECTION
- 5.5 NUMBER OF PROPERTY CONNECTIONS
 - 5.5.1 Single occupancy lots
 - 5.5.2 Multiple occupancy lots
- 5.6 LOCATION OF CONNECTION POINTS
 - 5.6.1 Undeveloped lots
 - 5.6.2 Developed lots
- 5.7 NOT USED
- 5.8 PROPERTY CONNECTION SEWERS

6 MAINTENANCE STRUCTURES

- 6.1 TYPES OF MAINTENANCE STRUCTURES
- 6.2 LOCATIONS OF MAINTENANCE STRUCTURES
- 6.3 SPACING OF MAINTENANCE STRUCTURES
 - 6.3.1 General
 - 6.3.2 Maintenance structure spacing—Reticulation sewers
 - 6.3.3 Maintenance structure spacing—Branch and trunk sewers
- 6.4 SPECIAL CONSIDERATIONS FOR LOCATION OF MAINTENANCE STRUCTURES

6.5 SPECIAL CONSIDERATIONS FOR CONNECTION OF NEW SEWERS TO EXISTING SEWERS

6.6 MAINTENANCE HOLES (MH)

6.6.1 General

6.6.2 Types of MH construction

6.6.3 Design parameters for MHs

SW 6.6.3.1 Sewer connections to MHs

6.6.4 Property connections into MHs

6.6.5 Diameters of MHs

6.6.6 MH base layout

6.6.7 Flotation

6.6.8 Ladders, step irons and landings

6.6.9 MH covers

6.6.10 Cross-fall on MH covers

SW 6.6.11 MH adjustments

6.7 MAINTENANCE CHAMBERS (MC), MAINTENANCE SHAFTS (MS) AND TERMINAL MAINTENANCE SHAFTS (TMS)

6.7.1 General

6.7.2 Design parameters for MCs, MSs and TMSs

6.7.3 High-level connections to MCs, MSs and TMSs

SW 6.7.4 Connections to MCs, MSs and TMSs

SW 6.7.5 MC and MS adjustment

6.8 OTHER MAINTENANCE STRUCTURES AT INTERFACE OF PROPERTY CONNECTION SEWER AND CUSTOMER DRAINS

7 ANCILLIARY STRUCTURES

7.1 GENERAL

7.2 WATER SEALS, BOUNDARY TRAPS AND WATER-SEALED MHS

7.2.1 General design parameters

7.2.2 Water seals on reticulation sewers entering branch or trunk sewers

7.2.3 Not Used

7.3 NOT USED

7.3.1 Not Used

7.3.2 Not Used

SW 7.3.3 Flow gauging MH

SW 7.3.4 Infiltration checking MH

7.4 VERTICAL AND NEAR VERTICAL SEWERS

7.4.1 General

7.4.2 Design parameters for bored, exposed and encased vertical and near vertical sewers

7.5 VENTILATION

7.5.1 General

7.5.2 Design parameters for vents

7.6 NEAR-HORIZONTAL BOREHOLES

7.6.1 General

7.6.2 Design requirements

7.6.3 Maintenance requirements

7.7 VORTEX INLETS AND WATER CUSHIONS

7.8 INVERTED SYPHONS

7.8.1 General

7.8.2 Design parameters for inverted siphons

7.9 OVERFLOWS / EMERGENCY RELIEF STRUCTURES (ERS)

7.9.1 General

7.9.2 Design parameters for ERSs

SW 7.9.3 Overflow pipe

SW 7.9.4 Overflow level

7.10 FLOW MEASURING DEVICES

7.11 WET WEATHER STORAGE

- 7.11.1 General
- 7.11.2 Design requirements for wet weather storage

8 STRUCTURAL DESIGN

- 8.1 GENERAL
- 8.2 PRODUCTS AND MATERIALS
- 8.3 STRUCTURAL COMPUTATIONS
 - SW 8.3.1 Pipelines
 - SW 8.3.2 Maintenance holes
 - SW 8.3.2.1 Concrete requirements for cast in-situ MHs
 - SW 8.3.2.2 Concrete requirements for precast MHs
 - SW 8.3.2.3 Epoxy mortars for precast MHs
 - SW 8.3.2.4 Internal corrosion protection of MHs
 - SW 8.3.2.5 Pipe connections to MHs
- 8.4 EXTERNAL FORCES
- 8.5 FOUNDATION DESIGN AND GROUND WATER CONTROL
- 8.6 GEOTECHNICAL CONSIDERATIONS
 - 8.6.1 General
 - 8.6.2 Sewers in engineered or controlled fill
 - 8.6.3 Sewers in non-engineered fill
 - 8.6.4 Filling along route of pipeline
 - 8.6.5 Mine subsidence
 - SW 8.6.5.1 Extensions of or connections to existing DN 100 sewer
 - 8.6.6 Slip areas
 - 8.6.7 Water-charged ground
- 8.7 ABOVE GROUND CROSSINGS
- 8.8 PIPE COVER
- 8.9 TRENCH DESIGN
- 8.10 BULKHEADS AND TRENCHSTOPS

9 DESIGN REVIEW AND DRAWINGS

- 9.1 DESIGN REVIEW
- 9.2 DESIGN DRAWINGS
 - 9.2.1 General
 - 9.2.2 Real property information
 - 9.2.3 Sewers
 - 9.2.4 Structures
 - 9.2.5 Longitudinal sections (sewer profiles)
 - 9.2.6 Title block notation and standard notes
 - 9.2.7 Other
- 9.3 DRAFTING STANDARDS
 - 9.3.1 Scale
 - 9.3.2 Recording of as-constructed information

APPENDIX A ESTIMATION OF EQUIVALENT POPULATION (EP)

- A1 GENERAL
- A2 ESTIMATION METHOD
 - A2.1 Residential component
 - A2.1.1 Single occupancy lots
 - A2.1.2 Multiple occupancy lots—Medium density residential
 - A2.1.3 Multiple occupancy lots—High-density / multi-storey residential
 - A2.2 Commercial and special use components
 - A2.3 Industrial component
 - A2.3.1 General
 - A2.3.2 Use of Tables A2 and A3
- A3 WORKED EXAMPLE FOR AN INDUSTRIAL DEVELOPMENT

APPENDIX B FLOW ESTIMATION FOR UNDEVELOPED AREAS

- B1 GENERAL

B2 PEAK DRY WEATHER (SANITARY) FLOW

B3 GWI CALCULATION FOR CONVENTIONAL DESIGN APPROACH

B4 RDI CALCULATION FOR CONVENTIONAL DESIGN APPROACH

SW B4.1 Dilution factor (F) for Leaktight sewer design approach

SW B4.2 Flow Schedule for pipe size and grading using Leaktight design approach

B5 WORKED EXAMPLE FOR A RESIDENTIAL DEVELOPMENT FOR CONVENTIONAL DESIGN APPROACH

B5.1 Description

B5.2 Peak dry weather flow (PDWF)

B5.3 Ground water infiltration (GWI)

B5.4 Rainwater dependent inflow and infiltration (RDI)

B5.5 Design flow

SW B6 WORKED EXAMPLE FOR A RESIDENTIAL DEVELOPMENT FOR LEAKTIGHT SEWER DESIGN APPROACH

SW B6.1 Description

SW B6.2 Peak dry weather flow (PDWF)

SW B6.3 Design flow

APPENDIX C GAUGING OF SEWER OVERFLOWS, FLOWS, LEVELS AND VELOCITIES

C1 GENERAL

C2 PRE-CONSTRUCTED FLUMES AND WEIRS

C3 RETRO-FITTING OF DEVICES

C3.1 Flumes and weirs

C3.2 Doppler HVQ gauges

C3.3 Transit-time HVQ gauges

C3.4 Other HVQ type gauges

C3.5 Using “H-only” and a rating table at unrated structures

C3.6 Flumes and weirs in conjunction with HVQ gauges

C4 FULL PIPE METERS

C5 OVERFLOW EVENT RECORDERS

APPENDIX D COMPUTER FLOW MODELLING

APPENDIX E ANALYSIS OF FLOW GAUGING RESULTS FROM EXISTING SYSTEMS

E1 GENERAL

E2 PEAK DRY WEATHER FLOW (PLUS GROUNDWATER INFILTRATION)

E3 RAINFALL DEPENDENT INFLOW AND INFILTRATION (RDI)

TABLES

Table 1.1	Typical Aset Design Life
Table 1.2	Planning and Design Approach
Table 4.1	Maximum Allowable Change of Direction Through a MH
Table 4.2	Clearances Between Sewers and Other Underground Services
Table 4.3	Minimum Pipe Sizes for Reticulation and Property Connection Services
Table 4.4	Maximum EP for Reticulation Sewers
Table 4.5	Manning Coefficient
Table 4.6	Absolute Minimum Grades
Table 4.7	Minimum Grades for Property Connection Sewers and Permanent Ends
Table 4.8	Minimum Cover Over Sewers
Table 4.9	Minimum Internal Fall Through an MH Joining Reticulation Sewers

of Same Diameter

Table 4.10 Limitations on Large Falls at MHs Using Internal and External Drops

Table SW 4.11 Methods of Achieving Curved Sewers

Table SW 4.12 Steep Sewers Requiring Special Treatment

Table 6.1 Acceptable MH, MS and TMS Options for Reticulation Sewers

Table 7.1 Maximum Limit of Deviation in Level and Line of Boreholes

Table 7.2 Design Requirement for Silt Traps

Table 7.3 Requirements for Vortex Inlets and Water Cushions

Table 8.1 Requirements for Bulkheads

Table A1 Equivalent Populations for Synchronous Discharges

Table A2 Non-Synchronous Discharges – List of Industries and Their EP Classifications

Table A3 EP of Non-Residential EP/Ha Classifications

Table B1 Leakage Severity Coefficient (C)

Table B2 Approximate Values of $I_{(1,2)}$ for Various Locations

Table B3 Containment Factor Versus ARI

FIGURES

Figure 2.1 Disaggregation Model for Transportation Subsystems

Figure 3.1 Flow Components in a Gravity System

Figure 4.1 Physical Losses in Customer Sanitary Drains

Figure 4.2 Depth of Point of Connection and Use of Risers

Figure SW 5.1 Typical PCS Configurations

Figure 6.1 Multiple MCs or MSs Between MH and “Last” MH/TMS

Figure 6.2 Multiple MCs or MSs Between Consecutive MHs

Figure B1 “d” Peaking Factor Versus Area for Different EP Densities



WATER SERVICES ASSOCIATION
of Australia

Sewerage Code of Australia

WSA 02—2002-2.2

Sydney Water Edition

Version 4

Part 2: Products and Materials

CONTENTS

10 PRODUCTS AND MATERIALS OVERVIEW

- 10.1 PURPOSE
- 10.2 SCOPE
- 10.3 RESPONSIBILITIES
 - 10.3.1 Water Agency
 - 10.3.2 Designer
 - 10.3.3 Constructor
 - 10.3.4 Purchaser
- 10.4 PRODUCT AND MATERIAL STANDARDS AND SPECIFICATIONS
 - 10.4.1 Product standards
 - 10.4.2 Product specifications
 - 10.4.3 Product specifications—Alternatives
- 10.5 QUALITY ASSURANCE
 - 10.5.1 Default requirement
 - 10.5.2 Additional information on quality assurance
 - 10.5.3 Innovative products and materials
- 10.6 SELECTION GUIDE FOR PIPELINE SYSTEMS
- 10.7 ADDITIONAL PRODUCT AND MATERIAL INFORMATION

APPENDIX F QUALITY ASSURANCE OF PRODUCTS AND MATERIALS

- F1 GENERAL
- F2 QUALITY ASSURANCE OPTIONS
 - F2.1 ISO 9000 quality management system certification
 - F2.2 Product certification
 - F2.2.1 Product certification – Type 1
 - F2.2.2 Product certification – Type 3
 - F2.2.3 Product certification – Type 5
 - F2.3 Supplier's declaration of conformance
 - F2.4 Second party verification
- F3 FACTORS INFLUENCING SELECTION OF QUALITY ASSURANCE OPTIONS
 - F3.1 General factors
 - F3.2 Likelihood of manufacturing non-conformance
 - F3.3 Likelihood of failure of pipeline system from a product non-conformance
 - F3.4 Consequences of failure
 - F3.5 Product specification
 - F3.6 Project magnitude / management
 - F3.7 Innovative products
- F4 SELECTING THE QUALITY ASSURANCE OPTION
 - F4.1 General factors
 - F4.2 Product certification
 - F4.2.1 General
 - F4.2.2 Type 1
 - F4.2.3 Type 3
 - F4.2.4 Type 5
 - F4.3 ISO 9000 quality management system certification
 - F4.4 Supplier's declaration of conformance
 - F4.5 Second party verification

TABLES

- Table 10.1 [Guideline - Standard Pipe Sizes, Classes and Jointing Methods for Gravity Wastewater Pipes and Fittings](#)
- Table 10.2 Principal Sewerage Gravity Pipeline Systems - Precautions, Limitations Advantages and Disadvantages

Table 10.3 Principal Sewerage Pressure Pipeline Systems

Table 10.4 Principal Sewerage Pressure Pipeline Systems - Precautions, Limitations Advantages and Disadvantages



WATER SERVICES ASSOCIATION
of Australia

Sewerage Code of Australia

WSA 02—2002-2.2

Sydney Water Edition

Version 4

Part 3: Construction

CONTENTS

11 GENERAL

- 11.1 SCOPE
- 11.2 INTERPRETATION

12 QUALITY

- 12.1 QUALITY ASSURANCE
 - 12.1.1 General
 - 12.1.2 Quality system
 - 12.1.3 Project management plan
 - 12.1.4 Inspection and test plans
 - 12.1.5 Quality tests
 - 12.1.6 Quality audits
 - 12.1.7 Traceability
 - 12.1.8 Quality records
 - 12.1.9 Inspection
- 12.2 PERSONNEL QUALIFICATIONS

13 GENERAL CONSTRUCTION

- 13.1 GENERAL
- 13.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING
- 13.3 CONTRACT INTERFACES
- 13.4 CUSTOMER FOCUS
 - 13.4.1 General
 - 13.4.2 Resolution of complaints
- 13.5 PROTECTION OF PEOPLE, PROPERTY AND ENVIRONMENT
 - 13.5.1 Safety of people
 - 13.5.2 Protection of other services
 - 13.5.3 Disused / Redundant sewers
 - 13.5.4 Road reserves or other thoroughfares
 - 13.5.4.1 Treatment of pavements and other surfaces
 - 13.5.4.2 Traffic management
 - 13.5.4.3 Cleanliness of roads, paths, accesses and drainage paths
 - 13.5.4.4 Storage of products, materials and equipment
 - 13.5.4.5 Obstruction of street drainage
 - 13.5.5 Private and public properties
 - 13.5.6 Protection of the environment and heritage areas
 - 13.5.6.1 General
 - 13.5.6.2 Collection and disposal of wastes
 - 13.5.6.3 Protection of adjacent lands and vegetation
 - 13.5.6.4 Control of water pollution
 - 13.5.6.5 Acid sulphate and contaminated soils
 - 13.5.6.6 Control of noise and atmospheric pollution
 - SW 13.5.6.7 Equipment and machinery use in bush fire prone areas
 - SW 13.5.6.8 Recycled/Waste materials
- 13.6 AFFECTED PARTY NOTIFICATIONS
- 13.7 ALTERATION OF EXISTING SERVICES
- 13.8 SURVEY MARKS
- 13.9 CONSTRUCTION TOLERANCES
- 13.10 LATENT CONDITIONS

14 PRODUCTS AND MATERIALS

- 14.1 AUTHORISED PRODUCTS AND MATERIALS
- 14.2 REJECTED PRODUCTS AND MATERIALS
- 14.3 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS
 - 14.3.1 General
 - 14.3.2 Plastics-lined concrete products

14.4 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS

14.5 CONCRETE WORKS

14.5.1 Delivery

14.5.2 Transportation of concrete

14.5.3 Formwork

14.5.3.1 General

14.5.3.2 Formwork for plastics-lined concrete

14.5.4 Reinforcement

14.5.5 Placement

14.5.5.1 General

14.5.5.2 Placement in water

14.5.6 Slump

14.5.7 Compaction

14.5.8 Stripping

14.5.9 Curing

14.5.10 Repair of blemishes

14.6 SUPPLY OF WATER TO THE WORKS

14.7 ON-SITE STOCKPILES

15 EXCAVATION

15.1 SAFETY

15.2 LIMITS OF EXCAVATION

15.3 EXCAVATION ACROSS IMPROVED SURFACES

15.4 EXCAVATION IN ROOT ZONES

15.5 BLASTING

15.6 SUPPORT OF EXCAVATIONS

15.7 DRAINAGE AND DEWATERING

15.8 FOUNDATIONS AND FOUNDATION STABILISATION

15.9 SURPLUS EXCAVATED MATERIAL

16 BEDDING FOR PIPES AND MAINTENANCE STRUCTURES

16.1 TRENCH FLOOR PREPARATION

16.2 BEDDING MATERIALS

16.3 PLACEMENT OF BEDDING

16.4 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS

16.5 BEDDING FOR MAINTENANCE SHAFTS AND BENDS

16.6 BEDDING FOR MAINTENANCE HOLES

17 PIPE LAYING AND JOINTING

17.1 INSTALLATION OF PIPES

17.1.1 General

17.1.2 Cleaning, inspection and joint preparation

17.1.3 Polyethylene

17.1.4 Laying

17.2 HORIZONTAL AND VERTICAL CHANGE OF DIRECTION OF SEWERS

17.2.1 General

17.2.2 Methods of achieving change of direction in sewers

17.2.3 Horizontal curves

17.2.4 Vertical curves

17.2.5 Compound curves

17.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES

17.4 FLOTATION CONTROL

17.5 TRENCH STOPS

17.6 BULKHEADS

17.7 PROPERTY CONNECTION SEWERS

17.8 DEAD ENDS

17.9 PROPERTY CONNECTION POINTS AND DEAD ENDS

17.10 CORROSION PROTECTION OF CAST IRON

17.11 MARKING TAPES

- 17.11.1 Non-detectable marking tape
- 17.11.2 Detectable marking tape
- 17.12 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE
- 17.13 AQUEDUCTS
- 17.14 BRIDGE CROSSINGS
- 17.15 PLASTICS-LINED RC PIPE JOINTING
 - 17.15.1 General
 - 17.15.2 Plastics lining work protection
 - 17.15.3 Field jointing
 - 17.15.4 Plastics lining ancillary work
 - 17.15.4.1 Alignment of lining keys
 - 17.15.4.2 Provision of seepage channels
 - 17.15.4.3 Use of jointing accessories and adhesives
- 17.16 WELDING OF STEEL PIPELINES
 - 17.16.1 General
 - 17.16.2 Field welding of flanges

18 MAINTENANCE HOLES (MHS)

- 18.1 GENERAL
- 18.2 MH BASE
- 18.3 TRENCH DRAINAGE AROUND MHS
- 18.4 PRECAST CONCRETE MH SYSTEMS
- 18.5 CAST IN-SITU CONCRETE MH
- 18.6 BENCHING AND CHANNELS
- 18.7 CONCRETING FOR PLASTICS-LINED WORK
 - 18.7.1 Concrete work planning
 - 18.7.2 Fixing of plastics lining for concrete work
 - 18.7.3 Concrete placement and formwork removal
- 18.8 INTERNAL COATING OF CONCRETE MHS
- 18.9 COVERS
- 18.10 CONNECTIONS TO MHS
- 18.11 MH DROPS

19 MAINTENANCE SHAFTS (MS AND TMS) AND INSPECTION OPENINGS (IO)

- 19.1 GENERAL
- 19.2 SEALING CAPS
- 19.3 COVERS
- 19.4 CONNECTIONS TO MSS AND TMSS

20 PIPE EMBEDMENT AND SUPPORT

- 20.1 GENERAL
- 20.2 EMBEDMENT MATERIALS
- 20.3 COMPACTION OF EMBEDMENT
 - 20.3.1 Methods
 - 20.3.2 Compaction trials / Pre-qualification of embedment compaction method
 - 20.3.2.1 General
 - 20.3.2.2 Test method
 - 20.3.2.3 Interpretation and applicability
 - 20.3.3 Compaction control
- 20.4 SPECIAL BEDDING AND EMBEDMENTS / GEOTEXTILE SURROUND AND PILLOW
- 20.5 REMOVAL OF TRENCH SUPPORTS
- 20.6 CONCRETE EMBEDMENT AND ENCASEMENT

21 FILL

- 21.1 TRENCH FILL
 - 21.1.1 General
 - 21.1.2 Material requirements
 - 21.1.3 Compaction of trench fill
- 21.2 EMBANKMENT FILL
- 21.3 DRIVES AND TUNNEL FILL

22 ACCEPTANCE TESTING

22.1 GENERAL

22.2 VISUAL INSPECTION—ABOVE-GROUND

22.3 COMPACTION TESTING

22.3.1 General

22.3.2 Minimum compaction

22.3.3 Embedment compaction testing

22.3.3.1 Applicable pipe sizes

22.3.3.2 Frequency and location of embedment tests

22.3.3.3 Retesting

22.3.4 Trench fill compaction testing

22.3.4.1 Trafficable Test Zone

22.3.4.2 Non-trafficable test zone

22.3.4.3 Test method

22.3.4.4 Frequency and location of tests

22.3.4.5 Retesting

22.3.5 Other fill compaction testing

22.3.5.1 General

22.3.5.2 Trafficable test zone

22.3.5.3 Non-trafficable test zone

22.3.5.4 Frequency and location of tests

22.3.5.5 Retesting

22.4 AIR PRESSURE AND VACUUM TESTING OF SEWERS

22.4.1 General

22.4.2 Air testing methods for sewers

22.4.2.1 Vacuum testing

22.4.2.2 Low pressure air testing

22.4.3 Testing of sewers >DN 1500

22.4.3.1 General

22.4.3.2 Method of test

22.4.4 Testing of concrete MHs

22.4.4.1 General

22.4.4.2 Test method

22.5 INFILTRATION TESTING

22.6 DEFLECTION (OVALITY) TESTING OF FLEXIBLE SEWERS

22.6.1 General

22.6.2 Ovality proving tools

22.6.3 Flexible sewers \leq DN 300

22.6.4 Flexible sewers >DN 300

22.6.4.1 General

22.6.4.2 Flexible sewers >DN 300 and <DN 750

22.6.4.3 Flexible sewers \geq DN 750

22.7 CCTV INSPECTION

22.8 INSPECTION AND TESTING OF PLASTIC LINED CONCRETE SEWERS AND MHS

22.8.1 Visual inspection

22.8.2 Spark testing

22.8.3 Locking key pull-out tests

22.9 PRESSURE TESTING OF INVERTED SYPHONS

22.9.1 General

22.9.2 System test pressure

22.9.3 Maximum allowable loss

22.9.4 Test procedure

22.9.5 Satisfactory pressure test

22.9.6 Failure of test

SW 22.10 WELD TESTING OF PE PIPES

SW 22.11 PERFORMANCE VALIDATION

23 TOLERANCES ON AS-CONSTRUCTED WORK

23.1 HORIZONTAL TOLERANCES

23.1.1 Sewers and on-line structures (e.g. MHs, MSs, TMSs, vents)

23.1.2 Property connection sewers

23.2 VERTICAL TOLERANCES

23.2.1 Sewers and structures

23.2.2 Property connection risers and inspection openings

23.2.3 Grade

23.2.4 Verticality (“plumb”)

23.3 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS**23.4 CAST IN-SITU CONCRETE STRUCTURES AND SLABS****24 CONNECTION TO EXISTING SEWERS****25 RESTORATION**

25.1 GENERAL

25.2 PAVEMENTS

25.3 LAWNS

25.4 GRASSED AREAS

25.5 BUSHLAND

25.6 PROVISION FOR SETTLEMENT

25.7 MAINTENANCE OF RESTORED SURFACES

26 WORK AS CONSTRUCTED DETAILS**APPENDIX G QUALITY TESTING OF GRAVITY SEWERS - DEFAULT PROVER DIAMETERS FOR PVC AND GRP PIPES**

G1 GENERAL

G2 REQUIREMENTS

TABLES

Table 20.1	Maximum Particle Size
Table 22.1	Embedment of Flexible Pipes Minimum Compaction
Table 22.2	Embedment of Rigid Pipes Minimum Compaction
Table 22.3	Trench / Embankment Fill of Rigid and Flexible Pipes and Maintenance Structures – Minimum Compaction
Table 22.4	Pressure and Vacuum Air Testing Acceptance Times for 7 kPa Pressure Change
Table 22.5	Concrete MH Testing Frequency
Table 22.6	Minimum Test Times for Concrete MHs
Table 22.7	Maximum Allowable Short-Term Pipe Deflections
Table SW 22.8	CCTV Acceptance/Rejection Criteria for New Sewers
Table 23.1	Sewer Grade Tolerances
Table 23.2	Property Connection Sewer Grade Tolerances
Table G1	Prover Outside Diameter for PVC and GRP Pipes



WATER SERVICES ASSOCIATION
of Australia

Sewerage Code of Australia

WSA 02—2002-2.2

Sydney Water Edition
Version 4

Part 4: Standard Drawings

CONTENTS

27 INTRODUCTION

27.1 GENERAL

27.2 DRAWING COMMENTARY

SW 27.3 VARIED STANDARD DRAWINGS

SW 27.4 SUPPLEMENTARY (ADDITIONAL) DRAWINGS

SW 27.5 SYDNEY WATER REFERENCE DRAWINGS (SUPERSEDED WATER BOARD STANDARD SERIES)

28 LISTING OF STANDARD DRAWINGS

29 COMMENTARY ON SEW-1100 SERIES – PIPELINE LAYOUT

29.1 GENERAL

29.2 SEW-1100, SEW-1101 AND SEW-1102 – DESIGN LAYOUTS

29.2.1 SEW-1100 – Locality and site plan

29.2.2 SEW-1101 – Longitudinal sections

29.2.3 SEW-1102 – Schedule of Works

29.3 SEW-1103 – TYPICAL ARRANGEMENTS

29.4 SEW-1104 AND SEW-1105 – PROPERTY CONNECTION DETAILS

29.5 SEW-1106 AND SEW-1107 – PROPERTY CONNECTION DETAILS – METHODS

29.5.1 SEW-1106 – IO interface method

29.5.2 SEW-1107 – Buried interface method

29.6 SEW-1108 – PROPERTY CONNECTION DETAILS – Y BRANCH AND AROUND OBSTRUCTIONS

29.7 SEW-1109 – PROPERTY CONNECTION DETAILS – PRIVATE PROPERTY & MARKING SYSTEMS

SW 29.8 SEW-1150-S – SEWER SYMBOLS

SW 29.9 SEW-1151-S – DN 100 PVC-U PROPERTY CONNECTION ARRANGEMENT – INSTALL PIPEWORK/RISER FOR SINGLE PROPERTY CONNECTION

30 COMMENTARY ON SEW-1200 SERIES – EMBEDMENT AND TRENCH FILL

30.1 GENERAL

30.2 MAXIMUM DEPTH TO INVERT FOR STANDARD SUPPORT TYPES

30.3 SEW-1200 – SOIL CLASSIFICATION GUIDELINES

30.4 SEW-1201 – EMBEDMENT AND TRENCHFILL – TYPICAL ARRANGEMENTS

30.5 SEW-1202 – STANDARD EMBEDMENT FLEXIBLE AND RIGID PIPES

30.6 SEW-1203 – SPECIAL EMBEDMENT INADEQUATE FOUNDATIONS

30.7 SEW-1204 – SPECIAL EMBEDMENT SUPPORT USING PILES

30.8 SEW-1205-V – SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS

30.9 SEW-1206 – BULKHEADS AND TRENCHSTOP

30.10 SEW-1207-V – TRENCH DRAINAGE TYPICAL SYSTEMS

30.11 SEW-1208 – VERTICALS AND NEAR VERTICALS EXPOSED AND CONCEALED METHODS

SW 30.12 SEW-1250-S – STANDARD TRENCH DETAILS – RIGID PIPES (VC & RC)

SW 30.13 SEW-1251-S – STANDARD TRENCH DETAILS – FLEXIBLE PIPES (PVC-U, PP & GRP)

SW 30.14 SEW-1252-S – STANDARD TRENCH DETAILS – FLEXIBLE PIPES (PE)

31 COMMENTARY ON SEW-1300 SERIES – MAINTENANCE STRUCTURES

31.1 GENERAL

31.2 SEW-1300-V – SEWERS \leq DN 300 PRECAST MH TYPES P1 AND P2

31.3 SEW-1301-V – CAST IN-SITU MH TYPES C1 AND C2

31.4 SEW-1302-V – MH PIPE CONNECTION DETAILS

31.5 SEW-1303 – SEWERS \leq DN 300 MH CHANGE IN LEVEL ARRANGEMENTS

31.6 SEW-1304-V AND SEW-1305 – MH CHANNEL ARRANGEMENTS AND DETAILS

31.7 SEW-1306-V – ALTERNATIVE MH DROP CONNECTIONS

31.8 SEW-1307-V – STEP IRONS

- 31.9 SEW-1308-V – TYPICAL MH COVER ARRANGEMENTS
- 31.10 SEW-1309-V, SEW-1310, SEW-1311-V AND SEW-1312-V – SPECIAL MHS
- 31.10.1 SEW-1309-V – Sewers DN 375 to DN 750 MHS
- 31.10.2 SEW-1310 – Special MHS using permanent formwork
- 31.11 SEW-1311-V AND SEW-1312-V – DEEP MHS
- SW 31.11.1 SEW-1313-V – MH connection details PE and PP pipe
- 31.12 SEW-1314-V, SEW-1315, SEW-1316-V AND SEW-1317-V – MAINTENANCE SHAFTS

31.13 NOT USED

SW 31.14 SEW-1350-S – TERMINAL MAINTENANCE SHAFT / RODDING POINT AT DEAD END OF PROPERTY CONNECTION SEWER

SW 31.15 SEW-1351-S – SELECTION OF ACCESS COVERS

SW 31.16 SEW-1352-S – INSTALLATION, STEP IRONS FOR DN 150 – DN 300

32 COMMENTARY ON SEW-1400 SERIES – SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS

- 32.1 GENERAL
- 32.2 SEW-1400 – SYPHON ARRANGEMENT
- 32.3 SEW-1401, SEW-1402-V AND SEW-1403 – BURIED CROSSINGS
- 32.4 SEW-1404, SEW-1405 AND SEW-1406 – AERIAL CROSSINGS
- 32.5 SEW-1407 AND SEW-1408 – VENTILATION SYSTEMS
- 32.6 SEW-1409, SEW-1410 AND SEW-1411 – WATER SEAL ARRANGEMENTS
- 32.7 SEW-1412 – EMERGENCY RELIEF STRUCTURES
- SW 32.8 SEW-1451-S – VENTILATION SYSTEMS – EDUCT VENTSHAFT BASE BLOCK DETAILS
- SW 32.9 SEW-1452-S – FLOW GAUGING MH

33 COMMENTARY ON SEW-1500 SERIES – INSERTIONS AND REPAIR SYSTEMS

- 33.1 GENERAL
- 33.2 SEW-1500-V – CUT-IN METHODS
- 33.3 SEW-1501 – INSERTION OF JUNCTIONS
- 33.4 SEW-1502-V – CONSTRUCTION OF MHS AND MSS OVER EXISTING SEWERS
- SW 33.5 SEW-1550-S, SEW-1551-S AND SEW-1552-S – INSTALLATION OF JUNCTIONS IN EXISTING SEWERS

STANDARD DRAWINGS

TABLES

- Table 29.1 Minimum Reticulation and Property Connection Sewer Sizes
- Table 29.2 Equivalent Stiffness Classes for PVC Sewers
- Table 30.1 Maximum Depth to Invert for PVC Sewers
- Table 30.2 Maximum Depth to Invert for GRP Sewers
- Table 30.3 Maximum Depth to Invert for VC Sewers
- Table 30.4 Maximum Depth to Invert for RC Sewers
- Table 30.5 Maximum Particle Size
- Table SW 30.6 10 mm Graded Aggregate – Grading Requirements
- Table SW 30.7 Pipe Sizes Comparison – PE SDR 21 and PVC-U SN8