



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# GRAVITY SEWERAGE CODE OF AUSTRALIA

Version 3.1

WSA 02-2014

## CONTENTS

### PREFACE

### INTRODUCTION

### PART 0: GLOSSARY OF TERMS AND ABBREVIATIONS

I Glossary of Terms

II Abbreviations

III Referenced Documents

### PART 1: PLANNING AND DESIGN

Contents

1 General

2 System Planning

3 Flow Estimation

4 Products and Materials

5 Detail Design

6 Property Connection

7 Maintenance Structures

8 Ancillary Structures

9 Structural Design

10 Design Review and Drawings

### PART 2: CONSTRUCTION

Contents

11 General

12 General Construction

13 Products and Materials

14 Excavation

15 Bedding for Pipes and Maintenance Structures

16 Pipe Laying and Jointing

17 Maintenance Holes (MHs)

18 Maintenance Shafts (MS and TMS), Maintenance Chambers (MC and Inspection Openings (IO) or Inspection Shafts (IS)

19 Pipe Embedment and Support

20 Fill

21 Acceptance Testing

22 Tolerances on As-Constructed Work

23 Connections to Existing Sewers

24 Restoration

25 Work As Constructed Details

**GRAVITY SEWERAGE CODE OF AUSTRALIA VERSION 3.1****APPENDICES**

Appendix A	Generic Infrastructure Protection Guidance
Appendix B	Estimation of Equivalent Population
Appendix C	Flow Estimation for Undeveloped Population
Appendix D	Protection Against Degradation
Appendix E	Ventilation of Reticulation Sewers Guidelines
Appendix F	Trenchless Technologies
Appendix G	Use of Bends, Fittings and Maintenance Shafts/Chambers
Appendix H	Property Connection Types
Appendix I	Maximum Depth to Invert for Standard Support Types
Appendix J	Pipelines in Slip and Potentially Unstable Areas
Appendix K	Ovality Testing of Gravity Sewers
Appendix L	Specification for Internal Inspection



# PART 1: PLANNING AND DESIGN

Gravity Sewerage Code of Australia  
Version 3.1

WSA 02-2014

## CONTENTS

### 1 GENERAL

- 1.1 SCOPE
- 1.2 PLANNING AND DESIGN
  - 1.2.1 Objectives
  - 1.2.2 Scope and requirements
  - 1.2.3 Servicing strategies
  - 1.2.4 Functional design requirements
  - 1.2.5 Concept plan format
  - 1.2.6 Critical infrastructure protection
    - 1.2.6.1 General
    - 1.2.6.2 Asset categorisation
    - 1.2.6.3 All hazards – Infrastructure protection
  - 1.2.7 Detailed design
    - 1.2.7.1 Designer’s needs and responsibilities
    - 1.2.7.2 Requirements to be addressed
    - 1.2.7.3 Design outputs
    - 1.2.7.4 Safety in design
- 1.3 CONSULTATION WITH OTHER PARTIES
  - 1.3.1 Design life
  - 1.3.2 Instrumentation and control systems

### 2 SYSTEM PLANNING

- 2.1 GENERAL
- 2.2 SEWER SYSTEM PHILOSOPHY AND DEFINITION
  - 2.2.1 Disaggregation
  - 2.2.2 Level 1 Total system
  - 2.2.3 Level 2 Transportation subsystems
  - 2.2.4 Level 3 operating units
    - 2.2.4.1 Sewers
    - 2.2.4.2 Sewage pumping stations (SPSs)
    - 2.2.4.3 Storage
- 2.3 PLANNING PRINCIPLES
  - 2.3.1 Planning horizon
  - 2.3.2 Concept plan
  - 2.3.3 Catchment analysis
  - 2.3.4 Provision for future gauging needs
- 2.4 PLANNING PARAMETERS
  - 2.4.1 Loading per serviced lot
  - 2.4.2 Estimating future catchment loads
  - 2.4.3 Estimating existing system loads
  - 2.4.4 Climate change impacts
  - 2.4.5 Environmental, cultural and heritage impacts
  - 2.4.6 Geotechnical investigations
  - 2.4.7 Contaminated sites
  - 2.4.8 Operations and maintenance considerations
  - 2.4.9 Sewer mining
- 2.5 SEWAGE QUALITY
  - 2.5.1 Septicity
  - 2.5.2 Australian sewage quality management guidelines
- 2.6 PLANNING REVIEW

### 3 FLOW ESTIMATION

- 3.1 GENERAL
- 3.2 DESIGN FLOW ESTIMATION
- 3.3 DESIGN FLOW ESTIMATION METHOD
  - 3.3.1 General

- 3.3.2 Traditional design flow estimation method
- 3.3.3 Design flow estimation incorporating existing systems
- 3.3.4 Design flow estimation—Partially pumped systems
- 3.3.5 Flow schedule

## **4 PRODUCTS AND MATERIALS**

- 4.1 GENERAL
- 4.2 IDENTIFICATION OF SEWER SYSTEMS
- 4.3 SERVICABILITY OF SEWER SYSTEMS
- 4.4 PROTECTION AGAINST DEGRADATION
- 4.5 DUCTILE IRON GRAVITY SEWERS
  - 4.5.1 Product Specifications
  - 4.5.2 Sizes and configurations
  - 4.5.3 Cement mortar lining
  - 4.5.4 Sleeving
- 4.6 PVC GRAVITY SEWERS
  - 4.6.1 Product Specifications
  - 4.6.2 Sizes and configurations
- 4.7 POLYETHYLENE GRAVITY SEWERS
  - 4.7.1 Product Specifications
  - 4.7.2 Sizes and configurations
- 4.8 POLYPROPYLENE GRAVITY SEWERS
  - 4.8.1 Product Specifications
  - 4.8.2 Sizes and configurations
- 4.9 GRP GRAVITY SEWERS
  - 4.9.1 Product Specifications
  - 4.9.2 Sizes and configurations
- 4.10 PLASTICS-LINED CONCRETE GRAVITY SEWERS
  - 4.10.1 Product Specifications
  - 4.10.2 Sizes and configurations
- 4.11 VITRIFIED CLAY SEWERS
  - 4.11.1 Product Specifications
  - 4.11.2 Sizes and configurations
- 4.12 STEEL GRAVITY SEWERS
  - 4.12.1 Product Specifications
  - 4.12.2 Sizes and configurations
  - 4.12.3 Joints
  - 4.12.4 Field welding
  - 4.12.5 Flanged joints
- 4.13 MAINTENANCE STRUCTURES
  - 4.13.1 Product Specifications
  - 4.13.2 Classification and application
  - 4.13.3 Sizes and configurations
- 4.14 MARKING TAPES
  - 4.14.1 Product Specifications
  - 4.14.2 Application
- 4.15 ACCESS COVERS AND FRAMES
  - 4.15.1 Product Specifications
  - 4.15.2 Application
  - 4.15.3 Cast iron access covers and frames
  - 4.15.4 Macro-composite access covers and frames
  - 4.15.5 Thermoplastic access covers and frames
  - 4.15.6 Size and configuration
  - 4.15.7 Marking of access covers and frames
- 4.16 VENT SHAFTS
  - 4.16.1 Product Specifications
  - 4.16.2 Application

## **5 DETAIL DESIGN**

### **5.1 DETAIL DESIGN PROCESS**

### **5.2 DETAIL DESIGN CONSIDERATIONS**

#### 5.2.1 Catchment design

#### 5.2.2 Design accuracy

#### 5.2.3 Sewer layout

#### 5.2.4 Location of sewers

##### 5.2.4.1 General

##### 5.2.4.2 Sewers located along side boundaries

##### 5.2.4.3 Sewers located along rear boundaries

##### 5.2.4.4 Sewers located in small lots (lot area $\leq 450 \text{ m}^2$ )

##### 5.2.4.5 Sewers servicing industrial /commercial lots

##### 5.2.4.6 Branch and trunk sewers

#### 5.2.5 Trenchless techniques for pipe installation

#### 5.2.6 Near-horizontal boreholes and tunnels

##### 5.2.6.1 General

##### 5.2.6.2 Design requirements

##### 5.2.6.3 Silt traps

#### 5.2.7 Environmental, cultural and heritage considerations

##### 5.2.7.1 General

##### 5.2.7.2 Urban salinity

##### 5.2.7.3 Acid sulphate soils

##### 5.2.7.4 Vegetation

##### 5.2.7.5 Coastal zones

#### 5.2.8 Easements

#### 5.2.9 Disused sewers

#### 5.2.10 Special design considerations

### **5.3 HORIZONTAL ALIGNMENT OF SEWERS**

#### 5.3.1 General

#### 5.3.2 Roads, reserves and open space

#### 5.3.3 Railway reserves

#### 5.3.4 Waterways

#### 5.3.5 Maintenance structures and vent shafts

#### 5.3.6 Changes in direction using an MH

#### 5.3.7 Changes in direction using an MS or MC

#### 5.3.8 Horizontal curves in sewers

##### 5.3.8.1 General

##### 5.3.8.2 Use of manufactured and variable bends in reticulation sewers

##### 5.3.8.3 Cumulative deflection using pipe joints

### **5.4 OBSTRUCTIONS AND CLEARANCES**

#### 5.4.1 General

#### 5.4.2 Surface obstructions

#### 5.4.3 Clearance from transmission towers and power lines

#### 5.4.4 Clearance from structures

#### 5.4.5 Underground obstructions and services

##### 5.4.5.1 General

##### 5.4.5.2 Clearance requirements

#### 5.4.6 Marker posts

### **5.5 PIPE SIZING AND GRADING**

#### 5.5.1 General

#### 5.5.2 Environmental protection requirements

#### 5.5.3 Minimum air space

#### 5.5.4 Minimum pipe sizes for maintenance purposes

#### 5.5.5 Maximum ET for reticulation sewers

##### 5.5.5.1 General

##### 5.5.5.2 Design assumptions

#### 5.5.6 Limitation on sewer size reduction

- 5.5.7 Minimum grades for self-cleansing
  - 5.5.7.1 General
  - 5.5.7.2 Reticulation sewers
  - 5.5.7.3 Property connection sewers and end-of-line sewers
- 5.5.8 Minimum grades for slime control
- 5.5.9 Maximum grades
  - 5.5.9.1 Branch and trunk sewers
  - 5.5.9.2 Reticulation sewers
- 5.6 VERTICAL ALIGNMENT OF SEWERS
  - 5.6.1 General
  - 5.6.2 Long section design plan
  - 5.6.3 Minimum cover over sewers
  - 5.6.4 Lot servicing requirements
    - 5.6.4.1 General
    - 5.6.4.2 Serviced area requirements for residential lots
    - 5.6.4.3 Serviced area requirements for industrial and commercial lots
    - 5.6.4.4 Partial lot service
    - 5.6.4.5 Servicing of basements
    - 5.6.4.6 Servicing of developed lots
  - 5.6.5 Minimum depth of sewer connection point
    - 5.6.5.1 General
    - 5.6.5.2 Soffit requirement
    - 5.6.5.3 Physical losses in customer sanitary drains
    - 5.6.5.4 Depth of connection point
  - 5.6.6 Grading through MHs
    - 5.6.6.1 General
    - 5.6.6.2 Internal fall through MHs joining sewers of same diameter
    - 5.6.6.3 Internal falls through MHs joining sewers of different diameters
    - 5.6.6.4 Major sewer junctions
    - 5.6.6.5 Large falls at MHs
    - 5.6.6.6 Avoiding hydraulic jumps due to steep grades
    - 5.6.6.7 Avoiding deep channels in MHs due to steep grades
  - 5.6.7 Vertical curves in sewers
  - 5.6.8 Compound curves

## **6 PROPERTY CONNECTION**

- 6.1 GENERAL
- 6.2 LIMITATIONS OF CONNECTION TO SEWERS
- 6.3 METHODS OF THE PROPERTY CONNECTION
  - 6.3.1 General
  - 6.3.2 IO interface method
  - 6.3.3 Buried interface method
  - 6.3.4 Typical layouts of sewers and general arrangements for property connection sewers
  - 6.3.5 Maximum depth of property connection point
- 6.4 NUMBER OF PROPERTY CONNECTION POINTS
  - 6.4.1 Single occupancy lots
  - 6.4.2 Multiple occupancy lots
- 6.5 LOCATION OF PROPERTY CONNECTION POINTS
  - 6.5.1 General
  - 6.5.2 Vacant lots
  - 6.5.3 Lots with existing buildings
- 6.6 PROPERTY CONNECTION SEWERS
  - 6.6.1 General
  - 6.6.2 'Type 7 spur' or 'Y' property sewer connections
- 6.7 LENGTH OF PROPERTY CONNECTION SEWERS

## **7 MAINTENANCE STRUCTURES**

- 7.1 TYPES OF MAINTENANCE STRUCTURES



**7.2 LOCATIONS OF MAINTENANCE STRUCTURES****7.3 SPACING OF MAINTENANCE STRUCTURES**

## 7.3.1 General

## 7.3.2 Maintenance structure spacing—Reticulation sewers

## 7.3.3 Maintenance structure spacing—Branch and trunk sewers

**7.4 SPECIAL CONSIDERATIONS FOR LOCATION OF MAINTENANCE STRUCTURES****7.5 SPECIAL CONSIDERATIONS FOR CONNECTION OF NEW SEWERS TO EXISTING SEWERS****7.6 MAINTENANCE HOLES (MHS)**

## 7.6.1 General

## 7.6.2 Types of MH construction

## 7.6.3 Design parameters for MHs

## 7.6.4 Design requirements for connection of sewers to MHs

## 7.6.4.1 Pre-cast concrete MH base units

## 7.6.4.2 Cast in-situ concrete MH base units

## 7.6.4.3 Rocker pipes

## 7.6.5 Connection of property connection sewers into MHs

## 7.6.6 MH drops

## 7.6.7 Diameters of MHs

## 7.6.8 MH base layout

## 7.6.9 Ladders, step irons and landings

**7.7 MAINTENANCE SHAFTS (MSS) / MAINTENANCE CHAMBERS (MCS)**

## 7.7.1 General

## 7.7.2 Design parameters for MCs, MSs and TMSs

## 7.7.3 Connections to MCs, MSs and TMSs

## 7.7.3.1 Connections to PE MSs and TMSs

## 7.7.3.2 Connections to pre-cast concrete MC base units

## 7.7.3.3 Connections to PP MCs and MSs

## 7.7.4 High-level connections to MCs, MSs and TMSs

## 7.7.4.1 High-level connections into a pre-cast concrete MC

## 7.7.4.2 High-level connections into a PE MC and MS

## 7.7.4.3 High-level connections into a PVC-U MS

## 7.7.4.4 High-level connections into a PP MC and MS

**7.8 INSPECTION SHAFTS (ISS)**

## 7.8.1 General

## 7.8.2 Terminal inspection shaft (Type A)

## 7.8.3 Vertical drop inspection shaft (Type B)

## 7.8.4 Intermediate inspection shaft (Type C)

## 7.8.5 Ends of pipe

## 7.8.5.1 Temporary ends of pipe

## 7.8.5.2 Permanent ends of pipe

**7.9 MAINTENANCE STRUCTURE COVERS**

## 7.9.1 General

## 7.9.2 Cross-fall on MH covers

## 7.9.3 Modifications to existing maintenance holes

**7.10 SEWERS FROM JUNCTIONS****7.11 OTHER MAINTENANCE STRUCTURES AT INTERFACE OF PROPERTY CONNECTION SEWERS AND SANITARY DRAINS****8 ANCILLIARY STRUCTURES****8.1 GENERAL****8.2 WATER SEALS, BOUNDARY TRAPS, WATER-SEALED MHS AND GAS CHECK MHS**

## 8.2.1 Boundary traps on sanitary drains

## 8.2.1.1 General

## 8.2.1.2 Responsibility for installation of boundary traps

## 8.2.2 Water seals, water-sealed MHs and gas check MHs

## 8.2.2.1 General

- 8.2.2.2 Water seals on reticulation sewers entering branch or trunk sewers
- 8.2.2.3 Water seals on branch sewers entering trunk sewers
- 8.2.3 Water-sealed MHs and gas check MHs
  - 8.2.3.1 General
  - 8.2.3.2 Water-sealed MHs
  - 8.2.3.3 Gas check MHs
- 8.3 VERTICAL AND NEAR VERTICAL SEWERS
  - 8.3.1 General
  - 8.3.2 Design parameters for bored, exposed and encased vertical and near vertical sewers
- 8.4 VENTILATION
  - 8.4.1 General
  - 8.4.2 Design parameters for ventilation and location of vent shafts
  - 8.4.3 Design details for ventilation lines, vent shafts and cowls
- 8.5 VORTEX INLETS AND WATER CUSHIONS
- 8.6 INVERTED SYPHONS
  - 8.6.1 General
  - 8.6.2 Design parameters for inverted syphons
- 8.7 EMERGENCY RELIEF STRUCTURES
  - 8.7.1 General
  - 8.7.2 Design parameters for ERSs
    - 8.7.2.1 General
    - 8.7.2.2 Configuration
    - 8.7.2.3 Overflow pipe
    - 8.7.2.4 Overflow level
- 8.8 FLOW MEASURING DEVICES
  - 8.8.1 General
  - 8.8.2 Within the sewer system
  - 8.8.3 At a sewage pumping station
- 8.9 WET WEATHER STORAGE
  - 8.9.1 General
  - 8.9.2 Design considerations

## **9 STRUCTURAL DESIGN**

- 9.1 GENERAL
- 9.2 PRODUCTS AND MATERIALS
- 9.3 STRUCTURAL CONSIDERATIONS
  - 9.3.1 Pipes
  - 9.3.2 Design factors affecting buried flexible and rigid pipes
  - 9.3.3 Maintenance structures
- 9.4 LOADINGS
  - 9.4.1 External forces
  - 9.4.2 Native soil strength
  - 9.4.3 Embedment zone dimensions
  - 9.4.4 Pipe embedment
  - 9.4.5 Buoyancy
  - 9.4.6 Flotation
- 9.5 FOUNDATION DESIGN AND GROUNDWATER CONTROL
  - 9.5.1 Migration of fines
- 9.6 GEOTECHNICAL CONSIDERATIONS
  - 9.6.1 General
  - 9.6.2 Pipelines in engineered or controlled fill
  - 9.6.3 Pipelines in non-engineered fill
  - 9.6.4 Filling along route of pipeline
  - 9.6.5 Mine subsidence
  - 9.6.6 Slip areas
  - 9.6.7 Water-charged ground
- 9.7 SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS

- 9.7.1 General
- 9.7.2 Requirements
- 9.8 ABOVE GROUND CROSSINGS
- 9.9 PIPE COVER
- 9.10 BULKHEADS AND TRENCHSTOPS
- 9.11 TRENCH DRAINAGE

## **10 DESIGN REVIEW AND DRAWINGS**

- 10.1 DESIGN REVIEW
- 10.2 DESIGN DRAWINGS
  - 10.2.1 General
  - 10.2.2 Composition of Design Drawings
  - 10.2.3 Scale
  - 10.2.4 Real property information
  - 10.2.5 Sewers
  - 10.2.6 Structures
  - 10.2.7 Longitudinal sections (profiles)
  - 10.2.8 Title block notation and standard notes
  - 10.2.9 Other
- 10.3 SEWER SYSTEM ACRONYMS
- 10.4 SPECIFICATIONS
- 10.5 RECORDING OF WORK AS CONSTRUCTED INFORMATION

## **TABLES**

Table 1.1	Asset Categories
Table 1.2	Typical Asset Design Life
Table 1.3	Planning and Design Approach
Table 4.1	Colour Identification of Components in Reticulation Sewer Systems
Table 4.2	Limitations of Sewage Chemistry Constituents for Use of Different Types of Cement
Table 5.1	Maximum Limit of Deviation in Level and Line of Boreholes and Tunnels
Table 5.2	Maximum Allowable Deflections Through an MH
Table 5.3	Methods of Achieving Curved Sewers
Table 5.4	Clearances Between Sewers and Other Underground Services
Table 5.5	Minimum Pipe Sizes for Reticulation and Property Connection Sewers
Table 5.6	Maximum Capacities for Gravity Sewers for Various Locations
Table 5.7	Manning Coefficient
Table 5.8	Design Minimum Grades
Table 5.9	Minimum Grades for Property Connection Sewers
Table 5.10	Minimum Grades for End-of-line Sewers
Table 5.11	Minimum Cover over Sewers
Table 5.12	Minimum Internal Fall Through an MH Joining Reticulation Sewers of Same Diameter
Table 5.13	Limitations on Large Falls at MHs Using Internal and External Drops
Table 5.14	Steep Sewers Requiring Special Treatment
Table 7.1	Acceptable Maintenance Structure Options for Reticulation and Property Connection Sewers
Table 7.2	External MH Drop Pipe Structure

Table 7.3	Rocker Pipe Dimensions
Table 7.4	Minimum Drop Height Details for PP
Table 7.5	Guide to Selection of Maintenance Structure Access Covers, Class and Finished Surface Levels
Table 8.1	Requirements for Vortex Inlets and Water Cushions
Table 8.2	ERS Structure Components
Table 9.1	Requirements for Bulkheads and Trenchstops

## FIGURES

Figure 2.1	Disaggregation Model for Transportation Subsystems
Figure 3.1	Flow Components in a Gravity System
Figure 5.1	Physical Losses in Customer Sanitary Drains
Figure 5.2	Depth of Point of Connection and Use of Risers
Figure 5.3	Excessively Deep Channels Caused By Steep Grades
Figure 5.4	Incoming Level Adjusted to Prevent Deep Channel
Figure 6.1	Typical Raised Inspection Opening Interface Method
Figure 6.2	Typical Buried Interface Method – Variation (A)
Figure 6.3	Typical Buried Interface Method – Variation (B)
Figure 6.4	Property Connection Points for Sewers in Road Reserves – IO Interface Method
Figure 6.5	Property Connection Points for Sewers in Easements and Private Lots – Buried Interface Method
Figure 6.6	Typical Connection to Deep Sewers in Private Property
Figure 6.7	'Type 7 'Spur' or 'Y' Property Sewer Connections – Buried Interface Method
Figure 7.1	Single MS or MC Between Consecutive MHs
Figure 7.2	Multiple MS or MC Between Consecutive MHs
Figure 7.3	No MS or MC Between Last MH and IS, TMS or MC
Figure 7.4	Single MS/MC Between Last MH and IS, TMS or MC
Figure 7.5	Typical Pre-Cast MH Base with Pre-Formed Benching
Figure 7.6	Typical Pre-Cast Concrete MH Base with Conical Benching
Figure 7.7	Typical Cast In-Situ Concrete MH Base for VC, RC and DI RRJ Sewers
Figure 7.8	Typical Cast In-Situ Concrete MH Base for PVC RRJ Sewers
Figure 7.9	Typical Cast In-Situ Concrete MH Base for PVC-U SCJ
Figure 7.10	Typical Cast In-Situ Concrete MH Base for VC and GRP Sleeved Coupled Sewers
Figure 7.11	Typical Cast In-Situ Concrete MH Base for Profile Wall PP Sewers
Figure 7.12	Typical Cast In-Situ Concrete MH Base for Solid Wall PE Sewers
Figure 7.13	Typical Cast In-Situ Concrete MH with External Drop Pipe (PVC-U DWV RRJ Sewer Pipe Shown)
Figure 7.14	Typical Pre-Cast Concrete MH with External Drop Pipe (PVC-U DWV RRJ Sewer Pipe Shown)
Figure 7.15	Typical Cast In-Situ Concrete MH with Internal Drop Pipe (PVC-U

DWV Sewer Pipe Shown)

- Figure 7.16 Typical MH Base Design
- Figure 7.17 Typical Arrangements for the Connection of PE Sewers
- Figure 7.18 Typical Arrangements for the Connection of a PE MS to PE Sewers
- Figure 7.19 Typical PVC-U Cap Assembly and Fittings
- Figure 7.20 Typical Arrangement for the Connection to a Pre-Cast Concrete MC
- Figure 7.21 Typical PP MC and MS Connection Details
- Figure 7.22 Typical TMS with Property Connection Ahead
- Figure 7.23 Typical Pre-Cast MC with High-Level Connection
- Figure 7.24 Typical PE MC or MS Drop Detail Dimensions
- Figure 7.25 Typical PVC-U MS Drop Detail Dimensions
- Figure 7.26 Typical PP MC/MS With High-Level Connection
- Figure 7.27 Typical External Sewer Drop Structure Type A - 45° Slope Junction
- Figure 7.28 Typical External Sewer Drop Structure Type B – 90° Slope Junction
- Figure 7.29 Terminal Inspection Shaft – Type A
- Figure 7.30 Vertical Drop Inspection Shaft – Type B
- Figure 7.31 Intermediate Inspection Shaft – Type C
- Figure 7.32 Access Requirements for Sewers from Junctions
- Figure 8.1 Application of Water Seal Arrangements
- Figure 8.2 Typical Boundary Trap and Shaft
- Figure 8.3 Typical Water Seal on Inlet Sewer
- Figure 8.4 Typical Water-Sealed MH with External Drop – Plan View
- Figure 8.5 Typical Water-Sealed MH with External Drop – Elevation
- Figure 8.6 Typical Water-Sealed MH with Minimum Drop – Plan View
- Figure 8.7 Typical Water-Sealed MH with Minimum Drop – Elevation
- Figure 8.8 Typical Gas Check MH – Sectional Plan
- Figure 8.9 Typical Gas Check MH – Section Elevation
- Figure 8.10 Typical Gas Check MH – Internal Drop Arrangement Section Elevation
- Figure 8.11 Typical Syphon Creek Crossing
- Figure 8.12 Typical PE Pipe Section
- Figure 8.13 Typical ERS Arrangement – Plan
- Figure 8.14 Typical ERS Arrangement – Elevation
- Figure 8.15 Typical Headwall Arrangement - Elevation
- Figure 9.1 Typical Arrangement for Buried Flexible Pipelines
- Figure 9.2 Type 1 Support for Rigid Pipes Only
- Figure 9.3 Type 2 Support for Rigid Pipes Only
- Figure 9.4 Type 3 Support for Flexible And Rigid Pipes
- Figure 9.5 Type 4 Embedment Support with Geotextile Filter Fabric for Flexible and Rigid Pipes
- Figure 9.6 Type 5 and 6 Support Utilising Concrete Foundation

- Figure 9.7 Type 7 Support Utilising Geotextile Pillow Foundation for Rigid and Flexible Pipes
- Figure 9.8 Type 8 Support Utilising Cement Stabilised Foundation for Rigid and Flexible Pipes
- Figure 9.9 Type 9 Embedment Support
- Figure 9.10 Type 10 Embedment Support
- Figure 9.11 Type 11 Embedment Support
- Figure 9.12 Type 12R Support Concrete Encasement
- Figure 9.13 Type 12U Support Concrete Embedment
- Figure 9.14 Type 13 Support Utilising Cement Stabilised Embedment
- Figure 9.15 Typical Concrete Bulkhead Detail
- Figure 9.16 Typical Road Crossing Bulkhead
- Figure 9.17 Typical Trenchstop Detail
- Figure 9.18 Typical Trench Drainage Detail at Bulkhead
- Figure 9.19 Typical Trench Drainage Discharge
- Figure 9.20 Typical Trench Drainage Detail at Low Point in Trench
- Figure 9.21 Typical Trench Drainage Detail at Concrete Encased Sections
- Figure 9.22 Typical Trench Drainage Around MHs



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# **PART 2: CONSTRUCTION**

Gravity Sewerage Code of Australia  
Version 3.1

## CONTENTS

### 11 GENERAL

#### 11.1 SCOPE

##### 11.1.1 Resolution of complaints

#### 11.2 INTERPRETATION

### 12 GENERAL CONSTRUCTION

#### 12.1 GENERAL

#### 12.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING

#### 12.3 CONTRACT INTERFACES

#### 12.4 CUSTOMER FOCUS

##### 12.4.1 General

##### 12.4.2 Resolution of complaints

#### 12.5 PROTECTION OF PROPERTY AND ENVIRONMENT

##### 12.5.1 Protection of other services

##### 12.5.2 Road reserves or other thoroughfares

###### 12.5.2.1 Road opening permits

###### 12.5.2.2 Treatment of pavements and other surfaces

###### 12.5.2.3 Cleanliness of roads, paths, accesses and drainage paths

###### 12.5.2.4 Storage of products, materials, equipment and excavated material

###### 12.5.2.5 Obstruction of street drainage

##### 12.5.3 Private and public lands

##### 12.5.4 Protection of the environment and heritage areas

###### 12.5.4.1 General

###### 12.5.4.2 Collection and disposal of wastes

###### 12.5.4.3 Protection of adjacent lands and vegetation

###### 12.5.4.4 Control of water pollution

###### 12.5.4.5 Contaminated soils

###### 12.5.4.6 Control of noise and atmospheric pollution

###### 12.5.4.7 Equipment and machinery use in bush fire prone areas

#### 12.6 DISUSED SEWERS

#### 12.7 OPERATION OF WATER SUPPLY NETWORK

#### 12.8 ALTERATION OF EXISTING SERVICES

#### 12.9 SURVEY MARKS

#### 12.10 CONSTRUCTION TOLERANCES

#### 12.11 LATENT CONDITIONS

### 13 PRODUCTS AND MATERIALS

#### 13.1 APPROVED PRODUCTS AND MATERIALS

#### 13.2 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS

#### 13.3 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS

##### 13.3.1 General

##### 13.3.2 Transportation

##### 13.3.3 Unloading and handling

##### 13.3.4 On-site storage

##### 13.3.5 Plastics-lined concrete products

##### 13.3.6 Coiled plastics pipe

#### 13.4 CONCRETE WORKS

#### 13.5 SUPPLY OF WATER TO THE WORKS

### 14 EXCAVATION

#### 14.1 PRECAUTIONS

#### 14.2 LIMITS OF CLEARING AND EXCAVATION

#### 14.3 PROTECTION OF TREES

##### 14.3.1 General precautions

##### 14.3.2 Protection of roots

#### 14.4 BLASTING



- 14.5 SUPPORT OF EXCAVATIONS
- 14.6 DRAINAGE AND DEWATERING
- 14.7 EXCAVATION ACROSS IMPROVED SURFACES
- 14.8 TRENCH EXCAVATION
  - 14.8.1 General
  - 14.8.2 Construction of embankment
  - 14.8.3 Clearances for on-site works
- 14.9 REFILL OF EXCESSIVE EXCAVATION
- 14.10 FOUNDATIONS AND FOUNDATION STABILISATION
- 14.11 SURPLUS EXCAVATED MATERIAL
- 14.12 EXCAVATION AND PIPELAYING USING TRENCHLESS TECHNIQUES

## **15 BEDDING FOR PIPES AND MAINTENANCE STRUCTURES**

- 15.1 TRENCH FLOOR PREPARATION
- 15.2 BEDDING MATERIALS
  - 15.2.1 Placement of bedding
- 15.3 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS
- 15.4 BEDDING FOR MAINTENANCE CHAMBERS, MAINTENANCE SHAFTS, INSPECTION SHAFTS AND BENDS
- 15.5 BEDDING FOR MAINTENANCE HOLES

## **16 PIPE LAYING AND JOINTING**

- 16.1 INSTALLATION OF PIPES
  - 16.1.1 General
  - 16.1.2 Cleaning, inspection and joint preparation
  - 16.1.3 Coiled plastics pipes
  - 16.1.4 Laying
- 16.2 HORIZONTAL AND VERTICAL DEFLECTION OF SEWERS
  - 16.2.1 General
  - 16.2.2 Methods of deflection
  - 16.2.3 Horizontal curves
  - 16.2.4 Vertical curves
  - 16.2.5 Compound curves
- 16.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES
- 16.4 FLOTATION CONTROL
- 16.5 TRENCH STOPS
- 16.6 BULKHEADS
- 16.7 PROPERTY CONNECTION SEWERS
- 16.8 DEAD ENDS
- 16.9 MARKING OF PROPERTY CONNECTION SEWERS AND DEAD ENDS
- 16.10 CORROSION PROTECTION OF CAST IRON
- 16.11 MARKERS
  - 16.11.1 Non-detectable marking tape
  - 16.11.2 Detectable marking tape
- 16.12 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE
- 16.13 AQUEDUCTS
- 16.14 BRIDGE CROSSINGS
- 16.15 PLASTICS-LINED RC PIPE JOINTING
  - 16.15.1 General
  - 16.15.2 Plastics lining work protection
  - 16.15.3 Field jointing
  - 16.15.4 Plastics lining ancillary work
    - 16.15.4.1 Alignment of lining keys
    - 16.15.4.2 Provision of seepage channels
    - 16.15.4.3 Use of jointing accessories and adhesives
- 16.16 WELDING OF STEEL PIPELINES
  - 16.16.1 General
  - 16.16.2 Field welding of flanges
  - 16.16.3 Reinstatement of cement mortar lining

- 16.16.4 Reinstatement of external corrosion protection at joints using a tape system
  - 16.16.4.1 Surface preparation
  - 16.16.4.2 Priming surfaces
  - 16.16.4.3 Mastic filler
  - 16.16.4.4 Tape application
- 16.16.5 Reinstatement of external corrosion protection at joints using a heat-shrinkable sleeve system
  - 16.16.5.1 Surface preparation
  - 16.16.5.2 Preheat pipe
  - 16.16.5.3 Priming surfaces
  - 16.16.5.4 Mastic filler
  - 16.16.5.5 Heat-shrinkable sleeve preparation
  - 16.16.5.6 Heat-shrinkable sleeve application
- 16.17 WELDING OF PE PIPELINES
  - 16.17.1 General
  - 16.17.2 Welder qualifications
  - 16.17.3 Connections to pipes of other materials

## **17 MAINTENANCE HOLES (MHS)**

- 17.1 GENERAL
- 17.2 CONCRETE MHS
  - 17.2.1 Concrete MH base
  - 17.2.2 Pre-cast concrete MH systems
  - 17.2.3 Cast in-situ concrete MH
  - 17.2.4 Benching and channels
  - 17.2.5 Concreting for thermoplastics-lined works
    - 17.2.5.1 Concrete work planning
    - 17.2.5.2 Fixing of thermoplastics lining for concrete work
    - 17.2.5.3 Concrete placement and formwork removal
  - 17.2.6 Internal coating of concrete MHs
- 17.3 GLASS REINFORCED PLASTICS (GRP) MHS
- 17.4 POLYETHYLENE (PE) MHS
- 17.5 POLYPROPYLENE (PP) MHS
- 17.6 TRENCH DRAINAGE AROUND MHS
- 17.7 COVERS
- 17.8 CONNECTIONS TO MHS
- 17.9 MH DROPS
- 17.10 LADDERS, STEP IRONS AND LANDINGS

## **18 MAINTENANCE CHAMBERS (MC), MAINTENANCE SHAFTS (MS AND TMS) AND INSPECTION OPENINGS (IO) OR INSPECTION SHAFTS (IS)**

- 18.1 GENERAL
- 18.2 SEALING CAPS
- 18.3 COVERS
- 18.4 CONNECTIONS TO MCS, MSS AND TMSS

## **19 PIPE EMBEDMENT AND SUPPORT**

- 19.1 GENERAL
- 19.2 EMBEDMENT MATERIALS
- 19.3 COMPACTION OF EMBEDMENT
  - 19.3.1 Methods
  - 19.3.2 Compaction trials / Pre-qualification of embedment compaction method
    - 19.3.2.1 General
    - 19.3.2.2 Test method
    - 19.3.2.3 Interpretation and applicability
  - 19.3.3 Compaction control
- 19.4 SPECIAL BEDDING AND EMBEDMENTS / GEOTEXTILE SURROUND AND PILLOW
- 19.5 REMOVAL OF TRENCH SUPPORTS
- 19.6 CONCRETE EMBEDMENT AND ENCASMENT

**20 FILL**

- 20.1 TRENCH FILL
  - 20.1.1 General
  - 20.1.2 Material requirements
    - 20.1.2.1 Trafficable areas
    - 20.1.2.2 Non-trafficable areas
  - 20.1.3 Placement
  - 20.1.4 Compaction of trench fill
- 20.2 EMBANKMENT FILL
- 20.3 DRIVES AND TUNNEL FILL

**21 ACCEPTANCE TESTING**

- 21.1 GENERAL
- 21.2 VISUAL INSPECTION—ABOVE-GROUND
- 21.3 COMPACTION TESTING
  - 21.3.1 General
  - 21.3.2 Compaction testing requirements
    - 21.3.2.1 General
  - 21.3.3 Embedment compaction testing
    - 21.3.3.1 Applicable pipe sizes
    - 21.3.3.2 Frequency and location of embedment tests
    - 21.3.3.3 Retesting
  - 21.3.4 Trench fill compaction testing
    - 21.3.4.1 Trafficable test zone
    - 21.3.4.2 Non-trafficable test zone
    - 21.3.4.3 Test method
    - 21.3.4.4 Frequency and location of tests
    - 21.3.4.5 Retesting
  - 21.3.5 Other fill compaction testing
    - 21.3.5.1 General
    - 21.3.5.2 Trafficable test zone
    - 21.3.5.3 Non-trafficable test zone
    - 21.3.5.4 Frequency and location of tests
    - 21.3.5.5 Retesting
- 21.4 AIR PRESSURE AND VACUUM TESTING OF SEWERS
  - 21.4.1 General
  - 21.4.2 Air testing methods for sewers
    - 21.4.2.1 Vacuum testing
    - 21.4.2.2 Low pressure air testing
  - 21.4.3 Testing of sewers >DN 1500
    - 21.4.3.1 General
    - 21.4.3.2 Method of test
  - 21.4.4 Testing of non-pressure PE sewers
  - 21.4.5 Testing of concrete MHs
    - 21.4.5.1 General
    - 21.4.5.2 Test method
- 21.5 INFILTRATION TESTING
- 21.6 DEFLECTION (OVALITY) TESTING OF FLEXIBLE SEWERS
  - 21.6.1 General
  - 21.6.2 Ovality proving tools
  - 21.6.3 Flexible sewers  $\leq$ DN 300
  - 21.6.4 Flexible sewers >DN 300
    - 21.6.4.1 General
    - 21.6.4.2 Flexible sewers >DN 300 and <DN 750
    - 21.6.4.3 Flexible sewers  $\geq$ DN 750
- 21.7 MEASUREMENT OF SEWER GRADE
- 21.8 INTERNAL INSPECTION

## 21.9 INSPECTION AND TESTING OF THERMOPLASTICS LINED CONCRETE SEWERS AND MHS

21.9.1 Visual inspection

21.9.2 Spark testing

21.9.3 Locking key pull-out tests

## 21.10 PRESSURE TESTING OF INVERTED SYPHONS

21.10.1 General

21.10.2 Hydrostatic system test pressure

21.10.3 Satisfactory pressure test

## 22 TOLERANCES ON AS-CONSTRUCTED WORK

### 22.1 HORIZONTAL TOLERANCES

22.1.1 Sewers and on-line structures

22.1.2 Property connection sewers

### 22.2 VERTICAL TOLERANCES

22.2.1 Sewers and structures

22.2.2 Property connection risers and inspection openings

22.2.3 Grade

22.2.4 Verticality ("plumb")

### 22.3 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS

### 22.4 TOLERANCES ON CAST IN-SITU CONCRETE STRUCTURES AND SLABS

## 23 CONNECTION TO EXISTING SEWERS

## 24 RESTORATION

24.1 GENERAL

24.2 PAVEMENTS

24.3 LAWNS

24.4 GRASSED AREAS

24.5 BUSHLAND

24.6 PROVISION FOR AND RECTIFICATION OF SETTLEMENT

24.7 MAINTENANCE OF RESTORED SURFACES

## 25 WORK AS CONSTRUCTED DETAILS

### TABLES

Table 21.1	Flexible Pipes – Minimum Compaction Embedment, Trench Fill And Embankment Of Flexible Pipes
Table 21.2	Rigid Pipes – Minimum Compaction Embedment, Trench Fill And Embankment
Table 21.3	Pressure And Vacuum Air Testing Acceptance Times For 7 kPa Pressure Change
Table 21.4	Concrete MH Testing Frequency
Table 21.5	Minimum Test Times For Concrete MHs
Table 21.6	Maximum Allowable Short-Term Pipe Deflections
Table 22.1	Sewer Grade Tolerances
Table 22.2	Property Connection Sewer Grade Tolerances

### FIGURES

Figure 16.1	Ball and Socket Joint
Figure 16.2	Slip-In Welded Joint
Figure 16.3	Plain End Welded Collar Joint
Figure 16.4	Plain End Butt Welded Joint