



WATER SERVICES
ASSOCIATION OF AUSTRALIA

WATER SUPPLY CODE OF AUSTRALIA

Regional New South Wales Edition
Version 1



WATER
DIRECTORATE

WSA 03-2011-3.1

Contents

List of Figures.....	36
List of Tables.....	42
FRONTMATTER.....	2
GENERAL.....	2
ACKNOWLEDGEMENTS.....	2
ABOUT WSAA.....	2
ACKNOWLEDGEMENT OF COUNTRY.....	3
DISCLAIMER.....	3
COPYRIGHT.....	3
ALL RIGHTS RESERVED	3
FOREWORD.....	3
PREFACE.....	4
THE NEED FOR TECHNICAL DOCUMENTATION.....	4
The Benefits of National Codes.....	5
Innovation.....	5
HYPOTHETICAL EXAMPLE OF THE USE OF THE WATER SUPPLY CODE.....	6
Concept Plan.....	6
Agency / Development Agreement.....	6
Project Manager.....	6
Design.....	6
Project Specification.....	7
Constructor.....	7
Testing.....	7
The WSAA Website.....	7
INTRODUCTION.....	7
SCOPE OF CODE.....	7
CODE PURPOSE.....	8
MANDATORY AND INFORMATIVE.....	8
APPENDICES.....	9
PRODUCT SPECIFICATIONS.....	9
General.....	9
Quality Assurance.....	9
Packaging, Transportation and Delivery.....	9
Products and Material Information and Guidance.....	9
Water Industry Standards.....	10
WORK HEALTH AND SAFETY (WHS) LAWS.....	10
NATIONAL STANDARD FOR CONSTRUCTION WORK.....	10
SAFE DESIGN OF STRUCTURES.....	11
PROPOSED AMENDMENTS.....	12
USING STANDARD DRAWINGS IN CONJUNCTION WITH THE CODE.....	12
GLOSSARY, ABBREVIATIONS AND REFERENCES.....	45
I GLOSSARY OF TERMS.....	45
II ABBREVIATIONS.....	61
III REFERENCED DOCUMENTS.....	65
PART 1: PLANNING AND DESIGN.....	71

1 GENERAL.....	71
1.1 SCOPE.....	71
1.2 PLANNING AND DESIGN.....	72
1.2.1 Objectives.....	72
1.2.2 Scope and requirements.....	72
1.2.3 Concept plan format.....	72
1.2.4 Critical infrastructure protection.....	73
1.2.4.1 Asset categorisation.....	73
1.2.4.2 All hazards – Infrastructure protection.....	74
1.2.5 Detailed design.....	75
1.2.5.1 Designer's needs and responsibilities.....	75
1.2.5.2 Requirements to be addressed.....	75
1.2.5.3 Design outputs.....	76
1.2.6 Design life.....	76
1.2.7 Instrumentation and control systems.....	77
1.3 CONSULTATION WITH OTHER PARTIES.....	77
2 SYSTEM PLANNING.....	78
2.1 GENERAL.....	78
2.2 SYSTEM PLANNING PROCESS.....	78
2.2.1 General.....	78
2.2.2 Extending / upgrading an existing water supply system.....	78
2.2.3 Providing a new water supply.....	78
2.2.4 Non-drinking water as drinking water substitution.....	79
2.3 DEMANDS.....	79
2.3.1 General.....	79
2.3.2 Dual water supply systems.....	79
2.3.2.1 General.....	79
2.3.2.2 Rainwater tanks.....	80
2.3.3 Demand assessment.....	81
2.3.3.1 General.....	81
2.3.3.2 Residential.....	81
2.3.3.3 Non-residential.....	83
2.3.4 Peak demands.....	83
2.3.4.1 General.....	83
2.3.4.2 Peak day demand.....	83
2.3.4.3 Peak hour demand.....	84
2.4 SYSTEM CONFIGURATION.....	84
2.5 SYSTEM HYDRAULICS.....	86
2.5.1 General.....	86
2.5.2 Network analysis.....	86
2.5.3 Operating pressures.....	86
2.5.3.1 Service pressure.....	86
2.5.3.2 Maximum allowable service pressure.....	86
2.5.3.3 Minimum service pressure.....	87
2.5.3.4 Average service pressure.....	87
2.5.3.4.1 GENERAL.....	87

2.5.3.4.2	LIMITING HIGH AVERAGE SERVICE PRESSURES.....	88
2.5.3.4.3	ENSURING A SUITABLE RANGE OF SERVICE PRESSURES.....	88
2.5.3.4.4	DUAL WATER SUPPLY SYSTEMS.....	88
2.5.4	Pressure variation analysis.....	88
2.5.5	Determining supply zones.....	89
2.5.5.1	General.....	89
2.5.5.2	Use of minimum allowable or desirable minimum service pressures.....	89
2.5.5.3	Use of desirable minimum static pressure.....	89
2.6	WATER QUALITY.....	90
2.6.1	General.....	90
2.6.2	Prevention of back siphonage.....	90
2.6.3	Water age.....	90
2.6.4	Disinfection.....	91
2.7	SEPARATION OF DRINKING AND NON-DRINKING WATER SUPPLY SYSTEMS.....	91
2.7.1	Permanent cross links and cross connections.....	91
2.7.2	Temporary cross links.....	91
2.8	PUMPING STATIONS.....	91
2.8.1	General.....	91
2.8.2	Design factors.....	94
2.8.2.1	System related factors.....	94
2.8.2.2	Site related factors.....	94
2.8.2.3	Service related factors.....	94
2.8.3	Concept design.....	94
2.9	SERVICE RESERVOIRS.....	95
2.9.1	Storage capacity.....	95
2.9.2	Location.....	96
2.10	TRENCHLESS TECHNIQUES FOR PIPELAYING.....	97
2.11	FUTURE SYSTEM EXPANSION.....	97
2.12	SYSTEM REVIEW.....	98
3	HYDRAULIC DESIGN.....	99
3.1	SIZING.....	99
3.1.1	General.....	99
3.1.2	Minimum pipe sizes.....	99
3.1.3	Empirical sizing of reticulation mains.....	100
3.1.4	Dual water supply systems.....	100
3.1.5	Fire flows.....	100
3.1.6	Sizing by analysis.....	101
3.1.6.1	General.....	101
3.1.6.2	Head losses.....	101
3.1.6.3	Hydraulic roughness values.....	101
3.1.6.4	Flow velocities.....	102
3.2	DESIGN PRESSURES.....	102
3.2.1	General.....	102
3.2.2	Gravity systems.....	103
3.2.3	Systems subjected to dynamic pressures.....	103
3.3	PRESSURE CLASS OF SYSTEM COMPONENTS.....	104

3.3.1 Gravity systems.....	104
3.3.2 Systems subjected to dynamic pressures.....	104
3.4 THRUST AND ANCHOR BLOCK DESIGN.....	104
3.5 SYSTEM TEST PRESSURE.....	104
3.6 DESIGN FOR DYNAMIC STRESSES.....	104
3.6.1 General.....	104
3.6.2 Surge.....	105
3.6.3 Fatigue.....	105
3.6.4 Fatigue de-rating of plastics pipes and fittings.....	105
3.7 TEMPERATURE DE-RATING OF PLASTICS PIPES AND FITTINGS.....	106
3.8 PIPELINE COMPONENT MINIMUM PRESSURE CLASS.....	107
4 PRODUCTS AND MATERIALS.....	108
4.1 GENERAL.....	108
4.2 DIFFERENTIATION OF DRINKING AND NON-DRINKING PIPE SYSTEMS.....	108
4.2.1 Principles.....	108
4.2.2 Water supply mains – drinking water.....	109
4.2.3 Water supply mains – non-drinking water.....	109
4.2.4 Property services – drinking water.....	110
4.2.5 Property services – non-drinking water.....	110
4.2.6 Marking tapes.....	112
4.3 DUCTILE IRON PIPELINE SYSTEMS.....	112
4.3.1 Product Specifications.....	112
4.3.2 Sizes and configurations.....	113
4.3.3 Seal coating of lining.....	113
4.3.4 Sleeving.....	113
4.3.5 Screw-on flanges for DI pipes.....	113
4.3.6 Flanged joints.....	114
4.3.7 Coatings.....	114
4.4 PVC PIPELINE SYSTEMS.....	115
4.4.1 Product Specifications.....	115
4.4.2 Sizes and configurations.....	116
4.5 PE PIPELINE SYSTEMS.....	116
4.5.1 Product Specification.....	116
4.5.2 Sizes and Configurations.....	117
4.6 STEEL PIPELINE SYSTEMS.....	118
4.6.1 Product Specifications.....	118
4.6.2 Sizes and configurations.....	118
4.6.3 Joints.....	118
4.6.4 Field welding.....	119
4.6.5 Flanged joints.....	119
4.7 GRP PIPELINE SYSTEMS.....	119
4.8 PROTECTION AGAINST DEGRADATION.....	120
4.8.1 Application.....	120
4.8.2 Protection against aggressive environments.....	120
4.8.3 Protection against damage to coatings.....	120
4.8.4 Stainless steels.....	121

4.8.4.1	Grade selection.....	121
4.8.4.2	Welding.....	122
4.8.4.3	Threaded components.....	122
4.8.5	Cathodic protection.....	122
4.8.6	Stray current corrosion.....	123
4.8.7	Protection against contaminated ground.....	123
4.8.8	Bolted connections.....	124
5	GENERAL DESIGN.....	126
5.1	GENERAL REQUIREMENTS.....	126
5.1.1	Design tolerances.....	126
5.1.2	Levels.....	126
5.1.3	Water main renewals—electrical safety and earthing to water services.....	126
5.1.4	Environmental considerations.....	127
5.1.4.1	General.....	127
5.1.4.2	Urban salinity.....	128
5.1.5	Survey Control	128
5.1.5.1	Marking.....	128
5.1.5.2	Horizontal control	128
5.1.5.3	Vertical control.....	129
5.2	RETICULATION DESIGN FOR WATER QUALITY.....	129
5.2.1	Layout of water mains.....	129
5.2.2	Looped mains.....	129
5.2.3	Link mains.....	129
5.2.4	Reduced size mains.....	130
5.3	WATER MAIN ACCESS.....	131
5.4	LOCATION OF WATER MAINS.....	131
5.4.1	General.....	131
5.4.2	Water mains in road reserves.....	132
5.4.2.1	General.....	132
5.4.2.2	Location in footway.....	133
5.4.2.3	Location in carriageway.....	133
5.4.2.4	Location in roundabouts and bus bays.....	133
5.4.3	Location in other than dedicated public road reserves.....	133
5.4.4	Water mains in easements.....	134
5.4.5	Dual water supply systems.....	136
5.4.6	Effect on vegetation.....	136
5.4.7	Water mains near trees.....	136
5.4.8	Contaminated sites.....	136
5.4.9	Crossings.....	137
5.4.9.1	General.....	137
5.4.9.2	Requirements for encased pipe installations.....	138
5.4.10	Railway reserves.....	139
5.4.11	Crossings of creeks or drainage reserves.....	139
5.4.12	Overhead power lines and transmission towers.....	139
5.4.13	Water mains in conjunction with landscaping and/or other development.....	140
5.4.14	Water mains on curved alignments.....	140

5.4.15	Location markers.....	141
5.4.16	Marking tape.....	141
5.4.16.1	General.....	141
5.4.16.2	Mains.....	141
5.4.16.3	Property services.....	142
5.5	TRENCHLESS TECHNOLOGY.....	142
5.6	SHARED TRENCHING.....	143
5.7	DUPLICATE MAINS.....	146
5.8	RIDER MAINS.....	146
5.9	CONNECTION OF NEW MAINS TO EXISTING MAINS.....	146
5.9.1	Product Specifications.....	146
5.9.2	General.....	147
5.9.3	Under pressure Cut-in connection.....	147
5.9.4	Inserted tee method.....	148
5.10	TERMINATION POINTS.....	148
5.10.1	Permanent ends of water mains.....	148
5.10.2	Temporary ends of water mains.....	148
5.10.3	Chlorination assemblies.....	149
5.10.4	Flushing points.....	149
5.11	PROPERTY SERVICES.....	150
5.11.1	General.....	150
5.11.2	Connections to water mains.....	150
5.11.3	Services, outlets and meters.....	151
5.12	OBSTRUCTIONS AND CLEARANCES.....	152
5.12.1	General.....	152
5.12.2	Surface obstructions.....	153
5.12.3	Clearance from transmission towers.....	153
5.12.4	Clearance from structures and property boundaries.....	153
5.12.5	Underground obstructions and services.....	153
5.12.5.1	General.....	153
5.12.5.2	Clearance requirements.....	153
5.12.6	Deviation of water mains.....	155
5.12.6.1	General.....	155
5.12.6.2	Horizontal deviation of water mains.....	155
5.12.6.3	Vertical deviation of water mains.....	156
5.12.6.4	Curving of pipes to avoid obstructions.....	159
5.13	DISUSED OR REDUNDANT PIPELINES.....	159
6	SYSTEM PRESSURE MANAGEMENT.....	161
6.1	GENERAL.....	161
6.2	IN-LINE PRESSURE BOOSTER PUMPING STATIONS.....	161
6.2.1	Planning criteria.....	161
6.2.2	Concept design.....	162
6.2.2.1	General.....	162
6.2.2.2	Life cycle considerations.....	162
6.2.2.3	Functionality.....	162
6.2.2.4	Due diligence requirements.....	163

6.2.2.5 Reliability.....	163
6.2.2.6 Maintainability.....	163
6.2.2.7 Materials design.....	163
6.2.2.8 Location.....	164
6.2.2.9 Site selection.....	164
6.2.2.10 Noise control.....	165
6.2.2.11 Services.....	165
6.2.2.12 Access.....	165
6.2.2.13 Site drainage.....	165
6.2.2.14 Landscaping.....	165
6.2.2.15 Security.....	166
6.2.2.16 Signage.....	166
6.2.2.17 Supporting systems.....	166
6.2.2.18 Health and safety.....	166
6.2.3 Commissioning plan.....	166
6.2.3.1 General.....	166
6.2.3.2 Pre-commissioning.....	167
6.2.3.3 Commissioning.....	168
6.2.4 System planning and modelling.....	169
6.2.4.1 Modelling.....	169
6.2.4.2 Minimum pressure affecting the area.....	169
6.2.4.3 Number of affected properties within the low pressure zone.....	170
6.2.5 Booster design.....	170
6.2.5.1 General.....	170
6.2.5.2 Connection to the network.....	170
6.2.5.3 Maximum flow and pressure requirements.....	171
6.2.5.4 Design for minimum pressure boost conditions.....	171
6.2.5.5 Design for minimum flow conditions.....	171
6.2.5.6 Booster configuration design.....	171
6.2.5.7 Booster set and pump selection.....	172
6.2.5.8 Booster pipework and manifold design.....	173
6.2.5.9 Booster equipment and devices.....	173
6.2.5.10 Site specific requirements.....	174
6.2.6 Booster pipework.....	174
6.2.6.1 General design parameters.....	174
6.2.6.2 Manifolds, off-takes, suction and delivery pipework.....	175
6.2.6.3 Pressure gauges and tappings.....	175
6.2.7 Pressure accumulator tank.....	175
6.2.8 Power system and supply.....	176
6.2.8.1 General.....	176
6.2.8.2 Security of supply.....	176
6.2.8.3 Primary supply.....	177
6.2.8.4 Duplicate supply.....	177
6.2.8.5 Emergency power.....	177
6.2.8.6 On-site generator.....	178
6.2.8.7 Mobile generator.....	178

6.2.8.8 Power factor correction.....	178
6.2.8.9 Lighting.....	178
6.2.9 Control and telemetry system.....	178
6.2.9.1 General.....	178
6.2.9.2 Instrumentation.....	179
6.2.9.3 System requirements.....	179
6.2.9.4 Fire flow operation.....	180
6.2.10 Alarms and controls.....	180
6.2.10.1 General.....	180
6.2.10.2 Control switches – manual and emergency operation.....	181
6.2.11 Telemetry.....	181
6.2.11.1 General.....	181
6.2.11.2 Software.....	182
6.2.11.3 Communications.....	182
6.3 PRESSURE REDUCING VALVE INSTALLATIONS.....	183
6.3.1 Planning criteria.....	183
6.3.2 Design requirements.....	183
6.4 PRESSURE SUSTAINING VALVE INSTALLATIONS.....	183
6.4.1 Planning criteria.....	183
6.4.2 Design requirements.....	184
7 STRUCTURAL DESIGN.....	185
7.1 GENERAL.....	185
7.2 STRUCTURAL CONSIDERATIONS.....	185
7.3 INTERNAL FORCES.....	185
7.4 EXTERNAL FORCES.....	185
7.4.1 General.....	185
7.4.2 Pipe cover.....	186
7.4.3 Embedment zone dimensions.....	187
7.4.4 Pipe embedment.....	187
7.4.5 Buoyancy.....	188
7.5 GEOTECHNICAL CONSIDERATIONS.....	189
7.5.1 General.....	189
7.5.2 Water mains in engineered or controlled fill.....	192
7.5.3 Water mains in non-engineered fill.....	192
7.5.4 Construction of an embankment.....	193
7.6 CONCRETE ENCASEMENT.....	193
7.6.1 General.....	193
7.6.2 Requirements.....	194
7.6.3 Encased steel pipelines.....	195
7.6.3.1 General.....	195
7.6.3.2 Existing steel pipelines.....	195
7.7 WATER MAINS IN UNSTABLE GROUND.....	196
7.7.1 General.....	196
7.7.2 Mine subsidence areas.....	197
7.7.3 Slip areas.....	197
7.8 ABOVE-GROUND WATER MAINS.....	198

7.9 PIPELINE ANCHORAGE.....	198
7.9.1 General.....	198
7.9.2 Thrust blocks.....	198
7.9.2.1 General.....	198
7.9.2.2 Concrete thrust blocks.....	199
7.9.2.3 Use of puddle flanges to transfer thrust.....	200
7.9.2.4 Timber and recycled plastics thrust blocks.....	200
7.9.3 Anchor blocks.....	201
7.9.4 Thrust and anchor blocks for dual water supply systems.....	201
7.9.5 Restrained elastomeric seal joint water mains.....	202
7.9.6 Restraint requirements for special situations.....	202
7.9.6.1 Above-ground mains with unrestrained flexible joints.....	202
7.9.6.2 Buried steel mains with welded joints.....	202
7.9.6.3 Above-ground steel mains with welded joints.....	202
7.9.6.4 Ductile iron and steel mains with flanged joints.....	202
7.9.6.5 PE mains.....	202
7.10 BULKHEADS AND TRENCHSTOPS.....	203
7.11 UNFORESEEN GROUND CONDITIONS.....	204
7.12 INSTALLATION TREATMENTS FOR WATER MAINS.....	204
8 APPURTENANCES.....	207
8.1 VALVES—GENERAL.....	207
8.1.1 Valving design.....	207
8.1.2 Valve siting principles.....	207
8.1.3 Selection considerations.....	207
8.1.4 Installation	208
8.1.5 Local in-line booster pumping stations.....	208
8.1.6 Plastics identification covers.....	208
8.2 STOP VALVES.....	209
8.2.1 Product Specifications.....	209
8.2.2 Installation design and selection criteria.....	210
8.2.2.1 General.....	210
8.2.2.2 Gate valves.....	210
8.2.2.3 Butterfly valves.....	215
8.2.3 Stop valves for transfer/distribution mains.....	215
8.2.4 Stop valves for reticulation mains.....	215
8.2.5 Stop valves for local in-line booster pumping stations.....	216
8.2.6 Bypass of stop valve.....	216
8.2.7 Stop valves—location and arrangements.....	217
8.2.7.1 General.....	217
8.2.7.2 Arrangement 1.....	218
8.2.7.3 Arrangement 2.....	218
8.2.7.4 Arrangement 3.....	219
8.2.7.5 Arrangement 4.....	219
8.2.7.6 Arrangement 5.....	219
8.2.7.7 Arrangement 6.....	220
8.2.7.8 Arrangement 7.....	220

8.2.8 Stop valve special arrangements.....	220
8.2.9 Rider mains and network configurations.....	221
8.2.10 Crossing mains – interconnection.....	222
8.3 CONTROL VALVES.....	224
8.3.1 Product Specifications.....	224
8.3.2 Automatic inlet control valves (AICV).....	224
8.3.3 Pressure reducing valves (PRV).....	225
8.3.4 Pressure relief valves (PRelV).....	227
8.3.5 Pump control valves.....	228
8.3.6 Pressure sustaining valves (PSV).....	228
8.4 AIR VALVES (AV).....	229
8.4.1 Product Specifications.....	229
8.4.2 Installation design criteria.....	229
8.4.3 Air valves type.....	229
8.4.4 Air valves size.....	229
8.4.5 Air valves location.....	230
8.4.6 Use of hydrants as an alternative to air valves.....	231
8.4.7 Water sampling via air valves.....	231
8.5 NON-RETURN VALVES.....	231
8.5.1 Product Specifications.....	231
8.5.2 Installation design criteria.....	232
8.5.3 Non-return valves for local in-line booster pumping stations and boosted zones.....	232
8.6 SCOURS AND PUMP-OUT BRANCHES.....	232
8.6.1 Location and arrangements.....	232
8.6.2 Design.....	232
8.6.3 Scour application.....	234
8.6.4 Scour size.....	235
8.6.5 Scour location.....	235
8.7 SWABBING POINTS.....	235
8.8 HYDRANTS.....	236
8.8.1 Product Specifications.....	236
8.8.2 Purposes.....	236
8.8.3 Hydrant siting principles.....	236
8.8.4 Hydrant types.....	237
8.8.5 Hydrant installation.....	237
8.8.6 Hydrant outlet connections.....	238
8.8.7 Hydrant size.....	239
8.8.8 Hydrant spacing.....	239
8.8.9 Hydrant location.....	239
8.8.10 Hydrants for reticulation system operational requirements.....	241
8.8.11 Hydrants at ends of mains.....	242
8.9 DISINFECTION FACILITIES.....	242
8.9.1 General.....	242
8.9.2 Reticulation mains.....	242
8.9.3 Transfer and distribution mains.....	242
8.9.4 Discharge.....	242

8.10 SURFACE FITTINGS.....	242
8.10.1 Product Specifications.....	242
8.10.2 General.....	243
8.10.3 Marking of surface fittings.....	243
8.10.4 Installation requirements.....	243
8.11 APPURTENANCE LOCATION MARKING.....	246
8.11.1 General.....	246
8.11.2 Indicator plates and other markers.....	247
8.11.3 Pavement markers.....	247
8.11.4 Kerb markings.....	248
8.12 SAMPLING POINT ON DISTRIBUTION AND TRANSFER MAINS.....	248
9 DESIGN REVIEW AND DRAWINGS.....	249
9.1 DESIGN REVIEW.....	249
9.2 DESIGN DRAWINGS.....	249
9.2.1 General.....	249
9.2.2 Composition of Design Drawings.....	249
9.2.3 Scale.....	250
9.2.4 Contents of Design Drawings.....	250
9.2.5 Pipeline system acronyms.....	251
9.2.6 Water mains >DN 300.....	252
9.3 SPECIFICATIONS.....	252
9.4 RECORDING OF WORK AS CONSTRUCTED INFORMATION.....	252
PART 2: CONSTRUCTION.....	254
10 GENERAL.....	254
10.1 SCOPE.....	254
10.2 INTERPRETATION.....	254
11 GENERAL CONSTRUCTION.....	256
11.1 GENERAL.....	256
11.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING.....	256
11.3 CONTRACT INTERFACES.....	256
11.4 CUSTOMER FOCUS.....	257
11.4.1 General.....	257
11.4.2 Resolution of complaints.....	257
11.5 PROTECTION OF PROPERTY AND ENVIRONMENT.....	257
11.5.1 Protection of other services.....	257
11.5.2 Disused / Redundant water mains.....	258
11.5.3 Road reserves or other thoroughfares.....	259
11.5.3.1 Road opening permits.....	259
11.5.3.2 Treatment of pavements and other surfaces.....	259
11.5.3.3 Cleanliness of roads, paths, accesses and drainage paths.....	259
11.5.3.4 Storage of products, materials and equipment.....	260
11.5.3.5 Obstruction of street drainage.....	260
11.5.4 Private and public properties.....	260
11.5.5 Protection of the environment and heritage areas.....	260
11.5.5.1 General.....	260
11.5.5.2 Collection and disposal of wastes.....	260

11.5.5.3	Protection of adjacent lands and vegetation.....	261
11.5.5.4	Control of water pollution.....	261
11.5.5.5	Contaminated soils.....	263
11.5.5.6	Fire ant areas.....	263
11.5.5.7	Control of noise and atmospheric pollution.....	264
11.5.5.8	Equipment and machinery use in bush fire prone areas.....	264
11.6	OPERATION OF WATER SUPPLY NETWORK.....	264
11.7	ALTERATION OF EXISTING SERVICES.....	264
11.8	CONNECTION TO AND WORK ON EXISTING ASBESTOS WATER MAINS.....	264
11.9	CUT-IN CONNECTION EQUIPMENT.....	264
11.10	SURVEY MARKS.....	265
11.11	CONSTRUCTION TOLERANCES.....	265
11.12	LATENT CONDITIONS.....	265
12	PRODUCTS AND MATERIALS.....	266
12.1	AUTHORISED PRODUCTS AND MATERIALS.....	266
12.1.1	General.....	266
12.2	DELIVERY INSPECTION OF PRODUCTS AND MATERIALS.....	266
12.3	TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS.....	266
12.3.1	General.....	266
12.3.2	Transportation.....	267
12.3.3	Unloading and handling.....	267
12.3.4	On-site storage.....	267
12.4	REJECTED PRODUCTS AND MATERIALS.....	268
12.5	CONCRETE WORKS.....	268
12.6	SUPPLY OF WATER TO THE WORKS.....	268
12.7	SUPPLY OF WATER TO EXISTING PROPERTIES.....	269
12.8	UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80.....	269
12.8.1	Flanged off-takes.....	269
12.8.2	Valves.....	269
12.8.3	Flange holes.....	269
12.8.4	Gaskets.....	269
12.8.5	Bolting system.....	269
12.8.5.1	General.....	269
12.8.5.2	Carbon or alloy steel bolt assemblies.....	270
12.8.5.3	Stainless steel bolt assemblies.....	270
12.8.6	Insulation sleeves.....	270
12.8.7	Plastics inserts for metallic pipes.....	270
13	EXCAVATION.....	271
13.1	PRECAUTIONS.....	271
13.2	LIMITS OF CLEARING AND EXCAVATION.....	271
13.3	PROTECTION OF TREES.....	271
13.3.1	General precautions.....	271
13.3.2	Protection of roots.....	271
13.4	BLASTING.....	271
13.5	SUPPORT OF EXCAVATIONS.....	272
13.6	DRAINAGE AND DEWATERING.....	272

13.7 UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80.....	272
13.7.1 Excavation requirements.....	272
13.7.2 Extent of excavation.....	273
13.8 EXCAVATION ACROSS IMPROVED SURFACES.....	274
13.9 TRENCH EXCAVATION.....	274
13.9.1 General.....	274
13.9.2 Construction of embankment.....	274
13.9.3 Clearances for on-site works.....	274
13.10 REFILL OF EXCESSIVE EXCAVATION.....	275
13.11 FOUNDATIONS AND FOUNDATION STABILISATION.....	275
13.12 SURPLUS EXCAVATED MATERIAL.....	275
13.13 TUNNELLING.....	275
14 BEDDING FOR PIPES.....	277
14.1 TRENCH FLOOR PREPARATION.....	277
14.2 BEDDING AND PIPE SUPPORT.....	277
14.3 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS.....	277
15 PIPE LAYING, JOINTING AND CONNECTING.....	278
15.1 INSTALLATION OF PIPES.....	278
15.1.1 General.....	278
15.1.2 Dual water supply areas.....	278
15.1.3 Cleaning, inspection and joint preparation.....	278
15.1.4 Laying.....	279
15.1.5 Lift and re-lay construction.....	280
15.2 HORIZONTAL AND VERTICAL DEFLECTIONS OF PIPES.....	280
15.2.1 General.....	280
15.2.2 Deflection at a pipe joint.....	280
15.2.3 Curving of pipe.....	280
15.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES.....	280
15.4 VALVES, HYDRANTS AND OTHER APPURTENANCES.....	281
15.5 UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80.....	281
15.5.1 Inspection of host pipe.....	281
15.5.2 Inspection of valve to be installed.....	281
15.5.3 Disinfection of fittings and equipment.....	281
15.5.4 Installation of off-take clamp.....	281
15.5.5 Installation of the valve.....	282
15.5.6 Cut-in operation.....	282
15.5.7 Recording and reporting.....	283
15.6 FLOTATION CONTROL.....	283
15.7 THRUST AND ANCHOR BLOCKS AND RESTRAINED JOINTS.....	283
15.8 TAPPING OF MAINS, PROPERTY SERVICES AND WATER METERS.....	284
15.8.1 General.....	284
15.8.2 Tapping the main.....	284
15.8.3 Installation of Property Services.....	285
15.8.3.1 Drinking Water Mains.....	285
15.8.3.2 Dual Water Supply Systems.....	285
15.9 TRENCH STOPS.....	287

15.10 BULKHEADS.....	287
15.11 CORROSION PROTECTION OF DUCTILE IRON.....	287
15.12 MARKING TAPES.....	287
15.12.1 Non-detectable marking tape.....	287
15.12.2 Detectable marking tape.....	287
15.12.3 Tracer wire.....	287
15.13 VALVES, HYDRANTS AND SURFACE BOXES AND FITTINGS.....	287
15.13.1 Installation.....	287
15.13.2 Valve chambers for large diameter mains.....	288
15.14 SCOURS.....	288
15.15 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE.....	288
15.16 AQUEDUCTS.....	289
15.17 BRIDGE CROSSINGS.....	289
15.18 APPURTENANCE LOCATION MARKING.....	289
15.19 FLANGED JOINTS.....	289
15.20 WELDING OF STEEL PIPELINES.....	289
15.20.1 General.....	289
15.20.2 Field welding of flanges.....	290
15.20.3 Reinstatement of cement mortar lining.....	290
15.20.4 Reinstatement of external corrosion protection at joints using a tape system.....	290
15.20.4.1 General.....	290
15.20.4.2 Surface preparation.....	291
15.20.4.3 Priming surfaces.....	291
15.20.4.4 Mastic filler.....	291
15.20.4.5 Tape application.....	291
15.20.5 Reinstatement of external corrosion protection at joints using a heat-shrinkable sleeve system.....	292
15.20.5.1 Surface preparation.....	292
15.20.5.2 Preheat pipe.....	292
15.20.5.3 Priming surfaces.....	292
15.20.5.4 Mastic filler.....	292
15.20.5.5 Heat-shrinkable sleeve preparation.....	293
15.20.5.6 Heat-shrinkable sleeve application.....	293
15.21 WELDING OF PE PIPELINES.....	293
16 PIPE EMBEDMENT AND SUPPORT.....	294
16.1 GENERAL.....	294
16.2 EMBEDMENT MATERIALS.....	294
16.2.1 General.....	294
16.2.2 Recycled, reuse and waste materials.....	294
16.3 COMPACTION OF EMBEDMENT.....	294
16.3.1 Methods.....	294
16.3.2 Compaction trials / Pre-qualification of embedment compaction method.....	295
16.3.2.1 General.....	295
16.3.2.2 Test method.....	295
16.3.2.3 Interpretation and applicability.....	295
16.3.3 Compaction control.....	296

16.4 SPECIAL BEDDING AND EMBEDMENTS / GEOTEXTILE SURROUND AND PILLOW.....	296
16.5 REMOVAL OF TRENCH SUPPORTS.....	296
16.6 CONCRETE EMBEDMENT AND ENCASEMENT.....	296
17 FILL.....	297
17.1 TRENCH FILL.....	297
17.1.1 Material requirements.....	297
17.1.1.1 Trafficable Areas.....	297
17.1.1.2 Non-Trafficable Areas.....	297
17.1.2 Placement.....	298
17.1.3 Compaction of trench fill.....	298
17.2 EMBANKMENT FILL.....	298
17.3 DRIVES AND TUNNEL FILL.....	299
18 SWABBING.....	300
18.1 GENERAL.....	300
18.2 SWABS.....	300
18.3 SWABBING PROCEDURE.....	300
19 ACCEPTANCE TESTING.....	302
19.1 GENERAL.....	302
19.2 VISUAL INSPECTION.....	302
19.3 COMPACTION TESTING.....	302
19.3.1 General.....	302
19.3.2 NOT USED.....	303
19.3.2.1 Not Used.....	303
19.3.2.2 Not Used.....	303
19.3.2.3 Not Used.....	303
19.3.2.4 Not Used.....	303
19.3.2.5 Not Used.....	303
19.3.3 Minimum compaction.....	303
19.3.4 Embedment compaction testing.....	304
19.3.4.1 Applicable pipe sizes.....	304
19.3.4.2 Frequency and location of embedment tests.....	304
19.3.4.3 Retesting.....	304
19.3.5 Trench fill compaction testing.....	304
19.3.5.1 Trafficable areas test zone.....	304
19.3.5.2 Non-trafficable areas test zone.....	305
19.3.5.3 Property services.....	305
19.3.5.4 Frequency and location of tests.....	305
19.3.5.5 Retesting.....	305
19.3.6 Other fill compacting testing.....	305
19.3.6.1 General.....	305
19.3.6.2 Trafficable areas test zone.....	305
19.3.6.3 Non-trafficable areas test zone.....	305
19.3.6.4 Frequency and location of tests.....	306
19.3.6.5 Retesting.....	306
19.4 HYDROSTATIC PRESSURE TESTING.....	306
19.4.1 General.....	306

19.4.2 Mains.....	306
19.4.3 Property services.....	306
19.4.4 Under pressure cut-in connections.....	307
19.4.5 Alternative pressure test.....	307
19.4.5.1 Application.....	307
19.4.5.2 Pipeline extension/connection by inserted tee method.....	308
19.5 BLOCK TESTING DUAL WATER SUPPLY SYSTEMS FOR CONNECTIVITY.....	308
19.6 INSULATED JOINT RESISTANCE TEST.....	309
19.7 WATER QUALITY TESTING.....	309
19.7.1 General.....	309
19.7.2 Test Procedure.....	309
19.7.3 Satisfactory water quality test.....	310
19.7.4 Failure of test.....	310
20 DISINFECTION.....	311
20.1 APPLICATION.....	311
20.2 FLUSHING OF DISINFECTION WATER.....	311
21 TOLERANCES ON AS-CONSTRUCTED WORK.....	313
21.1 GENERAL.....	313
21.2 HORIZONTAL TOLERANCES.....	313
21.2.1 Water mains and in-line structures.....	313
21.2.2 Property services and meters.....	313
21.3 VERTICAL TOLERANCES.....	313
21.3.1 Water mains, property connections and structures.....	313
21.3.2 Verticality ("plumb").....	313
21.4 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS.....	313
21.5 CAST IN-SITU CONCRETE STRUCTURES AND SLABS.....	314
22 CONNECTIONS TO EXISTING WATER MAINS.....	315
22.1 GENERAL.....	315
22.1.1 Preparation for connection to existing water mains.....	315
22.2 UNDER PRESSURE CONNECTIONS.....	316
22.3 INSERTED TEE CONNECTIONS.....	316
22.3.1 Shutdown of existing water mains.....	316
22.3.2 Making the connection to existing water main.....	317
22.3.3 Re-charging the shutdown water main.....	318
22.4 CONNECTION AND/OR CHARGING THE NEW WATER MAINS.....	318
22.5 RECONNECTION OF PROPERTIES SUPPLIED BY TEMPORARY PRIVATE SERVICES.....	318
23 RESTORATION.....	319
23.1 GENERAL.....	319
23.2 PAVEMENTS.....	319
23.3 LAWNS.....	319
23.4 GRASSED AREAS.....	320
23.5 BUSHLAND.....	320
23.6 PROVISION FOR AND RECTIFICATION OF SETTLEMENT.....	320
23.7 MAINTENANCE OF RESTORED SURFACES.....	320
24 WORK AS CONSTRUCTED DETAILS.....	321
PART 3: STANDARD DRAWINGS.....	323

REGW 25 INTRODUCTION.....	323
REGW 25.1 GENERAL.....	323
REGW 25.2 DRAWING COMMENTARY.....	323
REGW 26 LIST OF DRAWINGS.....	325
REGW 27 COMMENTARY ON WAT–1100 SERIES-PIPELINE LAYOUT.....	332
REGW 27.1 GENERAL.....	332
REGW 27.2 WAT–1100, WAT–1101 DESIGN LAYOUT.....	332
REGW 27.2.1 WAT–1100-1 Typical locality plan.....	332
REGW 27.2.2 WAT–1100-2 Typical site plan.....	332
REGW 27.2.3 WAT–1101-2 and WAT-1101-3 Typical Water Reticulation design plan, details and notes.....	332
REGW 27.3 WAT-1102, WAT-1103, WAT-1104, WAT-1105 - Typical mains construction.....	332
REGW 27.3.1 WAT-1102 - Reticulation main arrangements.....	333
REGW 27.3.2 WAT-1103 Distribution and transfer mains.....	333
REGW 27.3.3 WAT 1104 - DN 63 PE cul-de-sac arrangement.....	333
REGW 27.3.4 WAT-1105 Connection to existing mains.....	333
REGW 27.4 WAT-1106 and WAT-1107 Property services – Main-to-meter.....	333
REGW 27.5 WAT-1108 Property Services - Connection to main.....	334
REGW 27.6 WAT–1109 - PROPERTY SERVICES - ABOVE GROUND METER ASSEMBLY ARRANGEMENT.....	334
REGW 27.7 WAT–1150 - WATER MAIN SYMBOLS.....	335
REGW 27.8 WAT–1151 AND WAT–1152 - DESIGN LAYOUTS – UTILITY SERVICES – SPACE ALLOCATIONS IN FOOTWAYS.....	335
REGW 28 COMMENTARY ON WAT–1200 SERIES - EMBEDMENT, TRENCH FILL AND RESTRAINTS.....	336
REGW 28.1 GENERAL.....	336
REGW 28.2 WAT–1200 SOIL CLASSIFICATION GUIDELINES.....	337
REGW 28.3 WAT–1201 EMBEDMENT AND TRENCH FILL.....	337
REGW 28.4 WAT–1202 STANDARD EMBEDMENT – ALL PIPE TYPES.....	338
REGW 28.5 WAT–1203 SPECIAL EMBEDMENTS – INADEQUATE AND POOR FOUNDATION.....	338
REGW 28.6 WAT-1204 SPECIAL EMBEDMENTS – CONCRETE, GEOTEXTILE AND CEMENT STABILISED SYSTEMS.....	338
REGW 28.7 WAT-1205 THRUST BLOCK DETAILS – CONCRETE BLOCKS.....	338
REGW 28.8 WAT-1206 THRUST BLOCK DETAILS – TIMBER & RECYCLED PLASTIC BLOCKS.....	339
REGW 28.9 WAT-1207 THRUST AND ANCHOR BLOCKS – GATE VALVES AND VERTICAL BENDS.....	339
REGW 28.10 WAT-1208 RESTRAINED JOINT SYSTEM – DN 100 TO DN 375 DI MAINS.....	339
REGW 28.11 WAT-1209 TRENCH DRAINAGE – BULKHEADS AND TRENCHSTOP.....	339
REGW 28.12 WAT-1210 TRENCH DRAINAGE – TYPICAL SYSTEMS.....	339
REGW 28.13 WAT-1211, WAT-1212, WAT-1213 AND WAT-1214 - BURIED CROSSINGS.....	339
REGW 28.14 WAT-1250 AND WAT-1251 – STANDARD TRENCH DETAILS.....	340
REGW 28.15 WAT-1252 – THRUST BLOCK DETAILS.....	340
REGW 28.16 WAT-1253 AND WAT-1254 – ANCHORAGE DETAILS – STOP VALVE INSTALLATIONS.....	340

REGW 29 COMMENTARY ON WAT-1300 SERIES - INSTALLATION PRACTICES /	
STRUCTURES.....	341
REGW 29.1 GENERAL.....	341
REGW 29.2 WAT-1300 VALVE AND HYDRANT IDENTIFICATION.....	341
REGW 29.3 WAT-1301 AND WAT-1302 TYPICAL VALVE, HYDRANT AND AIR VALVE	
INSTALLATION.....	341
REGW 29.4 WAT-1303, WAT-1304, WAT-1305 AND WAT-1306 – TYPICAL SURFACE FITTING	
INSTALLATION.....	341
REGW 29.5 WAT-1307 – TYPICAL APPURTENANCE (SCOUR) INSTALLATION.....	341
REGW 29.6 WAT-1308 – TYPICAL APPURTENANCE (VALVE CHAMBER AND BY-PASS)	
INSTALLATION.....	342
REGW 29.7 WAT-1309-1, WAT-1309-2, WAT-1309-3, WAT-1309-4, WAT-1310-1, WAT-1310-2,	
AND WAT-1310-3 TYPICAL PRESSURE REDUCING VALVE AND FLOW METER	
INSTALLATION.....	342
REGW 29.8 WAT-1310-4 TYPICAL APPURTENANCE FLOWMETER DETAILS.....	342
REGW 29.9 WAT-1313 TYPICAL BOLTING DETAILS.....	342
REGW 29.10 WAT-1314-1, WAT-1315-1, WAT-1316-1 AND WAT-1317-1 TYPICAL INSTALLATION	
FOR SMALL WATER SUPPLY PUMP STATION.....	343
REGW 29.11 WAT-1318-1 TYPICAL ARRANGEMENT MAIN SWABBING CHAMBER.....	343
REGW 29.12 WAT-1320, WAT-1321 AND WAT-1322 – AERIAL CROSSINGS.....	343
REGW 29.13 WAT-1319-1, WAT-1319-2, WAT-1319-3, WAT-1319-4 FALL PREVENTION COVERS	
AND GRATES AT WATER PUMPING STATIONS DRAWING INDEX, NOTES AND	
LEGEND.....	343
REGW 29.14 WAT-1350 AND WAT-1351– TYPICAL APPURTENANCE (VALVE)	
INSTALLATION.....	343
REGW 29.15 WAT-1352 AND WAT-1353– MARKING SYSTEMS – INDICATOR PLATES.....	344
REGW 29.16 WAT-1354 – POTENTIALLY UNSTABLE / LANDSLIP AREAS– MONITORING	
PITS.....	344
REGW 29.17 WAT-1355 – AERIAL CROSSING - CIRCULAR RC PIERS IN NON-FLOOD	
CONDITIONS.....	344
REGW 30 COMMENTARY ON WAT-1400 SERIES - FABRICATION DETAILS.....	345
REGW 30.1 GENERAL.....	345
REGW 30.2 WAT-1400 – TYPICAL STEEL PIPE JOINTING – BUTT WELDING OF JOINTS.....	345
REGW 30.3 WAT-1401 – TYPICAL STEEL PIPE JOINTING – RRJ SPIGOT BANDS.....	345
REGW 30.4 WAT-1402 – TYPICAL STEEL PIPE JOINTING – WELDED PIPE COLLARS.....	345
REGW 30.5 WAT-1403 – TYPICAL STEEL FABRICATION – BENDS.....	345
REGW 30.6 WAT-1404 – TYPICAL STEEL FABRICATION – ACCESS OPENINGS.....	346
REGW 30.7 WAT-1405 – TYPICAL STEEL FABRICATION – DISMANTLING AND FLEXIBLE	
JOINTS.....	346
REGW 30.8 WAT-1406 AND WAT-1407 – VALVE CONNECTION & BY-PASS	
ARRANGEMENTS.....	346
REGW 30.9 WAT-1408 – JOINT CORROSION PROTECTION.....	346
REGW 30.10 WAT-1409 – HYDRANT INSTALLATION FITTINGS – PE ASSEMBLIES.....	346
REGW 30.11 WAT-1410 – TYPICAL CHLORINATION TEST POINT.....	346
REGW 31 COMMENTARY ON WAT-1800 SERIES - DUAL WATER SUPPLY SYSTEMS.....	347
REGW 31.1 GENERAL.....	347

REGW 31.2 WAT-1850 and WAT-1851 TYPICAL MAINS CONSTRUCTION – MAIN ARRANGEMENT FOR DUAL WATER SUPPLY.....	347
REGW 31.3 WAT-1852 AND WAT-1853 PROPERTY SERVICES - STANDARD TAPPING METHODS.....	347
REGW 31.4 WAT-1854 AND WAT-1855 TYPICAL ABOVE-GROUND METER ARRANGEMENT.....	348
REGW 31.5 WAT-1856, WAT-1857-1 AND WAT-1857-2 PROPERTY SERVICES - TYPICAL SERVICE LAYOUTS AND ALTERNATIVE MARKING SYSTEMS.....	348
REGW 31.6 WAT-1858 TYPICAL MAINS CONSTRUCTION – MAIN ARRANGEMENT FOR CUL-DE-SACS AND COURT BOWLS.....	349
REGW 31.7 WAT-1859 TYPICAL MAIN CONSTRUCTION - MAIN ARRANGEMENT OFFTAKE MAIN DETAILS.....	349
REGW 31.8 WAT-1860 TYPICAL APPURTENANCE INSTALLATION DRINKING WATER AND RECYCLED WATER GATE VALVE /HYDRANT ARRANGEMENT.....	349
REGW 31.9 WAT-1861 MARKING SYSTEM INDICATOR PLATES FOR LOCATING HYDRANTS.....	350
REGW 31.10 WAT-1862 VALVE IDENTIFICATION - IDENTIFICATION AND MARKERS AND MARKER POST.....	350
REGW 31.11 WAT-1863 EMBEDMENT AND TRENCH FILL - MAIN ARRANGEMENT FOR DUAL WATER SUPPLY SYSTEMS.....	350
REGW 31.12 WAT-1864 TYPICAL APPURTENANCE INSTALLATION - HYDRANT VALVE AND FLUSHING INSTALLATION ON PE MAINS USING COMPRESSION FITTINGS.....	351
REGW 31.13 WAT-1865 TYPICAL APPURTENANCE INSTALLATION - HYDRANT VALVE AND FLUSHING INSTALLATION ON PE MAINS USING ELECTROFUSION FITTINGS.....	351
REGW 31.14 WAT-1866 TYPICAL APPURTENANCE INSTALLATION - TEMPORARY CROSS CONNECTIONS.....	351
REGW 31.15 WAT-1867 - TYPICAL RECYCLED WATER SURFACE FITTINGS- MARKING AND COLOUR IDENTIFICATION.....	352
REGW 32 REGIONAL NSW WATER EDITION - VERSION 2 DRAWINGS.....	353
WAT-1100 SERIES - PIPELINE LAYOUT.....	353
DESIGN LAYOUT.....	353
WATER RETICULATION - DESIGN LAYOUT.....	353
TYPICAL MAINS CONSTRUCTION.....	357
PROPERTY SERVICES.....	361
WATER CONNECTIONS.....	364
WATER MAIN SYMBOLS.....	365
DESIGN LAYOUTS.....	366
WAT-1200 SERIES - EMBEDMENT / TRENCHFILL AND RESTRAINTS.....	368
SOIL CLASSIFICATION GUIDELINES.....	368
EMBEDMENT & TRENCHFILL.....	369
STANDARD EMBEDMENT	370
SPECIAL EMBEDMENTS.....	371
TRENCH AND BEDDING DETAILS.....	372
THRUST AND ANCHOR BLOCKS.....	373
THRUST BLOCK DETAILS.....	373
THRUST AND ANCHOR BLOCKS.....	374

RESTRAINED JOINT SYSTEM.....	375
TRENCH DRAINAGE.....	376
BURIED CROSSINGS.....	378
STANDARD TRENCH DETAIL.....	382
THRUST BLOCK DETAILS.....	384
ANCHORAGE DETAILS.....	385
BURIED CROSSINGS.....	387
WAT-1300 SERIES - INSTALLATION PRACTICES / STRUCTURES.....	388
IDENTIFICATION ROADMARKERS AND MARKER POSTS.....	388
TYPICAL ROAD AND PAVEMENT MARKERS.....	388
TYPICAL VALVE AND HYDRANT INSTALLATION.....	389
TYPICAL SURFACE FITTING INSTALLATION.....	390
TYPICAL APPURTENANCE INSTALLATION.....	394
FLANGED JOINTS.....	404
AERIAL CROSSINGS.....	405
TYPICAL AERIAL CROSSINGS.....	406
AERIAL CROSSINGS.....	407
PUMP STATION OR RESERVOIR.....	408
TYPICAL SMALL WATER SUPPLY.....	408
SWABBING CHAMBER.....	412
TYPICAL ARRANGEMENT.....	412
FALL PREVENTION COVERS AND GRATES AT WATER PUMPING STATIONS.....	413
TYPICAL APPURTENANCE INSTALLATION.....	417
MARKING SYSTEMS.....	419
POTENTIALLY UNSTABLE/LANDSLIP AREAS.....	421
AERIAL CROSSINGS.....	422
WAT-1400 SERIES - FABRICATION DETAILS.....	423
TYPICAL STEEL PIPE JOINTING.....	423
TYPICAL STEEL FABRICATION.....	426
TYPICAL STEEL PIPE JOINTING.....	426
TYPICAL STEEL FABRICATION.....	427
DI INSTALLATION.....	430
JOINT CORROSION PROTECTION.....	431
TYPICAL JOINT CORROSION PROTECTION.....	431
TYPICAL PE ASSEMBLIES.....	432
HYDRANT INSTALLATION FITTINGS.....	432
CHLORINATION TEST POINT.....	433
TYPICAL CHLORINATION TEST POINT.....	433
WAT-1800 SERIES - DUAL WATER SUPPLY SYSTEM.....	434
TYPICAL MAINS CONSTRUCTION.....	434
PROPERTY SERVICES.....	436
Single Property Services.....	438
Twin Property Services.....	439
Single or Twin Property Services.....	440
Property Services.....	441
TYPICAL MAINS CONSTRUCTION.....	443

TYPICAL APPURTENANCE INSTALLATION.....	445
MARKING SYSTEMS.....	446
THRUST BLOCK DETAILS.....	448
TYPICAL APPURTENANCE INSTALLATION.....	449
TYPICAL RECYCLED WATER SURFACE FITTINGS.....	452
APPENDICES.....	453
APPENDIX A — GENERIC INFRASTRUCTURE PROTECTION GUIDANCE.....	453
A1 INFRASTRUCTURE PROTECTION TREATMENTS - SELECTION AND DEFINITION.....	453
A2 RISK MANAGEMENT - INFRASTRUCTURE PROTECTION RISK ASSESSMENTS.....	453
A3 INFRASTRUCTURE PROTECTION DESIGN CONSIDERATIONS.....	453
A4 INFRASTRUCTURE PROTECTION TREATMENTS.....	454
A5 SECURITY DESIGN CONCEPTS.....	454
A6 ENVIRONMENTAL DESIGN CONSIDERATIONS.....	454
A7 WATER MAIN FAILURE IMPACT ASSESSMENT.....	455
A8 WATER AGENCY’S ENVIRONMENTAL AESTHETICS GUIDANCE.....	456
APPENDIX B — EQUIVALENT PIPE SIZES FOR COMMONLY USED MATERIALS.....	464
APPENDIX C — UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80.....	468
C1 GENERAL.....	468
C1.1 SCOPE.....	468
C1.2 PURPOSE.....	468
C1.3 APPLICATIONS FOR UPCIC.....	468
C1.3.1 Pipe materials.....	468
C1.3.2 Off-take clamps.....	469
C1.3.3 Connections.....	469
C1.4 INTERPRETATIONS.....	470
C2 PLANNING.....	470
C2.1 WATER AGENCY LIMITATIONS.....	470
C2.2 GENERAL LIMITATIONS.....	470
C2.3 DESKTOP REVIEW.....	471
C3 DESIGN.....	471
C3.1 HYDRAULIC.....	471
C3.1.1 Size of drilled hole.....	471
C3.1.2 Calculation of headloss.....	471
C3.2 STRUCTURAL.....	472
C3.3 SPACING OF CUT-IN CONNECTION HOLES AND LOCATION OF OFF-TAKES.....	472
C3.3.1 Spacing distances.....	472
C3.3.2 Off-take clamp locations.....	473
C3.4 HOLE/OFF-TAKE BRANCH SIZE LIMITATION.....	473
C3.5 THRUST BLOCKS.....	473
C3.6 COVER OVER THE INSTALLED GATE VALVE.....	473
ANNEXURE 1 — PERMITTED CUTTER SIZES AND CLAMP LENGTHS.....	474
APPENDIX D — BOOSTER CONFIGURATION.....	482
APPENDIX E — SELECTION OF PRESSURE ACCUMULATOR TANKS.....	511
E1 SCOPE.....	511
E2 REFERENCED DOCUMENTS.....	511
E3 TANK TYPE.....	511

E4 TANK STANDARDS.....	511
E5 DESIGN LIMITATIONS.....	511
E6 PRODUCT AVAILABILITY.....	512
E7 TANK REQUIREMENTS.....	512
E8 MAINTENANCE.....	513
APPENDIX F — GUIDELINES FOR WATER MAINS IN SLIP AND POTENTIALLY UNSTABLE AREAS.....	514
F1 INTRODUCTION.....	514
F2 SLIP AND UNSTABLE AREAS.....	514
F2.1 GENERAL.....	514
F2.2 GREATER SYDNEY REGION.....	515
F3 FACTORS INFLUENCING STABILITY OF SLOPES.....	515
F3.1 SOIL AND ROCK CONDITION.....	515
F3.2 ANGLE OF SLOPE.....	515
F3.3 GROUNDWATER AND SURFACE WATER.....	515
F3.4 RESIDENTIAL DEVELOPMENT.....	515
F3.5 VEGETATION.....	515
F3.6 ROAD CONSTRUCTION.....	516
F4 IDENTIFICATION OF POTENTIALLY UNSTABLE AREAS.....	516
F4.1 GENERAL.....	516
F4.2 GREATER SYDNEY REGION.....	516
F5 PRECAUTIONS.....	516
F5.1 GENERAL.....	516
F5.2 AVOIDANCE.....	517
F5.3 SHALLOW TRENCH OR ABOVE-GROUND CONSTRUCTION.....	517
F5.4 ALTERNATIVE CONSTRUCTION TECHNIQUES.....	517
F5.5 DESIGN FOR POSSIBLE GROUND MOVEMENT.....	517
F5.6 CONSIDER GROUNDWATER AND DRAINAGE.....	520
F5.7 PRECAUTIONS DURING CONSTRUCTION.....	521
APPENDIX G — SOIL CLASSIFICATION GUIDELINES AND ALLOWABLE BEARING PRESSURES FOR ANCHORS AND THRUST BLOCKS.....	523
G1 GENERAL.....	523
G2 IDENTIFICATION GUIDANCE.....	523
G2.1 Identifying clay soils.....	523
G3 FIELD TEST METHODS.....	523
G3.1 Preparing the test area.....	523
G3.2 Testing clay soils.....	523
G3.3 Testing clean sand soils.....	523
G3.4 Testing rock.....	523
APPENDIX H — HYDRANT SPACINGS.....	526
H1 SCOPE.....	526
APPENDIX I — DISINFECTION OF WATER MAINS AND WATER QUALITY COMPLIANCE SPECIFICATION.....	527
I1 SCOPE.....	527
I2 PURPOSE.....	527
I3 SUMMARY OF REQUIREMENTS.....	527

I4 PREVENTIVE MEASURES.....	528
I4.1 General.....	528
I4.2 Keeping items clean and dry.....	528
I4.2.1 Storage.....	528
I4.2.2 Temporary capping during construction.....	528
I4.3 Cleaning methods.....	528
I5 DISINFECTION AND NEUTRALISATION OF DISINFECTANT.....	529
I5.1 General.....	529
I5.2 Safety.....	531
I6 SAMPLING.....	531
I6.1 General.....	531
I6.2 Sample set A – Existing main.....	531
I6.3 Sample set B – New main.....	531
I7 TESTS.....	532
I8 ACCEPTANCE OF TEST RESULTS.....	532
I8.1 All results – Sample set A (existing) and set B (new mains).....	532
I8.2 Non-compliant results for sample set A – existing main.....	532
I8.3 Non-compliant results for sample set B – New main.....	532
I9 NOTIFICATION.....	532
ANNEXURE 1 — DRINKING WATER / NON DRINKING WATER.....	533
Drinking Water.....	533
Non-Drinking Water.....	534
ANNEXURE 2 — RECOGNISED TESTING LABORATORY AND ANALYSIS.....	535
ANNEXURE 3 — FLOWCHART - WATER QUALITY COMPLIANCE FOR NEW MAINS.....	537
APPENDIX J — SAFETY ASSURANCE PLAN AND JOB SAFETY ANALYSIS.....	538
J1 SAFETY ASSURANCE PLAN.....	538
J2 JOB SAFETY ANALYSIS (JSA).....	538
APPENDIX K — CONNECTIVITY INSPECTION OF DUAL WATER SUPPLY SYSTEMS.....	540
K1 PRINCIPLE.....	540
K2 PROCEDURE.....	540
Abbreviations.....	542
Definitions.....	543

List of Figures

Figure 1.1 TYPICAL WATER SUPPLY SYSTEM.....	71
Figure 2.1 SINGLE TRANSFER / DISTRIBUTION MAIN, MINOR NETWORK AND DEAD-END BRANCH MAINS (not preferred due to low turn-over in dead-end mains).....	85
Figure 2.2 SINGLE TRANSFER / DISTRIBUTION MAIN, NETWORK WITH MULTIPLE DISTRIBUTION MAINS AND BRANCH MAINS WITH LOOPED REDUCED DIAMETER DEAD-ENDS.....	85
Figure 2.3 TWIN TRANSFER/ DISTRIBUTION MAINS, NETWORK WITH MULTIPLE DISTRIBUTION MAINS, LOOPED MAINS AND LINK MAINS TO MINIMISE DEAD-ENDS, SOME REDUCED DIAMETER DEAD-END MAINS AND STAGING OF PROVISION OF MAINS.....	85
Figure 2.4 TYPICAL WATER SUPPLY PUMPING STATION ARRANGEMENTS.....	93
Figure 4.1 NOT USED.....	114
Figure 4.2 NOT USED.....	119
Figure 4.3 NOT USED.....	124

Figure 4.4 NOT USED.....	125
Figure 4.5 NOT USED.....	125
Figure 5.1 LOOPED AND LINK MAINS.....	129
Figure 5.2 DESIGN REQUIREMENTS FOR REDUCED SIZED MAINS IN COURT BOWLS, CUL-DE-SACS AND DEAD-ENDS.....	131
Figure 5.3 NOT USED.....	136
Figure 5.4 TYPICAL SHARED / COMBINED TRENCH INSTALLATION.....	144
Figure 5.5 TYPICAL SHARED / COMBINED TRENCH INSTALLATION OFF-TAKE.....	145
Figure 5.6 TYPICAL UNDER PRESSURE CUT-IN CONNECTION METHOD USING A SPLIT SS CLAMP WITH FLANGED OFF-TAKE – PLAN VIEW.....	147
Figure 5.7 TYPICAL INSERTION TEE METHOD USING MECHANICAL COUPLINGS – PLAN VIEW.....	148
Figure 5.8 TYPICAL FLUSHING ASSEMBLY DETAILS FOR ENDS OF REDUCED SIZED MAINS.....	150
Figure 5.9 NOT USED.....	152
Figure 5.10 NOT USED.....	152
Figure 5.11 NOT USED.....	152
Figure 5.12 HORIZONTAL DEVIATION BY DEFLECTION AT PIPE JOINTS – PLAN VIEW.....	155
Figure 5.13 HORIZONTAL DEFLECTION USING A DI SOC-SOC CONNECTOR AND PERMITTED JOINT DEFLECTIONS FOR DI PIPES AND OTHER APPLICABLE PIPE TYPES – PLAN VIEW.....	156
Figure 5.14 DEFLECTION USING DI BENDS WITH DI AND OTHER PERMITTED PIPE TYPES - PLAN VIEW.....	156
Figure 5.15 VERTICAL DEVIATION BY DEFLECTION AT PIPE JOINTS – SECTION VIEW.....	157
Figure 5.16 VERTICAL DEVIATION USING DI BENDS – SECTION VIEW.....	157
Figure 5.17 TYPICAL ANCHOR BLOCK DETAIL FOR VERTICAL BENDS.....	158
Figure 5.18 VERTICAL DEFLECTIONS USING FABRICATED PIPE AND FLANGES – SECTION VIEW.....	158
Figure 5.19 VERTICAL DEFLECTIONS USING DOUBLE OFFSET FABRICATED PIPE AND FLANGES – SECTION VIEW.....	159
Figure 6.1 TYPICAL PRE-COMMISSIONING AND COMMISSIONING PROCESS.....	168
Figure 6.2 TYPICAL HANDOVER TO WATER AGENCY.....	169
Figure 7.1 NOT USED.....	186
Figure 7.2 TYPE A EMBEDMENT SUPPORT.....	188
Figure 7.3 TYPE B EMBEDMENT SUPPORT.....	188
Figure 7.4 TYPE C AND D EMBEDMENT SUPPORT.....	190
Figure 7.5 TYPE E EMBEDMENT SUPPORT.....	190
Figure 7.6 TYPE F EMBEDMENT SUPPORT.....	191
Figure 7.7 TYPE G EMBEDMENT SUPPORT.....	191
Figure 7.8 TYPE H EMBEDMENT SUPPORT.....	192
Figure 7.9 TYPE J AND K CONCRETE ENCASEMENT EMBEDMENT SUPPORT.....	194
Figure 7.10 ALTERNATIVE END TREATMENT FOR CONCRETE ENCASED STEEL PIPELINES.....	195
Figure 7.11 NOT USED.....	199
Figure 7.12 NOT USED.....	199
Figure 7.13 NOT USED.....	199
Figure 7.14 NOT USED.....	200
Figure 7.15 TYPICAL CONCRETE THRUST BLOCK FOR SOCKETED VALVES.....	200
Figure 7.16 NOT USED.....	201

Figure 7.17 TYPICAL VALVE RESTRAINT MECHANISM.....	201
Figure 7.18 NOT USED.....	201
Figure 7.19 NOTE USED.....	203
Figure 7.20 NOT USED.....	203
Figure 7.21 NOT USED.....	203
Figure 7.22 NOT USED.....	203
Figure 7.23 NOT USED.....	204
Figure 7.24 NOT USED.....	204
Figure 7.25 NOT USED.....	204
Figure 8.1 PLASTICS IDENTIFICATION COVER.....	208
Figure 8.2 TYPICAL GATE VALVE AND HYDRANT INSTALLATION AT STANDARD DEPTH.....	210
Figure 8.3 TYPICAL GATE VALVE INSTALLATION AT DEEPER THAN STANDARD DEPTH.....	211
Figure 8.4 TYPICAL VALVE CHAMBER ARRANGEMENT FOR DN 500 AND DN 600 MAINS – PLAN VIEW.....	212
Figure 8.5 TYPICAL VALVE CHAMBER ARRANGEMENT FOR A DN 750 MAIN – PLAN VIEW.....	213
Figure 8.6 TYPICAL VALVE CHAMBER ARRANGEMENT – CROSS SECTION.....	214
Figure 8.7 BYPASS ARRANGEMENT WITH L-TYPE BALL HYDRANT.....	217
Figure 8.8 BRANCH VALVE ADJACENT TO MAIN.....	218
Figure 8.9 BRANCH VALVE ADJACENT TO INNER SPLAY CORNER.....	219
Figure 8.10 VALVE AND HYDRANT COMBINATIONS.....	219
Figure 8.11 VALVE ADJACENT TO A TAPER.....	219
Figure 8.12 VALVES IN MAIN CROSS-LINKS.....	220
Figure 8.13 VALVES IN CONJUNCTION WITH CONTROL VALVES.....	220
Figure 8.14 TWO DIRECTION SUPPLY.....	221
Figure 8.15 OFF-TAKE ARRANGEMENT FOR RIDER MAINS.....	222
Figure 8.16 INTERCONNECTION OF DN 200 AND DN 225 CROSSING MAINS.....	222
Figure 8.17 INTERCONNECTION OF RETICULATION AND DISTRIBUTION MAINS.....	223
Figure 8.18 INTERCONNECTION OF DISTRIBUTION MAINS.....	223
Figure 8.19 INTERCONNECTION OF A CONTINUING RETICULATION MAIN AND LARGER MAIN.....	224
Figure 8.20 TYPICAL PRESSURE REDUCING VALVE INSTALLATION - SECTIONAL ELEVATION.....	226
Figure 8.21 ALTERNATIVE ABOVE-GROUND INSTALLATION – PRV ON BYPASS – SIDE ELEVATION.....	226
Figure 8.22 PRV ON MAIN LINE WITH BYPASS - PLAN VIEW.....	227
Figure 8.23 TYPICAL AIR VALVE ORIENTATION.....	230
Figure 8.24 TYPICAL AIR VALVE INSTALLATION.....	231
Figure 8.25 SCOUR DETAIL.....	233
Figure 8.26 SCOUR DISCHARGE TO APPROVED DRAINAGE SYSTEM.....	233
Figure 8.27 SCOUR DISCHARGE COLLECTION/PUMP-OUT SUMP.....	234
Figure 8.28 SCOUR DISCHARGE TO STORAGE LAGOON.....	234
Figure 8.29 SPRING HYDRANT-TYPICAL DIRECT CONNECTION.....	238
Figure 8.30 ISOLATING VALVE ASSEMBLY WITH SPRING HYDRANT.....	238
Figure 8.31 TYPICAL HYDRANT INSTALLATION IN NON-TRAFFICABLE LOCATION.....	239
Figure 8.32 TYPICAL HYDRANT INSTALLATION IN TRAFFICABLE ASPHALTIC CONCRETE PAVEMENT.....	240

Figure 8.33 TYPICAL HYDRANT WITH ISOLATING VALVE INSTALLATION WITH SPRING HYDRANT OPTION IN NON-TRAFFICABLE LOCATIONS.....	240
Figure 8.34 TYPICAL OFFSETTING OF HYDRANTS IN FOOTWAY.....	241
Figure 8.35 NON-TRAFFICABLE STOP VALVE SURFACE BOX.....	244
Figure 8.36 TYPICAL TRAFFICABLE STOP VALVE SURFACE BOXES.....	245
Figure 8.37 TYPICAL TRAFFICABLE HYDRANT SURFACE BOXES.....	246
Figure 8.38 RETRO-REFLECTIVE PAVEMENT MARKERS.....	247
Figure 8.39 KERB MARKINGS.....	248
Figure 13.1 TYPICAL EXCAVATION DIMENSIONS.....	273
Figure 15.1 NOT USED.....	291
Figure 15.2 NOT USED.....	291
Figure 15.3 NOT USED.....	292
Figure 15.4 NOT USED.....	292
Figure 15.5 CML/FBPE WELDED JOINT (CLPEWJ).....	292
WAT-1100-1 TYPICAL LOCALITY PLAN SHEET 1.....	353
WAT-1100-2 TYPICAL LOCALITY PLAN AND DETAILS SHEET 1	354
WAT-1101-2 TYPICAL DESIGN PLAN AND DETAILS SHEET 2.....	355
WAT-1101-3 TYPICAL DESIGN PLAN NOTES SHEET 3.....	356
WAT-1102 RETICULATION MAIN ARRANGEMENTS.....	357
WAT-1103 DISTRIBUTION AND TRANSFER MAIN ARRANGEMENTS.....	358
WAT-1104 DN63 PE CUL-DE-SAC ARRANGEMENT.....	359
WAT-1105 RETICULATION MAIN ARRANGEMENT.....	360
WAT-1106 SINGLE SERVICE MAIN TO METER.....	361
WAT-1107 SPLIT SERVICE MAIN TO METER.....	362
WAT-1108 POTABLE SERVICE CONNECTION CONDUIT DETAILS	363
WAT-1109 SINGLE, DOUBLE AND GHOST ABOVE GROUND METER.....	364
WAT-1150 WATER MAIN SYMBOLS.....	365
WAT-1151 UTILITY SERVICES – SPACE ALLOCATIONS IN FOOTWAYS – STREETS DEDICATED PRIOR TO 1ST JANUARY 1991.....	366
WAT-1152 UTILITY SERVICES – SPACE ALLOCATIONS IN FOOTWAYS DEDICATED AFTER 1-1-'91 AND COVER TO SERVICES.....	367
WAT-1200 AND ALLOWABLE BEARING PRESSURES FOR ANCHORS & THRUST BLOCKS.....	368
WAT-1201 TYPICAL ARRANGEMENT.....	369
WAT-1202 ALL PIPE TYPES.....	370
WAT-1203 INADEQUATE AND POOR FOUNDATION.....	371
WAT-1204 WITHIN EXISTING ROADS TYPE K TO N.....	372
WAT-1205 CONCRETE BLOCKS.....	373
WAT-1207 FOR VERTICAL BENDS.....	374
WAT-1208 DN 100 TO DN 375 DI MAINS.....	375
WAT-1209 BULKHEADS AND TRENCHSTOP.....	376
WAT-1210 TRENCH SYSTEMS.....	377
WAT-1211 UNDER OBSTRUCTIONS.....	378
WAT-1212 MAJOR ROADWAYS.....	379
WAT-1213 RAILWAYS.....	380
WAT-1214 BORED AND JACKED ENCASING PIPE DETAILS.....	381
WAT-1250 RETICULATION MAINS DN 100 TO DN 375.....	382

WAT-1251 TRANSFER AND DISTRIBUTION MAINS DN 300 TO DN 750.....	383
WAT-1252 DN 450 TO DN 750.....	384
WAT-1253 STOP VALVE INSTALLATIONS UP TO DN 1200 SCL MAINS.....	385
WAT-1254 STOP VALVE INSTALLATIONS UP TO DN 750 DICL MAINS.....	386
WAT-1255 UNDER MINOR OBSTRUCTIONS.....	387
WAT-1300 IDENTIFICATION MARKERS FOR VALVES HYDRANTS AND WATER MAIN ROAD CROSSINGS.....	388
WAT-1301 VALVE ARRANGEMENT.....	389
WAT-1302 HYDRANTS AND AIR RELIEF VALVES.....	389
WAT-1303 GATE VALVE SURFACE BOXES NON TRAFFICABLE.....	390
WAT-1304 VALVE CHAMBERS.....	391
WAT-1305 HYDRANT SURFACE BOXES TRAFFICABLE AND NON TRAFFICABLE.....	392
WAT-1306 HYDRANT SURFACE BOXES TRAFFICABLE.....	393
WAT-1307 SCOUR ARRANGEMENTS.....	394
WAT-1308 VALVE CHAMBERS.....	395
WAT-1309-1 PASSIVE PRESSURE REDUCING VALVES (PRV).....	396
WAT-1309-2 ACTIVE PRESSURE REDUCING VALVES (PRV) ON 100 TO DN300.....	397
WAT-1309-3 ACTIVE PRESSURE REDUCING VALVES (PRV) DN100 AND DN150.....	398
WAT-1309-4 ACTIVE PRESSURE REDUCING VALVES (PRV) DN200 TO DN300.....	399
WAT-1310-1 ACTIVE PRESSURE REDUCING VALVES (PRV) ABOVE GROUND.....	400
WAT-1310-2 ACTIVE PRESSURE REDUCING VALVES (PRV) ABOVE GROUND.....	401
WAT-1310-3 ACTIVE PRESSURE REDUCING VALVES (PRV) ABOVE GROUND CABINET DETAILS.....	402
WAT-1310-4 FLOWMETER DETAILS BELOW GROUND INSTALLATION.....	403
WAT-1313 TYPICAL BOLTING DETAILS.....	404
WAT-1320 TYPICAL AQUEDUCT.....	405
WAT-1321 AQUEDUCT PROTECTION GRILLE.....	406
WAT-1322 TYPICAL BRIDGE CROSSING CONCEPTS.....	407
WAT-1314-1 PUMP STATION OR RESERVOIR DRAWING 1 OF 4.....	408
WAT-1315-1 PUMP STATION OR RESERVOIR DRAWING 2 OF 4.....	409
WAT-1316-1 PUMP STATION OR RESERVOIR DRAWING 3 OF 4.....	410
WAT-1317-1 PUMP STATION OR RESERVOIR DRAWING 4 OF 4.....	411
WAT-1318-1 MAIN SWABBING CHAMBER.....	412
WAT-1319-1 DRAWING INDEX, NOTES AND LEGEND.....	413
WAT-1319-2 GENERAL ARRANGEMENTS AND OPENING AND CLOSING SEQUENCE.....	414
WAT-1319-3 CROSS SECTIONS AND DETAILS SHEET 1 OF 2.....	415
WAT-1319-4 CROSS SECTIONS AND DETAILS SHEET 2 OF 2.....	416
WAT-1350 VALVE GEARBOX CHAMBER FOR VERTICAL TYPE SLUICE VALVE AND BYPASS IN FOOTWAY.....	417
WAT-1351 VALVE GEARBOX CHAMBER FOR VERTICAL TYPE SLUICE VALVE AND BYPASS IN CARRIAGEWAY.....	418
WAT-1352 INDICATOR PLATES FOR LOCATING HYDRANTS.....	419
WAT-1353 INDICATOR PLATES FOR LOCATING VALVES.....	420
WAT-1354 MONITORING PITS FOR DN 100 AND DN 150 RETICULATION MAINS IN ROAD RESERVES.....	421
WAT-1355 CIRCULAR R.C. PIERS IN NON-FLOOD CONDITIONS FOR DN100 TO 750 MAINS.....	422

WAT-1400 BUTT WELDING OF JOINTS.....	423
WAT-1401 RUBBER RING JOINT SPIGOT BAND SPECIALS.....	424
WAT-1402 WELDED PIPE COLLARS.....	425
WAT-1403 BENDS.....	426
WAT-1404 ACCESS OPENING FOR PIPES \geq DN 750.....	427
WAT-1405 DISMANTLING AND FLEXIBLE JOINTS.....	428
WAT-1406 VALVE CONNECTION AND BYPASS.....	429
WAT-1407 VALVE BYPASS ARRANGEMENT TYPICAL DI PIPE FITTINGS.....	430
WAT-1408 CEMENT MORTAR LINED STEEL PIPE $>$ DN 750 TO DN 1200.....	431
WAT-1409 TYPICAL PE ASSEMBLIES NOMENCLATURE.....	432
WAT-1410 DETAILS.....	433
WAT-1850 Reticulation Main Arrangements for Dual Water Systems.....	434
WAT-1851 Reticulation Main Arrangements – Single Water System.....	435
WAT-1852 Connection to DICL Reticulation Mains.....	436
WAT-1853 Connection to PVC/GRP Reticulation Mains.....	437
WAT-1854 Prelaid in Footways.....	438
WAT-1855 Prelaid in Footways.....	439
WAT-1856 Prelaid in Roadways.....	440
WAT-1857-1 Typical Service Layouts and Alternative Marking Systems.....	441
WAT-1857-2 Typical Service Arrangement	442
WAT-1858 Main Arrangement for Cul-de-sacs and Court Bowls.....	443
WAT-1859 Offtake Main Details.....	444
WAT-1860 Drinking Water and Recycled Water Gate Valve/Hydrant Arrangement.....	445
WAT-1861 Indicator Plates for Locating Hydrants.....	446
WAT-1862 Indicator Plates for Locating Valves.....	447
WAT-1863 Concrete Thrust Blocks for Adjacent Dual Water Mains.....	448
WAT-1864 Hydrant, Valve and Flushing Installation on PE Mains using Compression Fittings.....	449
WAT-1865 Hydrant, Valve and Flushing Installation on PE Mains using Electrofusion Fittings.....	450
WAT-1866 Temporary Cross Connections.....	451
WAT-1867 Marking and Colour Identification.....	452
Figure D.1 METROPOLITAN WATER SUPPLY WAPC 133171.....	484
Figure D.2 GERALDTON REGIONAL WATER SUPPLY.....	485
Figure D.3 GREAT SOUTHERN TOWNS WATER SUPPLY MAIN CONDUIT.....	486
Figure D.4 METROPOLITAN WATER SUPPLY WAPC 123872.....	487
Figure D.5 GINGIN WATER SUPPLY WAPC 118531.....	488
Figure D.6 METROPOLITAN WATER SUPPLY WAPC 124200.....	489
Figure D.7 GOLDFIELDS & AGRICULTURAL WATER SUPPLY.....	490
Figure D.8 KALBARRI WATER SUPPLY WAPC 126341.....	491
Figure D.9 WP 0339.....	492
Figure D.10 WP 0341.....	493
Figure D.11 NABAWA WATER SUPPLY SCHEME.....	494
Figure D.12 LAVERTON WATER SUPPLY.....	495
Figure D.13 GREAT SOUTHERN TOWNS WATER SUPPLY MAIN CONDUIT.....	496
Figure D.14 MANDURAH WATER SUPPLY.....	497
Figure D.15 WATER AUTHORITY OF W.A.....	498
Figure D.16 LANCELIN TOWN WATER SUPPLY.....	499

Figure D.17 METROPOLITAN WATER SUPPLY - MINDARIE HIGH LEVEL BOOSTER PUMPING STATION.....	500
Figure D.18 KUNUNNURRA WATER SUPPLY.....	501
Figure D.19 DENMARK WATER SUPPLY.....	502
Figure D.20 METROPOLITAN WATER SUPPLY - YANGEBUP BOOSTER PUMPING STATION.....	503
Figure D.21 METROPOLITAN WATER SUPPLY - BANKSIA GROVE BOOSTER PUMP STATION.....	504
Figure D.22 METROPOLITAN WATER SUPPLY - BANKSIA GROVE BOOSTER PUMP STATION.....	505
Figure D.23 HORIZONTAL BOOSTER PUMP STATION SECTIONS.....	506
Figure D.24 PEMBERTON WATER SUPPLY.....	507
Figure D.25 PEMBERTON WATER SUPPLY - WATER TREATMENT PLANT SITE.....	508
Figure D.26 AUSTRALIA WATER SUPPLY.....	509
Figure D.27 HORIZONTAL BOOSTER PUMP STATION.....	510
Figure F.1 Example of Typical Talus Slopes.....	514
Figure F.2 POTENTIALLY UNSTABLE/LANDSLIP AREAS MONITORING PITS FOR DN 100 AND DN 150 RETICULATION MAINS IN ROAD RESERVES.....	518
Figure F.3 TYPICAL TRANSITION PIT DETAIL.....	518
Figure F.4 TYPICAL RESTRAINED JOINT MAINS AND INTERMEDIATE AND TRANSITION PIT ARRANGEMENT.....	519
Figure F.5 EFFECTS OF CONSTRUCTION TRENCHES ON GROUNDWATER MOVEMENT.....	520
Figure F.6 EFFECT OF CONSTRUCTION TRENCHES ON GROUNDWATER FLOW PATHS.....	521

List of Tables

Table 1.1 ASSET CATEGORIES.....	73
Table 1.2 TYPICAL ASSET DESIGN LIVES.....	76
Table 2.1 GUIDE TO DEMAND ALLOCATION WITHIN DUAL WATER SYSTEMS.....	80
Table 2.2 TYPICAL PEAK HOUR DEMAND WORK SHEET FOR DUAL WATER SUPPLY SYSTEMS.....	81
Table 2.3 SERVICE PRESSURE LIMITS FOR DRINKING WATER SINGLE SUPPLY.....	87
Table 3.1 MINIMUM PIPE SIZES FOR PARTICULAR DEVELOPMENTS.....	99
Table 3.2 EMPIRICAL GUIDE FOR PIPE SIZING IN DRINKING WATER ONLY SYSTEMS.....	100
Table 3.3 METHODS FOR DESIGN OF PLASTICS PIPES AND FITTINGS FOR DYNAMIC STRESSES.....	105
Table 3.4 TEMPERATURE DE-RATING FACTORS FOR PLASTICS PIPES OPERATING AT ELEVATED TEMPERATURES.....	106
Table 4.1 COLOUR DIFFERENTIATION OF DRINKING WATER AND ON-DRINKING WATER COMPONENTS IN DUAL WATER RETICULATION SYSTEMS.....	110
Table 5.1 DESIGN REQUIREMENTS FOR REDUCED SIZED DRINKING WATER MAINS IN COURT BOWLS, CUL-DE-SACS AND DEAD-ENDS.....	130
Table 5.2 DEFAULT EASEMENT GUIDELINES.....	135
Table 5.3 TRENCH DETAILS FOR TWO PARALLEL MAINS/SERVICES.....	145
Table 5.4 RESIDENTIAL PROPERTY SERVICE PIPE/CONNECTION SIZES.....	151
Table 5.5 CLEARANCES BETWEEN WATER MAINS AND UNDERGROUND SERVICES.....	154
Table 6.1 FLOW VELOCITIES.....	173
Table 7.1 NOT USED.....	185
Table 7.2 MINIMUM DEPTHS OF PIPE COVER.....	186
Table 7.3 NOT USED.....	199
Table 7.4 NOT USED.....	201
Table 7.5 REQUIREMENTS FOR BULKHEADS AND TRENCHSTOPS.....	203

Table 7.6 MINIMUM INSTALLATION TREATMENTS FOR WATER MAINS.....	204
Table 8.1 COLOUR CODING OF SPINDLE CAP PLASTICS COVERS.....	209
Table 8.2 STOP VALVE SPACING CRITERIA.....	216
Table 8.3 MAXIMUM WATER MAIN DRAINAGE TIMES.....	233
Table 8.4 MINIMUM SCOUR SIZE.....	235
Table 18.1 DIMENSIONS OF SWABS AND DISCHARGE UNITS.....	300
Table 19.1 MINIMUM COMPACTION OF EMBEDMENT AND TRENCH / EMBANKMENTS / OTHER FILLS.....	303
Table 24.1 [MINIMUM TRENCH DIMENSIONS INFORMATIVE].....	336
Table A.1 ASSET CATEGORISATION AND INDICATIVE PROTECTIVE TREATMENT SCHEDULE.....	457
Table B.1 EQUIVALENT PE PIPE DIAMETER COPPER PIPE AS 1432:2004.....	464
Table B.2 EQUIVALENT PE PIPE DIAMETER COMMONLY SPECIFIED WATER PIPE MATERIALS AND SIZES.....	465
Table C.1 ALLOWABLE PRESSURES FOR TYPE F AND R OFF-TAKE CLAMPS.....	469
Table C.2 HEAD LOSS COEFFICIENTS*.....	472
Table C.3 PERMITTED CUTTER SIZES AND FLANGED OFF-TAKE CLAMP LENGTHS FOR CIOD COMPATIBLE HOST PIPES.....	474
Table C.4 PERMITTED CUTTER SIZES AND FLANGED OFF-TAKE CLAMP LENGTHS FOR SERIES 1 PVC AND ABS HOST PIPES.....	475
Table C.5 PERMITTED CUTTER SIZES AND FLANGED OFF-TAKE CLAMP LENGTHS FOR SERIES 1 PE AND OTHER ISO SIZED HOST PIPES.....	478
Table D.1 BOOSTER CONFIGURATION APPLICATION GUIDANCE.....	482
Table E.1 TANK OPERATING CONDITIONS AND LIMITATIONS.....	512
Table G.1 FIELD TESTING OF SOILS TO ESTIMATE ALLOWABLE HORIZONTAL BEARING PRESSURE.....	524
Table H.1 MAXIMUM HYDRANT SPACINGS.....	526
Table I.1 C.t VALUES - MINIMUM CHLORINE RESIDUAL/CONTACT TIME (C.t) FOR THE DISINFECTANT - (BASED ON THE LOWEST MEASURED FCR).....	530
Table I.2 DRINKING WATER QUALITY PARAMETER SAMPLE TOLERANCE LIMITS.....	533
Table I.3 NON-DRINKING WATER QUALITY PARAMETER SAMPLE TOLERANCE LIMITS.....	534