



WATER SERVICES
ASSOCIATION OF AUSTRALIA

WATER SUPPLY CODE OF AUSTRALIA

Version 3.1

WSA 03-2011

CONTENTS

PREFACE

INTRODUCTION

PART 0: GLOSSARY OF TERMS AND ABBREVIATIONS

I Glossary of Terms

II Abbreviations

III Referenced Documents

PART 1: PLANNING AND DESIGN

Contents

1 General

2 System Planning

3 Hydraulic Design

4 Products and Materials

5 General Design

6 System Pressure Management

7 Structural Design

8 Appurtenances

9 Design Review and Drawings

PART 2: CONSTRUCTION

Contents

10 General

11 General Construction

12 Products and Materials

13 Excavation

14 Bedding for Pipes

15 Pipe Laying, Jointing and Connecting

16 Pipe Embedment and Support

17 Fill

18 Swabbing

19 Acceptance Testing

20 Disinfection

21 Tolerances on As-Constructed Work

22 Connections to Existing Water Mains

23 Restoration

24 Work As Constructed Details

WATER SUPPLY CODE OF AUSTRALIA VERSION 3.1**APPENDICES**

| | |
|------------|--|
| Appendix A | Generic Infrastructure Protection Guidance |
| Appendix B | Equivalent Pipe Sizes for Commonly Used Materials |
| Appendix C | Under Pressure Cut-In Connection to Pressure Pipes \geq DN 80 |
| Appendix D | Booster Configurations |
| Appendix E | Selection of Pressure Accumulator Tanks |
| Appendix F | Water Mains in Slip and Potentially Unstable Areas |
| Appendix G | Soil Classification Guidelines and Allowable Bearing Pressures for Anchors and Thrust Blocks |
| Appendix H | Hydrant Spacings |
| Appendix I | Disinfection of Water Mains |
| Appendix J | Safety Assurance Plan and Job Safety Analysis |
| Appendix K | Connectivity Inspection of Dual Water Supply Systems |



PART 1: PLANNING AND DESIGN

Water Supply Code of Australia
Version 3.1

WSA 03-2011

CONTENTS

1 GENERAL

1.1 SCOPE

1.2 PLANNING AND DESIGN

1.2.1 Objectives

1.2.2 Scope and requirements

1.2.3 Concept plan format

1.2.4 Critical infrastructure protection

1.2.4.1 Asset categorisation

1.2.4.2 All hazards – Infrastructure protection

1.2.5 Detailed design

1.2.5.1 Designer's needs and responsibilities

1.2.5.2 Requirements to be addressed

1.2.5.3 Design outputs

1.2.6 Design life

1.2.7 Instrumentation and control systems

1.3 CONSULTATION WITH OTHER PARTIES

2 SYSTEM PLANNING

2.1 GENERAL

2.2 SYSTEM PLANNING PROCESS

2.2.1 General

2.2.2 Extending / upgrading an existing water supply system

2.2.3 Providing a new water supply

2.2.4 Non-drinking water as drinking water substitution

2.3 DEMANDS

2.3.1 General

2.3.2 Dual water supply systems

2.3.2.1 General

2.3.2.2 Rainwater tanks

2.3.3 Demand assessment

2.3.3.1 General

2.3.3.2 Residential

2.3.3.3 Non-residential

2.3.4 Peak demands

2.3.4.1 General

2.3.4.2 Peak day demand

2.3.4.3 Peak hour demand

2.4 SYSTEM CONFIGURATION

2.5 SYSTEM HYDRAULICS

2.5.1 General

2.5.2 Network analysis

2.5.3 Operating pressures

2.5.3.1 Service pressure

2.5.3.2 Maximum allowable service pressure

2.5.3.3 Minimum service pressure

2.5.3.4 Average service pressure

2.5.4 Pressure variation analysis

2.5.5 Determining supply zones

2.5.5.1 General

2.5.5.2 Use of minimum allowable or desirable minimum service pressures

2.5.5.3 Use of desirable minimum static pressure

2.6 WATER QUALITY

- 2.6.1 General
- 2.6.2 Prevention of back siphonage
- 2.6.3 Water age
- 2.6.4 Disinfection

2.7 SEPARATION OF DRINKING AND NON-DRINKING WATER SUPPLY SYSTEMS

- 2.7.1 Permanent cross links and cross connections
- 2.7.2 Temporary cross links

2.8 PUMPING STATIONS

- 2.8.1 General
- 2.8.2 Design factors
 - 2.8.2.1 System related factors
 - 2.8.2.2 Site related factors
 - 2.8.2.3 Service related factors
- 2.8.3 Concept design

2.9 SERVICE RESERVOIRS

- 2.9.1 Storage capacity
- 2.9.2 Location

2.10 TRENCHLESS TECHNIQUES FOR PIPELAYING

2.11 FUTURE SYSTEM EXPANSION

2.12 SYSTEM REVIEW

3 HYDRAULIC DESIGN

3.1 SIZING

- 3.1.1 General
- 3.1.2 Minimum pipe sizes
- 3.1.3 Empirical sizing of reticulation mains
- 3.1.4 Dual water supply systems
- 3.1.5 Fire flows
- 3.1.6 Sizing by analysis
 - 3.1.6.1 General
 - 3.1.6.2 Head losses
 - 3.1.6.3 Hydraulic roughness values
 - 3.1.6.4 Flow velocities

3.2 DESIGN PRESSURES

- 3.2.1 General
- 3.2.2 Gravity systems
- 3.2.3 Systems subjected to dynamic pressures

3.3 PRESSURE CLASS OF SYSTEM COMPONENTS

- 3.3.1 Gravity systems
- 3.3.2 Systems subjected to dynamic pressures

3.4 THRUST AND ANCHOR BLOCK DESIGN

3.5 SYSTEM TEST PRESSURE

3.6 DESIGN FOR DYNAMIC STRESSES

- 3.6.1 General
- 3.6.2 Surge
- 3.6.3 Fatigue
- 3.6.4 Fatigue de-rating of plastics pipes and fittings

3.7 TEMPERATURE DE-RATING OF PLASTICS PIPES AND FITTINGS

3.8 PIPELINE COMPONENTS MINIMUM PRESSURE CLASS

4 PRODUCTS AND MATERIALS

4.1 GENERAL

4.2 DIFFERENTIATION OF DRINKING AND NON-DRINKING PIPE SYSTEMS

- 4.2.1 Principles
- 4.2.2 Water supply mains – drinking water
- 4.2.3 Water supply mains – non-drinking water
- 4.2.4 Property services – drinking water
- 4.2.5 Property services – non-drinking water
- 4.2.6 Marking tapes

4.3 DUCTILE IRON PIPELINE SYSTEMS

- 4.3.1 Product Specifications
- 4.3.2 Sizes and configurations
- 4.3.3 Seal coating of lining
- 4.3.4 Sleeving
- 4.3.5 Screw-on flanges for DI pipes
- 4.3.6 Flanged joints

4.4 PVC PIPELINE SYSTEMS

4.5 PE PIPELINE SYSTEMS

4.6 STEEL PIPELINE SYSTEMS

- 4.6.1 Product Specifications
- 4.6.2 Sizes and configurations
- 4.6.3 Joints
- 4.6.4 Field welding
- 4.6.5 Flanged joints

4.7 GRP PIPELINE SYSTEMS

4.8 PROTECTION AGAINST DEGRADATION

- 4.8.1 Application
- 4.8.2 Protection against aggressive environments
- 4.8.3 Protection against damage to coatings
- 4.8.4 Stainless steels
 - 4.8.4.1 Grade selection
 - 4.8.4.2 Welding
 - 4.8.4.3 Threaded components
- 4.8.5 Cathodic protection
- 4.8.6 Stray current corrosion
- 4.8.7 Protection against contaminated ground
- 4.8.8 Bolted connections

5 GENERAL DESIGN

5.1 GENERAL REQUIREMENTS

- 5.1.1 Design tolerances
- 5.1.2 Levels
- 5.1.3 Water main renewals—electrical safety and earthing to water services
- 5.1.4 Environmental considerations
 - 5.1.4.1 General
 - 5.1.4.2 Urban salinity

5.2 RETICULATION DESIGN FOR WATER QUALITY

- 5.2.1 Layout of water mains
- 5.2.2 Looped mains
- 5.2.3 Link mains
- 5.2.4 Reduced size mains

5.3 WATER MAIN ACCESS

5.4 LOCATION OF WATER MAINS

- 5.4.1 General
- 5.4.2 Water mains in road reserves
 - 5.4.2.1 General
 - 5.4.2.2 Location in footway
 - 5.4.2.3 Location in carriageway
 - 5.4.2.4 Location in roundabouts and bus bays
- 5.4.3 Location in other than dedicated public road reserves
- 5.4.4 Water mains in easements
- 5.4.5 Dual water supply systems
- 5.4.6 Effect on vegetation
- 5.4.7 Water mains near trees
- 5.4.8 Contaminated sites
- 5.4.9 Crossings
 - 5.4.9.1 General
 - 5.4.9.2 Requirements for encased pipe installations
- 5.4.10 Railway reserves
- 5.4.11 Crossings of creeks or drainage reserves
- 5.4.12 Overhead power lines and transmission towers
- 5.4.13 Water mains in conjunction with landscaping and/or other development
- 5.4.14 Water mains on curved alignments
- 5.4.15 Location markers
- 5.4.16 Marking tape
 - 5.4.16.1 General
 - 5.4.16.2 Mains
 - 5.4.16.3 Property services
- 5.5 TRENCHLESS TECHNOLOGY
- 5.6 SHARED TRENCHING
- 5.7 DUPLICATE MAINS
- 5.8 RIDER MAINS
- 5.9 CONNECTION OF NEW MAINS TO EXISTING MAINS
- 5.10 TERMINATION POINTS
 - 5.10.1 Permanent ends of water mains
 - 5.10.2 Temporary ends of water mains
 - 5.10.3 Chlorination assemblies
 - 5.10.4 Flushing points
- 5.11 PROPERTY SERVICES
 - 5.11.1 General
 - 5.11.2 Connections to water mains
 - 5.11.3 Services, outlets and meters
- 5.12 OBSTRUCTIONS AND CLEARANCES
 - 5.12.1 General
 - 5.12.2 Surface obstructions
 - 5.12.3 Clearance from transmission towers
 - 5.12.4 Clearance from structures and property boundaries
 - 5.12.5 Underground obstructions and services
 - 5.12.5.1 General
 - 5.12.5.2 Clearance requirements
 - 5.12.6 Deviation of water mains
 - 5.12.6.1 General
 - 5.12.6.2 Horizontal deviation of water mains
 - 5.12.6.3 Vertical deviation of water mains
 - 5.12.6.4 Curving of pipes to avoid obstructions
- 5.13 DISUSED OR REDUNDANT PIPELINES

6 SYSTEM PRESSURE MANAGEMENT

6.1 GENERAL

6.2 IN-LINE PRESSURE BOOSTER PUMPING STATIONS

6.2.1 Planning criteria

6.2.2 Concept design

6.2.2.1 General

6.2.2.2 Life cycle considerations

6.2.2.3 Functionality

6.2.2.4 Due diligence requirements

6.2.2.5 Reliability

6.2.2.6 Maintainability

6.2.2.7 Materials design

6.2.2.8 Location

6.2.2.9 Site selection

6.2.2.10 Noise control

6.2.2.11 Services

6.2.2.12 Access

6.2.2.13 Site drainage

6.2.2.14 Landscaping

6.2.2.15 Security

6.2.2.16 Signage

6.2.2.17 Supporting systems

6.2.2.18 Health and safety

6.2.3 Commissioning plan

6.2.3.1 General

6.2.3.2 Pre-commissioning

6.2.3.3 Commissioning

6.2.4 System planning and modelling

6.2.4.1 Modelling

6.2.4.2 Minimum pressure affecting the area

6.2.4.3 Number of affected properties within the low pressure zone

6.2.5 Booster design

6.2.5.1 General

6.2.5.2 Connection to the network

6.2.5.3 Maximum flow and pressure requirements

6.2.5.4 Design for minimum pressure boost conditions

6.2.5.5 Design for minimum flow conditions

6.2.5.6 Booster configuration design

6.2.5.7 Booster set and pump selection

6.2.5.8 Booster pipework and manifold design

6.2.5.9 Booster equipment and devices

6.2.5.10 Site specific requirements

6.2.6 Booster pipework

6.2.6.1 General design parameters

6.2.6.2 Manifolds, off-takes, suction and delivery pipework

6.2.6.3 Pressure gauges and tappings

6.2.7 Pressure accumulator tank

6.2.8 Power system and supply

6.2.8.1 General

6.2.8.2 Security of supply

6.2.8.3 Primary supply

6.2.8.4 Duplicate supply

6.2.8.5 Emergency power

6.2.8.6 On-site generator

6.2.8.7 Mobile generator

6.2.8.8 Power factor correction

6.2.8.9 Lighting

- 6.2.9 Control and telemetry system
 - 6.2.9.1 General
 - 6.2.9.2 Instrumentation
 - 6.2.9.3 System requirements
 - 6.2.9.4 Fire flow operation
- 6.2.10 Alarms and controls
 - 6.2.10.1 General
 - 6.2.10.2 Control switches – manual and emergency operation
- 6.2.11 Telemetry
 - 6.2.11.1 General
 - 6.2.11.2 Software
 - 6.2.11.3 Communications
- 6.3 PRESSURE REDUCING VALVE INSTALLATIONS
 - 6.3.1 Planning criteria
 - 6.3.2 Design requirements
- 6.4 PRESSURE SUSTAINING VALVE INSTALLATIONS
 - 6.4.1 Planning criteria
 - 6.4.2 Design requirements

7 STRUCTURAL DESIGN

- 7.1 GENERAL
- 7.2 STRUCTURAL CONSIDERATIONS
- 7.3 INTERNAL FORCES
- 7.4 EXTERNAL FORCES
 - 7.4.1 General
 - 7.4.2 Pipe cover
 - 7.4.3 Embedment zone dimensions
 - 7.4.4 Pipe embedment
 - 7.4.5 Buoyancy
- 7.5 GEOTECHNICAL CONSIDERATIONS
 - 7.5.1 General
 - 7.5.2 Water mains in engineered or controlled fill
 - 7.5.3 Water mains in non-engineered fill
 - 7.5.4 Construction of an embankment
- 7.6 CONCRETE ENCASEMENT
 - 7.6.1 General
 - 7.6.2 Requirements
 - 7.6.3 Encased steel pipelines
 - 7.6.3.1 General
 - 7.6.3.2 Existing steel pipelines
- 7.7 WATER MAINS IN UNSTABLE GROUND
 - 7.7.1 General
 - 7.7.2 Mine subsidence areas
 - 7.7.3 Slip areas
- 7.8 ABOVE-GROUND WATER MAINS
- 7.9 PIPELINE ANCHORAGE
 - 7.9.1 General
 - 7.9.2 Thrust blocks
 - 7.9.2.1 General
 - 7.9.2.2 Concrete thrust blocks
 - 7.9.2.3 Use of puddle flanges to transfer thrust
 - 7.9.2.4 Timber and recycled plastics thrust blocks
 - 7.9.3 Anchor blocks

- 7.9.4 Thrust and anchor blocks for dual water supply systems
- 7.9.5 Restrained elastomeric seal joint water mains
- 7.9.6 Restraint requirements for special situations
 - 7.9.6.1 Above-ground mains with unrestrained flexible joints
 - 7.9.6.2 Buried steel mains with welded joints
 - 7.9.6.3 Above-ground steel mains with welded joints
 - 7.9.6.4 Ductile iron and steel mains with flanged joints
 - 7.9.6.5 PE mains
- 7.10 BULKHEADS AND TRENCHSTOPS
- 7.11 UNFORESEEN GROUND CONDITIONS

8 APPURTENANCES

- 8.1 VALVES—GENERAL
 - 8.1.1 Valving design
 - 8.1.2 Valve siting principles
 - 8.1.3 Selection considerations
 - 8.1.4 Local in-line booster pumping stations
 - 8.1.5 Plastics identification covers
- 8.2 STOP VALVES
 - 8.2.1 Product Specifications
 - 8.2.2 Installation design and selection criteria
 - 8.2.2.1 General
 - 8.2.2.2 Gate valves
 - 8.2.2.3 Butterfly valves
 - 8.2.3 Stop valves for transfer/distribution mains
 - 8.2.4 Stop valves for reticulation mains
 - 8.2.5 Stop valves for local in-line booster pumping stations
 - 8.2.6 Bypass of stop valve
 - 8.2.7 Stop valves—location and arrangements
 - 8.2.7.1 General
 - 8.2.7.2 Arrangement 1
 - 8.2.7.3 Arrangement 2
 - 8.2.7.4 Arrangement 3
 - 8.2.7.5 Arrangement 4
 - 8.2.7.6 Arrangement 5
 - 8.2.7.7 Arrangement 6
 - 8.2.7.8 Arrangement 7
 - 8.2.8 Stop valve special arrangements
 - 8.2.9 Rider mains and network configurations
 - 8.2.10 Crossing mains – interconnection
- 8.3 CONTROL VALVES
 - 8.3.1 Product Specifications
 - 8.3.2 Automatic inlet control valves (AICV)
 - 8.3.3 Pressure reducing valves (PRV)
 - 8.3.4 Pressure relief valves (PReIV)
 - 8.3.5 Pump control valves
 - 8.3.6 Pressure sustaining valves (PSV)
- 8.4 AIR VALVES (AV)
 - 8.4.1 Product Specifications
 - 8.4.2 Installation design criteria
 - 8.4.3 Air valves type
 - 8.4.4 Air valves size
 - 8.4.5 Air valves location
 - 8.4.6 Use of hydrants as an alternative to air valves
 - 8.4.7 Water sampling via air valves

8.5 NON-RETURN VALVES

8.5.1 Product Specifications

8.5.2 Installation design criteria

8.5.3 Non-return valves for local in-line booster pumping stations and boosted zones

8.6 SCOURS AND PUMP-OUT BRANCHES

8.6.1 Location and arrangements

8.6.2 Design

8.6.3 Scour application

8.6.4 Scour size

8.6.5 Scour location

8.7 SWABBING POINTS

8.8 HYDRANTS **ERROR! BOOKMARK NOT DEFINED.**

8.8.1 Product Specifications

8.8.2 Purposes

8.8.3 Hydrant siting principles

8.8.4 Hydrant types

8.8.5 Hydrant installation

8.8.6 Hydrant outlet connections

8.8.7 Hydrant size

8.8.8 Hydrant spacing

8.8.9 Hydrant location

8.8.10 Hydrants for reticulation system operational requirements

8.8.11 Hydrants at ends of mains

8.9 DISINFECTION FACILITIES

8.9.1 General

8.9.2 Reticulation mains

8.9.3 Transfer and distribution mains

8.9.4 Discharge

8.10 SURFACE FITTINGS

8.10.1 Product Specifications

8.10.2 General

8.10.3 Marking of surface fittings

8.10.4 Installation requirements

8.11 APPURTENANCE LOCATION MARKING

8.11.1 General

8.11.2 Marker posts and plates

8.11.3 Pavement markers

8.11.4 Kerb markings

9 DESIGN REVIEW AND DRAWINGS

9.1 DESIGN REVIEW

9.2 DESIGN DRAWINGS

9.2.1 General

9.2.2 Composition of Design Drawings

9.2.3 Scale

9.2.4 Contents of Design Drawings

9.2.5 Pipeline system acronyms

9.2.6 Water mains >DN 300

9.3 SPECIFICATIONS

9.4 RECORDING OF WORK AS CONSTRUCTED INFORMATION

TABLES

| | |
|-----------|---|
| Table 1.1 | Asset Categories |
| Table 1.2 | Typical Asset Design Lives |
| Table 2.1 | Guide to Demand Allocation Within Dual Water Systems |
| Table 2.2 | Typical Peak Hour Demand Work Sheet for Dual Water Supply Systems |
| Table 2.3 | Service Pressure Limits for Drinking Water Single Supply |
| Table 3.1 | Minimum Pipe Sizes for Particular Developments |
| Table 3.2 | Empirical Guide for Pipe Sizing |
| Table 3.3 | Methods for Design of Plastics Pipes and Fittings for Dynamic Stresses |
| Table 3.4 | Temperature De-Rating Factors for Plastics Pipes Operating at Elevated Temperatures |
| Table 4.1 | Colour Differentiation of Drinking Water and Non-Drinking Water Components in Dual Water Reticulation Systems |
| Table 5.1 | Design Requirements for Reduced Sized Drinking Water Mains in Court Bowls, Cul-de-Sacs and Dead-Ends |
| Table 5.2 | Default Easement Guidelines |
| Table 5.3 | Trench Details for Two Parallel Mains/Services |
| Table 5.4 | Residential Property Service Pipe/Connection Sizes |
| Table 5.5 | Clearances Between Water Mains and Underground Services |
| Table 6.1 | Flow Velocities |
| Table 7.1 | PVC Pipe Material Characteristics |
| Table 7.2 | Minimum Depths of Pipe Cover |
| Table 7.3 | Minimum Thrust Area for Concrete Blocks at 1000 kPa System Test Pressure |
| Table 7.4 | Allowable Applications for Timber and Recycled Plastics Thrust Blocks |
| Table 7.5 | Requirements for Bulkheads and Trenchstops |
| Table 8.1 | Colour Coding of Spindle Cap Plastics Covers |
| Table 8.2 | Stop Valve Spacing Criteria |
| Table 8.3 | Maximum Water Main Drainage Times |
| Table 8.4 | Minimum Scour Size |

FIGURES

| | |
|---------------|---|
| Figure 1.1 | Typical Water Supply System |
| Figure 2.1(a) | Single Transfer/Distribution Main, Minor Network and Dead-End Branch Mains |
| Figure 2.1(b) | Single Transfer/Distribution Main, Network With Multiple Distribution Mains and Branch Mains With Reduced Diameter Dead-Ends |
| Figure 2.1(c) | Twin Transfer/Distribution Mains, Network With Multiple Distribution Mains, Looped Mains and Link Mains to Minimise Dead-Ends, Some Reduced Diameter Dead-End Mains and Staging of Provision of Mains |
| Figure 2.2 | Typical Water Supply Pumping Station Arrangements |
| Figure 4.1 | Flange Fastener Tightening Sequence |

- Figure 4.2 Typical Insulated Flanged Joint for Cathodically Protected Steel Mains
- Figure 4.3 Typical Bolted Connection Detail for Fusion Bonded Coated Ductile Iron Flanges With Stainless Steel Fasteners
- Figure 4.4 Typical Bolted Connection Detail and Corrosion Protection Procedure for Buried Ductile Iron Flanges With Galvanised Steel Fasteners
- Figure 4.5 Typical Bolted Connection Detail for PE Stub Flange and Raised Ductile Iron Flange With Stainless Steel Fasteners and Backing Plate
- Figure 5.1 Looped and Link Mains
- Figure 5.2 Design Requirements for Reduced Sized Mains in Court Bowls, Cul-de-Sacs and Dead-Ends
- Figure 5.3 Typical Dual Water Installation in Common Trench
- Figure 5.4 Typical Shared/Combined Trench Installation
- Figure 5.5 Typical Shared/Combined Trench Installation Off-take
- Figure 5.6 Typical Under Pressure Cut-In Connection Method Using a Split SS Clamp With Flanged Off-take – Plan View
- Figure 5.7 Typical Inserted Tee Method Using Mechanical Couplings – Plan View
- Figure 5.8 Typical Flushing Assembly Details for Ends of Reduced Sized Mains
- Figure 5.9 Typical Split Service Main to Meter Across Road Carriageway
- Figure 5.10 Typical Property Service Layouts in Dual Water Supply Networks
- Figure 5.11 Typical Duct and Service Marker Details
- Figure 5.12 Horizontal Deviation by Deflection at Pipe Joints – Plan View
- Figure 5.13 Horizontal Deflection Using a DI SOC-SOC Connector and Permitted Joint Deflections for DI Pipes and Other Applicable Pipe Types – Plan View
- Figure 5.14 Deflection Using DI Bends with DI and Other Permitted Pipe Types – Plan View
- Figure 5.15 Vertical Deviation by Deflection at Pipe Joints – Section View
- Figure 5.16 Vertical Deviation Using DI Bends – Section View
- Figure 5.17 Typical Anchor Block Detail for Vertical Bends
- Figure 5.18 Vertical Deflections Using Fabricated Pipe and Flanges – Section View
- Figure 5.19 Vertical Deflections Using Double Offset Fabricated Pipe and Flanges – Section View
- Figure 6.1 Typical Pre-Commissioning and Commissioning Process
- Figure 6.2 Typical Handover to Water Agency
- Figure 7.1 Typical Arrangement of Buried Pipe
- Figure 7.2 Type A Embedment Support
- Figure 7.3 Type B Embedment Support
- Figure 7.4 Type C and D Embedment Support
- Figure 7.5 Type E Embedment Support
- Figure 7.6 Type F Embedment Support

| | |
|-------------|--|
| Figure 7.7 | Type G Embedment Support |
| Figure 7.8 | Type H Embedment Support |
| Figure 7.9 | Type J and K Concrete Encasement Embedment Support |
| Figure 7.10 | Alternative End Treatment for Concrete Encased Steel Pipelines |
| Figure 7.11 | Thrust Block for Tees (for Horizontal Thrust) |
| Figure 7.12 | Thrust Block for Bends (for Horizontal Thrust) |
| Figure 7.13 | Taper Thrust Block (for Horizontal Thrust) |
| Figure 7.14 | Flushing/Washout Bend Thrust Block (for Horizontal Thrust) (Minimum Required Thrust Area as Per Dead-End) |
| Figure 7.15 | Typical Concrete Thrust Block for Flanged Valves |
| Figure 7.16 | Typical Concrete Thrust Block for Socketed Valves |
| Figure 7.17 | Typical Timber and Recycled Plastics Thrust Block Configurations |
| Figure 7.18 | Typical Valve Restraint Mechanism |
| Figure 7.19 | Typical Concrete Thrust Blocks for Adjacent Dual Water Mains |
| Figure 7.20 | Typical Concrete Bulkhead Detail |
| Figure 7.21 | Typical Road Crossing Bulkhead |
| Figure 7.22 | Typical Trench Stop Detail |
| Figure 7.23 | Typical Trench Drainage Detail at Bulkhead |
| Figure 7.24 | Typical Trench Drainage Detail at Low Point in Trench |
| Figure 7.25 | Typical Trench Drainage Detail at Concrete Encased Sections |
| Figure 7.26 | Typical Trench Drainage Discharge |
| Figure 8.1 | Plastics Identification Cover |
| Figure 8.2 | Typical Gate Valve and Hydrant Installation at Standard Depth |
| Figure 8.3 | Typical Gate Valve Installation at Deeper Than Standard Depth |
| Figure 8.4 | Typical Valve Chamber Arrangement for DN 500 and DN 600 Mains – Plan View |
| Figure 8.5 | Typical Valve Chamber Arrangement for a DN 750 Main – Plan View |
| Figure 8.6 | Typical Valve Chamber Arrangement – Cross Section |
| Figure 8.7 | Bypass Arrangement With L-Type Ball Hydrant |
| Figure 8.8 | Branch Valve Adjacent to Main |
| Figure 8.9 | Branch Valve Adjacent to Inner Splay Corner |
| Figure 8.10 | Valve and Hydrant Combinations |
| Figure 8.11 | Valve Adjacent to a Taper |
| Figure 8.12 | Valves in Main Cross-Links |
| Figure 8.13 | Valves in Conjunction With Control Valves |
| Figure 8.14 | Two Direction Supply |
| Figure 8.15 | Off-take Arrangement for Rider Mains |
| Figure 8.16 | Interconnection of DN 200 and DN 225 Crossing Mains |
| Figure 8.17 | Interconnection of Reticulation and Distribution Mains |
| Figure 8.18 | Interconnection of Distribution Mains |
| Figure 8.19 | Interconnection of a Continuing Reticulation Main and Larger Main |

- Figure 8.20 Typical Pressure Reducing Valve Installation – Sectional Elevation
- Figure 8.21 Alternative Above-Ground Installation – PRV on Bypass – Side Elevation
- Figure 8.22 PRV on Main Line With Bypass – Plan View
- Figure 8.23 Typical Air Valve Orientation
- Figure 8.24 Typical Air Valve Installation
- Figure 8.25 Scour Detail
- Figure 8.26 Scour Discharge to Approved Drainage System
- Figure 8.27 Scour Discharge Collection/Pump-Out Sump
- Figure 8.28 Scour Discharge to Storage Lagoon
- Figure 8.29 Spring Hydrant – Typical Direct Connection
- Figure 8.30 Isolating Valve Assembly With Spring Hydrant
- Figure 8.31 Typical Hydrant Installation in Non-Trafficable Location
- Figure 8.32 Typical Hydrant Installation in Trafficable Asphaltic Concrete Pavement
- Figure 8.33 Typical Hydrant With Isolating Valve Installation With Spring Hydrant Option in Non-Trafficable Location
- Figure 8.34 Typical Offsetting of Hydrants in Footway
- Figure 8.35 Non-Trafficable Stop Valve Surface Box
- Figure 8.36 Typical Trafficable Stop Valve Surface Boxes
- Figure 8.37 Typical Trafficable Hydrant Surface Boxes
- Figure 8.38 Retro-Reflective Pavement Markers
- Figure 8.39 Kerb Markings



WATER SERVICES
ASSOCIATION OF AUSTRALIA

PART 2: CONSTRUCTION

Water Supply Code of Australia
Version 3.1

CONTENTS

10 GENERAL

- 10.1 SCOPE
- 10.2 INTERPRETATION

11 GENERAL CONSTRUCTION

- 11.1 GENERAL
- 11.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING
- 11.3 CONTRACT INTERFACES
- 11.4 CUSTOMER FOCUS
 - 11.4.1 General
 - 11.4.2 Resolution of complaints
- 11.5 PROTECTION OF PROPERTY AND ENVIRONMENT
 - 11.5.1 Protection of other services
 - 11.5.2 Disused / Redundant water mains
 - 11.5.3 Road reserves or other thoroughfares
 - 11.5.3.1 Road opening permits
 - 11.5.3.2 Treatment of pavements and other surfaces
 - 11.5.3.3 Cleanliness of roads, paths, accesses and drainage paths
 - 11.5.3.4 Storage of products, materials and equipment
 - 11.5.3.5 Obstruction of street drainage
 - 11.5.4 Private and public properties
 - 11.5.5 Protection of the environment and heritage areas
 - 11.5.5.1 General
 - 11.5.5.2 Collection and disposal of wastes
 - 11.5.5.3 Protection of adjacent lands and vegetation
 - 11.5.5.4 Control of water pollution
 - 11.5.5.5 Contaminated soils
 - 11.5.5.6 Fire ant areas
 - 11.5.5.7 Control of noise and atmospheric pollution
 - 11.5.5.8 Equipment and machinery use in bush fire prone areas
- 11.6 OPERATION OF WATER SUPPLY NETWORK
- 11.7 ALTERATION OF EXISTING SERVICES
- 11.8 CONNECTION TO AND WORK ON EXISTING ASBESTOS WATER MAINS
- 11.9 CUT-IN CONNECTION EQUIPMENT
- 11.10 SURVEY MARKS
- 11.11 CONSTRUCTION TOLERANCES
- 11.12 LATENT CONDITIONS

12 PRODUCTS AND MATERIALS

- 12.1 AUTHORISED PRODUCTS AND MATERIALS
 - 12.1.1 General
- 12.2 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS
- 12.3 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS
 - 12.3.1 General
 - 12.3.2 Transportation
 - 12.3.3 Unloading and handling
 - 12.3.4 On-site storage
- 12.4 REJECTED PRODUCTS AND MATERIALS
- 12.5 CONCRETE WORKS
- 12.6 SUPPLY OF WATER TO THE WORKS
- 12.7 SUPPLY OF WATER TO EXISTING PROPERTIES
- 12.8 UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80
 - 12.8.1 Flanged off-takes
 - 12.8.2 Valves
 - 12.8.3 Flange holes
 - 12.8.4 Gaskets

- 12.8.5 Bolting system
 - 12.8.5.1 General
 - 12.8.5.2 Carbon or alloy steel bolt assemblies
 - 12.8.5.3 Stainless steel bolt assemblies
- 12.8.6 Insulation sleeves
- 12.8.7 Plastics inserts for metallic pipes

13 EXCAVATION

- 13.1 PRECAUTIONS
- 13.2 LIMITS OF CLEARING AND EXCAVATION
- 13.3 PROTECTION OF TREES
 - 13.3.1 General precautions
 - 13.3.2 Protection of roots
- 13.4 BLASTING
- 13.5 SUPPORT OF EXCAVATIONS
- 13.6 DRAINAGE AND DEWATERING
- 13.7 UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80
 - 13.7.1 Excavation requirements
 - 13.7.2 Extent of excavation
- 13.8 EXCAVATION ACROSS IMPROVED SURFACES
- 13.9 TRENCH EXCAVATION
 - 13.9.1 General
 - 13.9.2 Construction of embankment
 - 13.9.3 Clearances for on-site works
- 13.10 REFILL OF EXCESSIVE EXCAVATION
- 13.11 FOUNDATIONS AND FOUNDATION STABILISATION
- 13.12 SURPLUS EXCAVATED MATERIAL
- 13.13 TUNNELLING

14 BEDDING FOR PIPES

- 14.1 TRENCH FLOOR PREPARATION
- 14.2 BEDDING AND PIPE SUPPORT
- 14.3 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS

15 PIPE LAYING, JOINTING AND CONNECTING

- 15.1 INSTALLATION OF PIPES
 - 15.1.1 General
 - 15.1.2 Dual water supply areas
 - 15.1.3 Cleaning, inspection and joint preparation
 - 15.1.4 Laying
 - 15.1.5 Lift and re-lay construction
- 15.2 HORIZONTAL AND VERTICAL DEFLECTIONS OF PIPES
 - 15.2.1 General
 - 15.2.2 Deflection at a pipe joint
 - 15.2.3 Curving of pipe
- 15.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES
- 15.4 VALVES, HYDRANTS AND OTHER APPURTENANCES
- 15.5 UNDER PRESSURE CUT-IN CONNECTION TO PRESSURE PIPES \geq DN 80
 - 15.5.1 Inspection of host pipe
 - 15.5.2 Inspection of valve to be installed
 - 15.5.3 Disinfection of fittings and equipment
 - 15.5.4 Installation of off-take clamp
 - 15.5.5 Installation of the valve
 - 15.5.6 Cut-in operation
 - 15.5.7 Recording and reporting
- 15.6 FLOTATION CONTROL
- 15.7 THRUST AND ANCHOR BLOCKS AND RESTRAINED JOINTS
- 15.8 TAPPING OF MAINS, PROPERTY SERVICES AND WATER METERS
- 15.9 TRENCH STOPS

- 15.10 BULKHEADS
- 15.11 CORROSION PROTECTION OF DUCTILE IRON
- 15.12 MARKING TAPES
 - 15.12.1 Non-detectable marking tape
 - 15.12.2 Detectable marking tape
 - 15.12.3 Tracer wire
- 15.13 VALVES, HYDRANTS AND SURFACE BOXES AND FITTINGS
 - 15.13.1 Installation
 - 15.13.2 Valve chambers for large diameter mains
- 15.14 SCOURS
- 15.15 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE
- 15.16 AQUEDUCTS
- 15.17 BRIDGE CROSSINGS
- 15.18 APPURTENANCE LOCATION MARKING
- 15.19 FLANGED JOINTS
- 15.20 WELDING OF STEEL PIPELINES
 - 15.20.1 General
 - 15.20.2 Field welding of flanges
 - 15.20.3 Reinstatement of cement mortar lining
 - 15.20.4 Reinstatement of external corrosion protection at joints using a tape system
 - 15.20.4.1 Surface preparation
 - 15.20.4.2 Priming surfaces
 - 15.20.4.3 Mastic filler
 - 15.20.4.4 Tape application
 - 15.20.5 Reinstatement of external corrosion protection at joints using a heat-shrinkable sleeve system
 - 15.20.5.1 Surface preparation
 - 15.20.5.2 Preheat pipe
 - 15.20.5.3 Priming surfaces
 - 15.20.5.4 Mastic filler
 - 15.20.5.5 Heat-shrinkable sleeve preparation
 - 15.20.5.6 Heat-shrinkable sleeve application
- 15.21 WELDING OF PE PIPELINES

16 PIPE EMBEDMENT AND SUPPORT

- 16.1 GENERAL
- 16.2 EMBEDMENT MATERIALS
- 16.3 COMPACTION OF EMBEDMENT
 - 16.3.1 Methods
- 16.4 SPECIAL BEDDING AND EMBEDMENTS / GEOTEXTILE SURROUND AND PILLOW
- 16.5 REMOVAL OF TRENCH SUPPORTS
- 16.6 CONCRETE EMBEDMENT AND ENCASEMENT

17 FILL

- 17.1 TRENCH FILL
 - 17.1.1 Material requirements
 - 17.1.1.1 Trafficable Areas
 - 17.1.1.2 Non-Trafficable Areas
 - 17.1.2 Placement
 - 17.1.3 Compaction of trench fill
- 17.2 EMBANKMENT FILL
- 17.3 DRIVES AND TUNNEL FILL

18 SWABBING

- 18.1 GENERAL
- 18.2 SWABS
- 18.3 SWABBING PROCEDURE

19 ACCEPTANCE TESTING

- 19.1 GENERAL

19.2 VISUAL INSPECTION

19.3 COMPACTION TESTING

19.3.1 General

19.3.2 Compaction testing requirements

19.3.2.1 General

19.3.2.2 Trafficable areas test zone

19.3.2.3 Non-trafficable areas test zone

19.3.2.4 Frequency and location of tests

19.3.2.5 Retesting

19.4 HYDROSTATIC PRESSURE TESTING

19.4.1 General

19.4.2 Mains

19.4.3 Property services

19.4.4 Under pressure cut-in connections

19.5 BLOCK TESTING DUAL WATER SUPPLY SYSTEMS FOR CONNECTIVITY

19.6 INSULATED JOINT RESISTANCE TEST

19.7 WATER QUALITY TESTING

19.7.1 General

19.7.2 Test procedure

19.7.3 Satisfactory water quality test

19.7.4 Failure of test

20 DISINFECTION

20.1 APPLICATION

20.2 FLUSHING OF DISINFECTION WATER

21 TOLERANCES ON AS-CONSTRUCTED WORK

21.1 GENERAL

21.2 HORIZONTAL TOLERANCES

21.2.1 Water mains and in-line structures

21.2.2 Property services and meters

21.3 VERTICAL TOLERANCES

21.3.1 Water mains, property connections and structures

21.3.2 Verticality ("plumb")

21.4 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS

21.5 CAST IN-SITU CONCRETE STRUCTURES AND SLABS

22 CONNECTIONS TO EXISTING WATER MAINS

22.1 GENERAL

22.2 UNDER PRESSURE CONNECTIONS

22.3 INSERTED TEE CONNECTIONS

22.3.1 Shutdown of existing water mains

22.3.2 Making the connection to existing water main

22.3.3 Re-charging the shutdown water main

22.4 CONNECTION AND/OR CHARGING THE NEW WATER MAINS

22.5 RECONNECTION OF PROPERTIES SUPPLIED BY TEMPORARY PRIVATE SERVICES

23 RESTORATION

23.1 GENERAL

23.2 PAVEMENTS

23.3 LAWNS

23.4 GRASSED AREAS

23.5 BUSHLAND

23.6 PROVISION FOR AND RECTIFICATION OF SETTLEMENT

23.7 MAINTENANCE OF RESTORED SURFACES

24 WORK AS CONSTRUCTED DETAILS

TABLES

| | |
|------------|--|
| Table 18.1 | Dimensions of Swabs and Discharge Units |
| Table 19.1 | Minimum Compaction of Embedment, Trench Fill and Embankments |

FIGURES

| | |
|-------------|-------------------------------|
| Figure 13.1 | Typical Excavation Dimensions |
| Figure 15.1 | Ball and Socket Joint |
| Figure 15.2 | Slip-In Welded Joint |
| Figure 15.3 | Plain End Welded Collar Joint |
| Figure 15.4 | Plain End Butt Welded Joint |