



WATER SERVICES ASSOCIATION
of Australia

SEWAGE PUMPING STATION CODE

of Australia

WSA 04-2005
Version 2.1



WATER SERVICES ASSOCIATION
of Australia

Sewage Pumping Station Code of Australia

WSA 04—2005

**Second Edition
Version 2.1**

Previous edition WSA 04—2001

CONTENTS

PREFACE	6
INTRODUCTION	9
PART 0: GLOSSARY OF TERMS AND ABBREVIATIONS	
I Glossary of Terms	12
II Abbreviations	19
III Referenced Documents	23
IV Other References	30
PART 1: PLANNING AND DESIGN	
Contents	36
1 General	45
2 Concept Design	53
3 General Design	62
4 Materials Design	70
5 Pumping Station Design	71
6 Pumping System	88
7 Power System	94
8 Control and Telemetry System	99
9 Wet-Well Pipework	115
10 Pressure Main	121
11 Structural Design	137
12 Supporting Systems	148
13 Health and Safety	150
14 Design Review	152
15 Design Documentation and Drawings	153
Appendix A Typical Precommissioning Checklist	157
Appendix B Commissioning Schedule	161
Appendix C AC Voltage Mitigation of Steel Pipelines	162
Appendix D Computer Program for Pressure Main Sizing	163
Appendix E Detailed Design Checklist	167
PART 2: PRODUCTS AND MATERIALS	
Contents	174
16 Products and Materials Overview	176
Appendix F Quality Assurance of Products	187
PART 3: CONSTRUCTION	
Contents	194

17	General	202
18	Quality	205
19	General Construction	208
20	Products, Materials and Equipment	215
21	Electrical Works	222
22	Telemetry System	235
23	Odour Control System	237
24	Mechanical Installation of Pumps, Valves and Fittings	238
25	Metalwork	240
26	Access Road and Hardstand Areas	242
27	Retaining Walls	244
28	Excavation	247
29	Bedding for Pipes, Bends, Wet-Wells and Maintenance Structures	249
30	Pipe Laying and Jointing	250
31	Wet-Wells and Maintenance Holes (MHS)	256
32	Pipe Embedment and Support	258
33	Fill	261
34	Connection to Existing Gravity Sewers	263
35	Restoration	264
36	Acceptance Testing	266
37	Commissioning	277
38	Tolerances on As-Constructed Work	279
39	Work As-Constructed Details	281
	Appendix G Ovality Testing of PVC and GRP Gravity Sewers Default Prover Diameters	282
	PART 4: STANDARD DRAWINGS	
	Contents	284
40	Introduction	285
41	Listing of Standard Drawings	286
	STANDARD DRAWINGS	



WATER SERVICES ASSOCIATION
of Australia

Sewage Pumping Station Code of Australia

WSA 04—2005

Part 1: Planning and Design

Second Edition

Version 2.1

CONTENTS

PREFACE

1 GENERAL

1.1 SCOPE

1.2 PLANNING

1.2.1 General

1.2.2 Pumping alternatives

1.3 SEWAGE PUMPING STATIONS

1.3.1 Pumping philosophy

1.4 PURPOSE AND APPLICATION

1.5 PLANNING AND DESIGN RESPONSIBILITIES AND INTERFACES

1.5.1 General

1.5.2 Planning responsibilities

1.5.3 Design responsibilities

1.5.4 Consultation with other parties

1.6 SEWER SYSTEM DESIGN APPROACH

1.6.1 Overall objective

1.6.2 System design life

1.6.3 Objectives of design

1.6.4 Design output

2 CONCEPT DESIGN

2.1 LIFE CYCLE CONSIDERATIONS

2.2 FUNCTIONALITY

2.3 MAINTAINABILITY

2.4 RELIABILITY

2.5 DUE DILIGENCE REQUIREMENTS

2.6 MATERIALS DESIGN

2.7 STAGING

2.8 SEPTICITY CONTROL

2.8.1 General

2.8.2 Detention time

2.9 ODOUR CONTROL

2.10 NOISE CONTROL

2.11 SERVICES

2.12 ACCESS

2.13 SECURITY

2.14 SIGNAGE

2.15 SUPPORTING SYSTEMS

2.16 HEALTH AND SAFETY

2.17 COMMISSIONING PLAN

2.17.1 General

2.17.2 Pre-commissioning

2.17.3 Commissioning

3 GENERAL DESIGN

3.1 GENERAL

3.2 DESIGN TOLERANCES

3.3 LEVELS

3.4 UNFORESEEN GROUND CONDITIONS

3.5 IMPACT OF CONSEQUENTIAL DAMAGE

3.6 ENVIRONMENTAL CONSIDERATIONS

- 3.6.1 General
- 3.6.2 Urban salinity
- 3.6.3 Effect on vegetation
- 3.6.4 Contaminated sites
- 3.6.5 Tidal zones
- 3.7 EASEMENTS
- 3.8 CROSSINGS
 - 3.8.1 General
 - 3.8.2 Creeks and drainage reserves
 - 3.8.3 Major roads
- 3.9 FUTURE MAINTENANCE
- 3.10 AC VOLTAGE MITIGATION OF METALLIC PIPELINES
- 3.11 OBSTRUCTIONS AND CLEARANCES
 - 3.11.1 General
 - 3.11.2 Surface obstructions
 - 3.11.3 Clearance from structures
 - 3.11.4 Underground obstructions and services
 - 3.11.4.1 General
 - 3.11.4.2 Clearance requirements
 - 3.11.5 Crossing services
 - 3.11.6 Deviation of pressure mains around structures
- 3.12 DISUSED OR REDUNDANT ITEMS
- 3.13 SEWAGE QUALITY
 - 3.13.1 Septicity
 - 3.13.2 Sewage quality/Trade waste management

4 MATERIALS DESIGN

- 4.1 GENERAL
- 4.2 CORROSION PROTECTION
 - 4.2.1 Protective coatings
 - 4.2.2 Concrete surfaces
 - 4.2.3 Metallic materials
 - 4.2.4 Miscellaneous items
 - 4.2.5 Corrosion protection against aggressive environments
 - 4.2.6 Cathodic protection
 - 4.2.7 Stray current corrosion
 - 4.2.8 Protection against contaminated ground

5 PUMPING STATION DESIGN

- 5.1 INTRODUCTION
- 5.2 SITE SELECTION, LOCATION AND LAYOUT
 - 5.2.1 Site selection
 - 5.2.2 Right of occupancy and access
 - 5.2.3 Location and layout
 - 5.2.4 Site area
 - 5.2.5 Site layout and access
 - 5.2.6 Landscaping
- 5.3 INLET MH
 - 5.3.1 Location
 - 5.3.2 Design
 - 5.3.3 Pumping station wet-well isolating valve
- 5.4 WET-WELL DESIGN
 - 5.4.1 General
 - 5.4.2 Sizing

- 5.4.3 Pumping control volume and pump starts
- 5.4.4 Control levels
- 5.4.5 Detention time
- 5.4.6 Benching
- 5.4.7 Washers
- 5.5 WET-WELL VENTILATION
 - 5.5.1 Natural ventilation
 - 5.5.2 Forced ventilation
 - 5.5.3 Educt vent shaft
- 5.6 OVERFLOW CONTAINMENT
 - 5.6.1 General
 - 5.6.2 Emergency storage
 - 5.6.2.1 General
 - 5.6.2.2 Configurations
 - 5.6.2.3 Design
 - 5.6.2.4 Access and cover arrangements
 - 5.6.2.5 Type of construction
 - 5.6.3 Future storage provisions
 - 5.6.4 Emergency relief system
- 5.7 LADDERS AND PLATFORMS
- 5.8 WET-WELL ACCESS COVERS
- 5.9 SAFETY SYSTEMS
- 5.10 GRIT COLLECTION
- 5.11 SCREENS
- 5.12 MIXERS

6 PUMPING SYSTEM

- 6.1 STAGING
- 6.2 HYDRAULIC DESIGN
- 6.3 PUMP EQUIPMENT
- 6.4 PUMP SELECTION
- 6.5 TRIPLE-PUMP PUMPING STATIONS
- 6.6 SUBMERSIBLE PUMPS
 - 6.6.1 General
 - 6.6.2 Impeller selection
 - 6.6.3 Motor selection
 - 6.6.4 Standard discharge connection
 - 6.6.5 Junction boxes
 - 6.6.6 Pumpset lifting equipment
- 6.7 ANCILLARY EQUIPMENT
 - 6.7.1 Flushing valves
- 6.8 PUMP STARTERS AND VARIABLE SPEED DRIVES
 - 6.8.1 General
 - 6.8.2 Single and double speed starters
 - 6.8.3 Soft starters
 - 6.8.4 Variable speed drives
- 6.9 HARMONICS AND RADIO FREQUENCY INTERFERENCE
- 6.10 EMERGENCY STOP

7 POWER SYSTEM

- 7.1 GENERAL
- 7.2 POWER SUPPLIES
 - 7.2.1 General
 - 7.2.2 Security of supply

- 7.2.3 Primary supply
- 7.2.4 Duplicate supply
- 7.2.5 Emergency power
- 7.2.6 On-site generator
- 7.2.7 Mobile generator
- 7.2.8 High voltage/Low voltage switching
- 7.2.9 Power factor correction

7.3 POWER AND CONTROL CUBICLE

- 7.3.1 Design
- 7.3.2 Low voltage switchboards
 - 7.3.2.1 Standards
 - 7.3.2.2 Construction
 - 7.3.2.3 Rated diversity factor
 - 7.3.2.4 Degree of protection
 - 7.3.2.5 Rated insulation and operating voltages
 - 7.3.2.6 Creepage distances
 - 7.3.2.7 Rated impulse withstand voltage
 - 7.3.2.8 Rated short-time current
 - 7.3.2.9 Internal arcing fault protection
- 7.3.3 Meter requirements
- 7.3.4 Lighting

8 CONTROL AND TELEMETRY SYSTEM

8.1 GENERAL

8.2 OPERATING LEVELS AND SETTINGS

8.3 PUMPING CONTROL

- 8.3.1 Control design
- 8.3.2 Control switches
- 8.3.3 Control systems
- 8.3.4 Emergency back-up control
- 8.3.5 Pump starts and interlocks

8.4 ALARMS

- 8.4.1 General
- 8.4.2 Locally displayed alarms
- 8.4.3 Remote alarms

8.5 ALARM, STATUS MONITORING AND CONTROL TELEMETRY

- 8.5.1 General design principles
- 8.5.2 Reliability
- 8.5.3 Alarm creation function
- 8.5.4 Status monitoring function
- 8.5.5 Control function

8.6 TELEMETRY HARDWARE

- 8.6.1 General
- 8.6.2 Software
- 8.6.3 Inputs and outputs
- 8.6.4 Telemetry communications
- 8.6.5 Communication validation

8.7 OPERATING LEVELS AND DEFAULT SETTINGS

- 8.7.1 General
- 8.7.2 Cut-in and cut-out levels
- 8.7.3 Alarm levels

8.8 EQUIPMENT AND DEVICES

- 8.8.1 General
- 8.8.2 Flow measurement
- 8.8.3 Flowmeter cabling

- 8.8.4 Suction safety switch
 - 8.8.5 Level sensors
 - 8.8.6 Float-switch
 - 8.8.7 Site access monitoring
 - 8.8.8 Protection devices
 - 8.8.8.1 Fuse and fuse-links
 - 8.8.8.2 Moulded-case circuit-breakers
 - 8.8.8.3 Miniature circuit-breakers
 - 8.8.8.4 Residual current devices
 - 8.8.8.5 Thermal-overload relays
 - 8.8.8.6 Electronic motor protection relays
 - 8.8.8.7 Thermistor and RTD motor protection devices
 - 8.8.9 Switching devices
 - 8.8.9.1 Switches
 - 8.8.9.2 Selector switches
 - 8.8.10 Contactors
 - 8.8.11 Push-buttons
 - 8.8.12 Emergency stop-buttons
 - 8.8.13 Time-switches
 - 8.8.14 Control devices
 - 8.8.14.1 Control relays
 - 8.8.14.2 Time-delay relays and timers
 - 8.8.15 ELV control transformers
 - 8.8.16 Current transformers
 - 8.9 INSTRUMENTATION (DISPLAYS)
 - 8.10 WIRE NUMBERING CONVENTION
 - 8.11 SYSTEMS INCORPORATING PROGRAMMABLE CONTROLLER / TELEMETRY RTU
 - 8.11.1 Digital inputs and outputs
 - 8.11.2 Analog inputs and outputs
 - 8.11.3 Address codes for communication link devices
 - 8.12 SYSTEMS INCORPORATING RELAY CONTROL
 - 8.12.1 General
 - 8.12.2 Loop tag definition guidelines
- 9 WET-WELL PIPEWORK
- 9.1 PUMP DISCHARGE PIPEWORK
 - 9.1.1 General
 - 9.1.2 Sizing
 - 9.1.3 Type
 - 9.2 VALVE APPLICATIONS
 - 9.2.1 Isolating valves
 - 9.2.2 Non-return valves
 - 9.2.3 Scour/Emergency by-pass connection
 - 9.2.4 Sewage air-release valves
 - 9.3 VALVE CHAMBER
 - 9.3.1 General
 - 9.3.2 Design
 - 9.3.3 Dismantling joints
 - 9.3.4 Pipework support
 - 9.3.5 Pressure main tappings
 - 9.3.6 Access covers
 - 9.4 EMERGENCY PUMPING ARRANGEMENTS
 - 9.4.1 Condition monitoring and maintenance

10 PRESSURE MAIN

10.1 DESIGN

10.1.1 General

10.2 LOCATION OF PRESSURE MAINS

10.2.1 General

10.2.2 Road reserves

10.2.3 Railway reserves

10.2.4 Alignment

10.2.5 Changes in direction

10.2.6 Easements

10.3 HYDRAULIC DESIGN

10.3.1 Total mean head

10.3.2 Mean static head

10.3.3 Friction head loss

10.3.4 Fitting head loss

10.3.5 Velocity in pressure mains

10.3.6 Sizing of pressure mains

10.4 DESIGN PRESSURES

10.4.1 General

10.4.2 Maximum design pressure

10.4.3 Surge

10.4.4 Maximum design pressure range

10.5 SELECTION OF PIPE AND FITTINGS PRESSURE CLASS

10.5.1 General

10.5.2 Maximum allowable operating pressure

10.5.3 Maximum cyclic pressure range - Thermoplastics pipes and fittings

10.5.4 Minimum pressure class

10.5.5 Other considerations

10.6 PLASTICS PIPES

10.6.1 Temperature de-rating of plastic pipes and fittings

10.6.2 Fatigue design for thermoplastics pipes

10.6.3 Fatigue design for thermoplastic fittings

10.6.4 Fatigue design for thermosetting pipes and fittings

10.6.5 Combined effects of fatigue and temperature

10.7 METALLIC PIPES AND FITTINGS

10.8 PIPELINE MATERIALS

10.9 PRESSURE MAIN VALVES

10.9.1 General

10.9.2 Isolating valves

10.9.3 Gas release valves

10.9.4 Non-return valves

10.9.5 Scours

10.10 ODOUR AND SEPTICITY CONTROL

10.11 RECEIVING SYSTEM

10.11.1 General

10.11.2 Discharge MHs

11 STRUCTURAL DESIGN

11.1 DIFFICULT GROUND CONDITIONS

11.1.1 Foundation design and ground water control

11.1.2 Geotechnical assessment

11.2 STRUCTURES

11.2.1 Design loads and forces

11.2.2 Concrete structures

- 11.2.2.1 General
- 11.2.2.2 Concrete strength
- 11.2.2.3 Minimum cover
- 11.2.2.4 Crack control requirement for serviceability
- 11.2.2.5 Areas to be designed as liquid retaining surfaces
- 11.2.3 Steel structures
- 11.2.4 Foundations
- 11.2.5 Pumping station walls
- 11.2.6 Base slab
- 11.2.7 Top slab
- 11.2.8 Emergency storage structures
- 11.3 PRESSURE MAINS
 - 11.3.1 General
 - 11.3.2 Products and materials
 - 11.3.3 Structural computations
 - 11.3.4 External forces
 - 11.3.4.1 General
 - 11.3.4.2 Pipe cover
 - 11.3.4.3 Trench design
 - 11.3.4.4 Pipe embedment
 - 11.3.5 Specific geotechnical considerations
 - 11.3.5.1 Pressure mains in engineered and/or controlled fill
 - 11.3.5.2 Pressure mains in non-engineered fill
 - 11.3.5.3 Filling along route of pressure main
 - 11.3.5.4 Mine subsidence
 - 11.3.5.5 Slip areas
 - 11.3.5.6 Water-charged ground
 - 11.3.6 Above ground crossings
 - 11.3.7 Bulkheads and trenchstops
 - 11.3.8 Trenchless technology
 - 11.3.9 Pressure main anchorage
 - 11.3.9.1 General
 - 11.3.9.2 Thrust blocks
 - 11.3.9.3 Anchor blocks
 - 11.3.10 Restrained elastomeric seal joint pressure mains
 - 11.3.11 Restraint requirements for special situations
 - 11.3.11.1 Above ground pressure mains with unrestrained flexible joints
 - 11.3.11.2 Steel mains with welded joints, buried
 - 11.3.11.3 Steel mains with welded joints, above ground
 - 11.3.11.4 Ductile iron or steel mains with flanged joints

12 SUPPORTING SYSTEMS

12.1 SERVICES

- 12.1.1 General
- 12.1.2 Water
- 12.1.3 Telephone/Telemetry lines
- 12.1.4 General lighting and power
- 12.1.5 Drainage
- 12.1.6 Water closet

12.2 MATERIALS HANDLING

- 12.2.1 Lifting equipment
- 12.2.2 Handling and storage of hazardous material

12.3 SECURITY

12.4 FIRE CONTROL

13 HEALTH AND SAFETY

13.1 GENERAL

13.2 HAZARDS

13.3 HEALTH AND SAFETY

13.3.1 General

13.3.2 Working at heights

13.4 CONFINED SPACES

14 DESIGN REVIEW

15 DESIGN DOCUMENTATION AND DRAWINGS

15.1 DOCUMENTATION

15.2 DESIGN DRAWINGS

15.2.1 General

15.2.2 Real property information

15.2.3 Pumping station and emergency storage

15.2.4 Structures

15.2.5 Pressure mains and sewers

15.2.6 Longitudinal sections (profiles)

15.2.7 Title block notation and standard notes

15.2.8 Other

15.2.9 Electrical and telemetry

15.3 DRAFTING STANDARDS

15.3.1 General

15.3.2 Scale

15.3.3 Recording of as-constructed information

APPENDIX A TYPICAL PRECOMMISSIONING CHECKLIST

APPENDIX B TYPICAL COMMISSIONING SCHEDULE

APPENDIX C AC VOLTAGE MITIGATION OF STEEL PIPELINES

C1 INTRODUCTION

C2 INDUCTIVE COUPLING HAZARD

C3 CONDUCTIVE COUPLING HAZARD

C4 CAPACITIVE COUPLING HAZARD

C5 MITIGATION

APPENDIX D PRESSURE MAIN CALCULATOR

D1 PRESSURE MAIN CALCULATOR

D2 NOMENCLATURE

D3 PRINCIPLES AND CRITERIA

D3.1 Design flows

D3.2 Detention time

D3.3 Minimum internal diameter of pressure main

D3.4 Maximum internal diameter of pressure main

D3.5 Minimum pumping rate

D3.6 Maximum pumping rate

D3.7 Pump control volume (cut-in / cut-out volume) and pump starts

D4 INSTRUCTIONS

D4.1 Data entry

D4.2 Internal diameter of pressure main

D4.3 Pumping rate and detention time

D4.4 Wet-well control volume / actual starts / detention time

- D4.5 Printing
- D4.6 New calculation
- D4.7 Reset

APPENDIX E DETAILED DESIGN CHECKLIST

TABLES

TABLE 1.1	TYPICAL ASSET DESIGN LIFE
TABLE 3.1	CLEARANCES BETWEEN PRESSURE MAINS AND UNDERGROUND SERVICES
TABLE 5.1	DEFAULT CONTROL LEVELS
TABLE 8.1	DEFAULT ALARM LEVELS
TABLE 8.2	TYPICAL LOCAL AND REMOTE ALARMS
TABLE 8.3	TYPICAL REMOTE MONITORED CONDITIONS
TABLE 10.1	PRESSURE DE-RATING FACTORS FOR PLASTIC PIPES AT ELEVATED TEMPERATURES
TABLE 10.2	FATIGUE DE-RATING FACTORS FOR THERMOPLASTIC PIPES
TABLE 10.3	SCOUR SIZES
TABLE 11.1	REQUIREMENT FOR BULKHEADS

FIGURES

FIGURE 1.1	CONCEPT DESIGN FLOWCHART
FIGURE 2.1	SPS OVERFLOW RISK REDUCTION DECISION DIAGRAM
FIGURE 2.2	TYPICAL PRE-COMMISSIONING AND COMMISSIONING PROCESS
FIGURE 2.3	TYPICAL HANDOVER TO WATER AGENCY
FIGURE 3.1	DEFLECTION AT JOINTS
FIGURE 3.2	DEFLECTION USING SOC-SOC BENDS
FIGURE 3.3	DEFLECTION USING SOC-SOC CONNECTORS
FIGURE 5.1	TYPICAL EMERGENCY STORAGE – CONFIGURATION 1
FIGURE 5.2	TYPICAL EMERGENCY STORAGE – CONFIGURATION 2
FIGURE 5.3	TYPICAL EMERGENCY STORAGE – CONFIGURATION 3
FIGURE 5.4	TYPICAL EMERGENCY STORAGE – CONFIGURATION 4
FIGURE 8.1	ALARM LEVEL CONTROL SETTINGS
FIGURE 10.1	TYPICAL SURGE WAVE
FIGURE 10.2	TYPICAL FATIGUE CYCLE



WATER SERVICES ASSOCIATION
of Australia

Sewage Pumping Station Code of Australia

WSA 04—2005

Part 2: Products and Materials

Second Edition

Version 2.1

CONTENTS

16 PRODUCTS AND MATERIALS OVERVIEW

16.1 PURPOSE

16.2 SCOPE

16.3 RESPONSIBILITIES

16.3.1 Water Agency

16.3.2 Designer

16.3.3 Constructor

16.3.4 Purchaser

16.4 PRODUCT AND MATERIAL STANDARDS AND SPECIFICATIONS

16.4.1 Product standards

16.4.2 Purchase specifications

16.4.3 Purchase specifications—Alternatives

16.5 QUALITY ASSURANCE

16.5.1 Default requirement

16.5.2 Additional information on quality assurance

16.5.3 Innovative products and materials

16.6 SELECTION GUIDE FOR PIPELINE SYSTEMS

16.7 ADDITIONAL PRODUCT AND MATERIAL INFORMATION

APPENDIX F

F1 GENERAL

F2 QUALITY ASSURANCE OPTIONS

F2.1 ISO 9000 quality management system certification

F2.2 Product certification

F2.2.1 General

F2.2.2 Product certification – Type 1

F2.2.3 Product certification – Type 3

F2.2.4 Product certification – Type 5

F2.3 Supplier's declaration of conformance

F2.4 Second party verification

F3 FACTORS INFLUENCING SELECTION OF QUALITY ASSURANCE OPTIONS

F3.1 General factors

F3.2 Likelihood of manufacturing non-conformance

F3.3 Likelihood of failure of pipeline system from a product non-conformance

F3.4 Consequences of failure

F3.5 Product specification

F3.6 Project magnitude / management

F3.7 Innovative products

F4 SELECTING THE QUALITY ASSURANCE OPTION

F4.1 General factors

F4.2 Product certification

F4.2.1 General

F4.2.2 Type 1

F4.2.3 Type 3

F4.2.4 Type 5

F4.3 ISO 9000 quality management system certification

F4.4 Supplier's declaration of conformance

F4.5 Second party verification

TABLES

TABLE 16.1 PRINCIPAL PRESSURE MAINS AND COMPONENTS
TABLE 16.2 PRECAUTIONS, LIMITATIONS, ADVANTAGES AND DISADVANTAGES



WATER SERVICES ASSOCIATION
of Australia

Sewage Pumping Station Code of Australia

Part 3: Construction

Second Edition

Version 2.1

CONTENTS

- 17 GENERAL
 - 17.1 SCOPE
 - 17.2 INTERPRETATION
- 18 QUALITY
 - 18.1 QUALITY ASSURANCE
 - 18.1.1 General
 - 18.1.2 Quality management system
 - 18.1.3 Quality system
 - 18.1.4 Project management plan
 - 18.1.5 Inspection and test plans
 - 18.1.6 Quality tests
 - 18.1.7 Quality audits
 - 18.1.8 Traceability
 - 18.1.9 Quality records
 - 18.1.10 Inspection
 - 18.2 PERSONNEL QUALIFICATIONS
- 19 GENERAL CONSTRUCTION
 - 19.1 GENERAL
 - 19.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING
 - 19.2.1 Pumping stations
 - 19.2.2 Inlet works, emergency storage and ERS
 - 19.2.3 Pressure mains
 - 19.3 CONTRACT INTERFACES
 - 19.4 CUSTOMER FOCUS
 - 19.4.1 General
 - 19.4.2 Resolution of complaints
 - 19.5 PROTECTION OF PEOPLE, PROPERTY AND ENVIRONMENT
 - 19.5.1 Safety of people
 - 19.5.2 Protection of other services
 - 19.5.3 Disused / Redundant sewers and pressure mains
 - 19.5.4 Road reserves or other thoroughfares
 - 19.5.4.1 Treatment of pavements and other surfaces
 - 19.5.4.2 Traffic management
 - 19.5.4.3 Cleanliness of roads, paths, accesses and drainage paths
 - 19.5.4.4 Storage of products, materials and equipment
 - 19.5.4.5 Obstruction of street drainage
 - 19.5.5 Private and public properties
 - 19.5.6 Protection of the environment and heritage areas
 - 19.5.6.1 General
 - 19.5.6.2 Collection and disposal of wastes
 - 19.5.6.3 Protection of adjacent lands and vegetation
 - 19.5.6.4 Control of water pollution
 - 19.5.6.5 Acid sulphate and contaminated soils
 - 19.5.6.6 Control of noise and atmospheric pollution
 - 19.6 AFFECTED PARTY NOTIFICATIONS
 - 19.7 ALTERATION OF EXISTING SERVICES
 - 19.8 SURVEY MARKS

- 19.9 CONSTRUCTION TOLERANCES
- 19.10 LATENT CONDITIONS
- 20 PRODUCTS, MATERIALS AND EQUIPMENT
 - 20.1 AUTHORISED PRODUCTS AND MATERIALS
 - 20.2 REJECTED PRODUCTS AND MATERIALS
 - 20.3 ELECTRICAL EQUIPMENT
 - 20.4 PUMPS
 - 20.5 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS
 - 20.6 DELIVERY AND STORAGE OF ELECTRICAL EQUIPMENT
 - 20.7 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS
 - 20.8 FASTENERS
 - 20.9 WORKS INSPECTION AND TESTING
 - 20.9.1 Switchboards
 - 20.9.2 Pumps
 - 20.9.3 Motors
 - 20.10 CONCRETE WORKS
 - 20.10.1 Delivery
 - 20.10.2 Transportation of concrete
 - 20.10.3 Formwork
 - 20.10.4 Reinforcement
 - 20.10.5 Placement
 - 20.10.5.1 General
 - 20.10.5.2 Placement in water
 - 20.10.6 Slump
 - 20.10.7 Compaction
 - 20.10.8 Stripping
 - 20.10.9 Curing
 - 20.10.10 Repair of blemishes
 - 20.11 SUPPLY OF WATER TO THE WORKS
 - 20.12 ON-SITE STOCKPILES
- 21 ELECTRICAL WORKS
 - 21.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS
 - 21.2 SCOPE OF WORK
 - 21.3 SUPPLY AUTHORITY REQUIREMENTS AND METERING
 - 21.4 CONSUMER MAINS
 - 21.4.1 Point of supply
 - 21.4.2 Cable size
 - 21.4.3 Maximum demand
 - 21.4.4 Calculations to be submitted
 - 21.4.5 Mains in reserves
 - 21.4.6 Mains requirements
 - 21.4.7 Lead-in pole and overhead mains construction
 - 21.4.7.1 Lead-in pole
 - 21.4.7.2 Poles
 - 21.4.7.3 Installation of poles
 - 21.4.7.4 Aerial cables
 - 21.4.8 Underground cable installation
 - 21.4.8.1 General

- 21.4.8.2 Location
 - 21.4.8.3 Excavation and bedding
 - 21.4.8.4 Underground cable marking
 - 21.4.8.5 Cable installation on poles
 - 21.4.8.6 Road crossings
 - 21.5 EARTHING
 - 21.5.1 General
 - 21.5.2 Earth circuits
 - 21.5.3 Labelling
 - 21.6 SWITCHBOARD INSTALLATION
 - 21.6.1 General
 - 21.6.2 Equipment mounting
 - 21.6.3 Thermal derating of equipment
 - 21.6.4 Labelling
 - 21.6.4.1 General
 - 21.6.4.2 Incoming mains and pump and motor detail labels
 - 21.6.4.3 Main labels
 - 21.6.4.4 Cubicle labels
 - 21.6.4.5 Danger notices
 - 21.6.4.6 Asset and equipment number labels
 - 21.7 CIRCUITS
 - 21.7.1 Main circuits
 - 21.7.2 Control circuit wiring
 - 21.8 CABLING
 - 21.8.1 General
 - 21.8.2 Conduits
 - 21.8.3 Cable protection
 - 21.8.4 Cable trays
 - 21.8.5 Junction boxes
 - 21.9 INSTALLATION OF PUMP CABLES
 - 21.9.1 Numbering of pumps
 - 21.9.2 Installation
 - 21.10 INSTALLATION OF LEVEL SENSORS
 - 21.10.1 General
 - 21.10.2 Wet-well level sensor probes
 - 21.11 TERMINATIONS
 - 21.11.1 General
 - 21.11.2 Glands
 - 21.11.3 Mains and pump terminations
 - 21.12 PAINTING
 - 21.12.1 General
 - 21.12.2 Paint materials
 - 21.12.3 Surface preparation
 - 21.12.4 Painting and finish
 - 21.13 INSTALLATION IN VALVE PITS
 - 21.13.1 General
 - 21.13.2 Cables
 - 21.14 NOTIFICATION OF ELECTRICAL WORK
- 22 TELEMETRY SYSTEM

- 22.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS
- 22.2 SCOPE OF WORK
- 22.3 HARDWARE INSTALLATION
- 22.4 PLC PROGRAMMING
- 22.5 SCADA DATABASE CONFIGURATION
- 23 ODOUR CONTROL SYSTEM
- 24 MECHANICAL INSTALLATION OF PUMPS, VALVES AND FITTINGS
 - 24.1 GENERAL
 - 24.2 FLANGED JOINTS
 - 24.3 INSTALLATION OF PUMPING UNITS
 - 24.3.1 General
 - 24.3.2 Machinery alignment
 - 24.3.3 Unit numbers
 - 24.3.4 Test tapping points
 - 24.4 GAUGES AND RECORDERS
 - 24.4.1 Pressure gauges
 - 24.4.2 Pressure recorder
- 25 METALWORK
 - 25.1 STEELWORK
 - 25.2 ALUMINIUM ALLOY COMPONENTS
 - 25.3 STAINLESS STEEL COMPONENTS
 - 25.4 FASTENERS
- 26 ACCESS ROAD AND HARDSTAND AREAS
 - 26.1 GENERAL
 - 26.2 SUBGRADE
 - 26.3 BASECOURSE
 - 26.4 SPRAYED BITUMINOUS SEALING
 - 26.5 ASPHALTIC CONCRETE
 - 26.6 TIMBER GUARDRAIL
- 27 RETAINING WALLS
 - 27.1 RETAINING WALLS - TIMBER CANTILEVER
 - 27.1.1 General
 - 27.1.2 Handrails
 - 27.2 RETAINING WALLS - CONCRETE - CRIB WALL
 - 27.2.1 General
 - 27.2.2 Foundations
 - 27.2.3 Cribfill and backfill
 - 27.2.4 Drainage
 - 27.2.5 Handrails
- 28 EXCAVATION
 - 28.1 SAFETY
 - 28.2 LIMITS OF EXCAVATION
 - 28.3 EXCAVATION ACROSS IMPROVED SURFACES
 - 28.4 EXCAVATION IN ROOT ZONES
 - 28.5 BLASTING
 - 28.6 SUPPORT OF EXCAVATIONS
 - 28.7 DRAINAGE AND DEWATERING

- 28.8 FOUNDATIONS AND FOUNDATION STABILISATION
- 28.9 SURPLUS EXCAVATED MATERIAL
- 29 BEDDING FOR PIPES, BENDS, WET-WELLS AND MAINTENANCE STRUCTURES
 - 29.1 TRENCH FLOOR PREPARATION
 - 29.2 BEDDING MATERIALS
 - 29.3 PLACEMENT OF BEDDING
 - 29.4 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS
 - 29.5 BEDDING FOR PIPES, VALVES AND FITTINGS
 - 29.6 BEDDING FOR CONCRETE STRUCTURES
 - 29.7 BEDDING FOR MAINTENANCE SHAFTS AND VARIABLE BENDS
- 30 PIPE LAYING AND JOINTING
 - 30.1 INSTALLATION OF PIPES
 - 30.1.1 General
 - 30.1.2 Cleaning, inspection and joint preparation
 - 30.1.3 Polyethylene
 - 30.1.4 Laying
 - 30.2 HORIZONTAL AND VERTICAL DEFLECTION OF GRAVITY SEWERS AND PRESSURE MAINS
 - 30.2.1 General
 - 30.2.2 Methods of deflection
 - 30.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES
 - 30.4 FLOTATION CONTROL
 - 30.5 THRUST AND ANCHOR BLOCKS AND RESTRAINED JOINTS FOR PRESSURE MAINS
 - 30.6 MARKING TAPES
 - 30.6.1 Non-detectable marking tape
 - 30.6.2 Detectable marking tape
 - 30.7 VALVES AND SURFACE FITTINGS
 - 30.7.1 Installation
 - 30.7.2 Scours for pressure mains
 - 30.8 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE
 - 30.9 BRIDGE CROSSINGS
 - 30.10 TRENCH STOPS FOR PRESSURE MAINS
 - 30.11 BULKHEADS FOR PRESSURE MAINS
 - 30.12 CORROSION PROTECTION OF CAST IRON FOR PRESSURE MAINS
 - 30.13 AQUEDUCTS
 - 30.14 LOCATION MARKERS
 - 30.15 FLANGED JOINTS
 - 30.16 WELDING OF STEEL PRESSURE MAINS
 - 30.16.1 General
 - 30.16.2 Field welding of flanges
- 31 WET-WELLS AND MAINTENANCE HOLES (MHS)
 - 31.1 GENERAL
 - 31.2 WET-WELL AND MH BASES
 - 31.3 TRENCH DRAINAGE AROUND WET-WELLS AND MHS
 - 31.4 PRECAST CONCRETE SYSTEMS
 - 31.5 CAST IN-SITU CONCRETE WET-WELLS AND MHS
 - 31.6 BENCHING AND CHANNELS
 - 31.7 INTERNAL COATING OF CONCRETE WET-WELLS AND MHS

- 31.8 COVERS
- 31.9 CONNECTIONS TO WET-WELLS AND MHS
- 31.10 MH DROPS
- 32 PIPE EMBEDMENT AND SUPPORT
 - 32.1 GENERAL
 - 32.2 EMBEDMENT MATERIALS
 - 32.3 COMPACTION OF EMBEDMENT
 - 32.3.1 General
 - 32.3.2 Methods
 - 32.3.3 Compaction trials/Pre-qualification of embedment compaction method
 - 32.3.3.1 General
 - 32.3.3.2 Test method
 - 32.3.3.3 Interpretation and applicability
 - 32.3.4 Compaction control
 - 32.4 SPECIAL BEDDING AND EMBEDMENTS/GEOTEXTILE SURROUND AND PILLOW
 - 32.5 REMOVAL OF TRENCH SUPPORTS
 - 32.6 CONCRETE EMBEDMENT AND ENCASEMENT
- 33 FILL
 - 33.1 TRENCH FILL
 - 33.2 GENERAL
 - 33.3 MATERIAL REQUIREMENTS
 - 33.4 COMPACTION OF TRENCH FILL
 - 33.5 EMBANKMENT FILL
 - 33.6 DRIVES AND TUNNEL FILL
- 34 CONNECTION TO EXISTING GRAVITY SEWERS
- 35 RESTORATION
 - 35.1 GENERAL
 - 35.2 PAVEMENTS
 - 35.3 LAWNS
 - 35.4 GRASSED AREAS
 - 35.5 BUSHLAND
 - 35.6 PROVISION FOR SETTLEMENT
 - 35.7 MAINTENANCE OF RESTORED SURFACES
- 36 ACCEPTANCE TESTING
 - 36.1 PIPELINES
 - 36.2 VISUAL EXTERNAL INSPECTION
 - 36.3 COMPACTION TESTING
 - 36.3.1 General
 - 36.3.2 Minimum compaction
 - 36.3.3 Embedment compaction testing
 - 36.3.3.1 Applicable pipe sizes
 - 36.3.3.2 Frequency and location of embedment tests
 - 36.3.3.3 Retesting
 - 36.3.4 Trench fill compaction testing
 - 36.3.4.1 Trafficable test zone
 - 36.3.4.2 Non-trafficable test zone
 - 36.3.4.3 Test method
 - 36.3.4.4 Frequency and location of tests

- 36.3.4.5 Retesting
- 36.3.5 Other fill compaction testing
 - 36.3.5.1 General
 - 36.3.5.2 Trafficable test zone
 - 36.3.5.3 Non-trafficable test zone
 - 36.3.5.4 Frequency and location of tests
 - 36.3.5.5 Retesting
- 36.4 AIR PRESSURE AND VACUUM TESTING OF GRAVITY SEWERS
 - 36.4.1 General
 - 36.4.2 Air testing methods for sewers
 - 36.4.2.1 Vacuum testing
 - 36.4.2.2 Low pressure air testing
 - 36.4.3 Testing of concrete emergency storage and maintenance structures
 - 36.4.3.1 General
 - 36.4.3.2 Test method
- 36.5 HYDROSTATIC PRESSURE TESTING OF PRESSURE MAINS
 - 36.5.1 General
 - 36.5.2 System test pressure
 - 36.5.3 Maximum allowable loss
 - 36.5.4 Test procedure
 - 36.5.5 Satisfactory pressure test
 - 36.5.6 Failure of test
- 36.6 INFILTRATION TESTING
- 36.7 DEFLECTION (OVALITY) TESTING OF FLEXIBLE GRAVITY SEWERS
 - 36.7.1 General
 - 36.7.2 Ovality proving tools
 - 36.7.3 Flexible sewers \leq DN 300
- 36.8 CCTV INSPECTION
- 36.9 ELECTRICAL WORKS
- 37 COMMISSIONING
 - 37.1 GENERAL
 - 37.2 PUMPING STATION
 - 37.2.1 Requirements
 - 37.2.2 Pre-commissioning
 - 37.2.3 Commissioning
 - 37.2.4 Handover
 - 37.3 ODOUR CONTROL SYSTEM
- 38 TOLERANCES ON AS-CONSTRUCTED WORK
 - 38.1 HORIZONTAL TOLERANCES
 - 38.1.1 Sewers, mains, valves, in-line structures, pumping stations, roads
 - 38.2 VERTICAL TOLERANCES
 - 38.2.1 Sewers, pressure mains, structures, pumping stations, roads
 - 38.2.2 Grade
 - 38.3 VERTICALITY (“PLUMB”)
 - 38.4 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS
 - 38.5 CAST IN-SITU CONCRETE STRUCTURES AND SLABS
- 39 WORK AS-CONSTRUCTED DETAILS
 - 39.1 GENERAL
 - 39.2 ELECTRICAL WORKS

39.2.1 Electrical Contractors Installation Drawings

39.2.2 Principal Supplied Installation Drawings and Equipment Schedules

**APPENDIX G OVALITY TESTING OF PVC AND GRP GRAVITY SEWERS DEFAULT
PROVER DIAMETERS**

G1 GENERAL

G2 DEFAULT PROVER DIAMETERS

TABLES

TABLE 21.1	CONTROL CIRCUIT WIRING INSULATION COLOUR CODING
TABLE 26.1	TIMBER GUARDRAIL DEFAULT CONSTRUCTION DIMENSIONS
TABLE 27.1	RETAINING WALL DEFAULT CONSTRUCTION DIMENSIONS
TABLE 27.2	TIMBER HANDRAIL DEFAULT CONSTRUCTION DIMENSIONS
TABLE 30.1	METHODS OF ACHIEVING CURVED PIPELINES
TABLE 32.1	MAXIMUM PARTICLE SIZE
TABLE 36.1	ORDER OF ACCEPTANCE TESTING OF CIVIL ITEMS
TABLE 36.2	MINIMUM COMPACTION OF EMBEDMENT AND TRENCH / EMBANKMENT / OTHER FILLS
TABLE 36.3	PRESSURE AND VACUUM AIR TESTING ACCEPTANCE TIMES FOR 7 KPA PRESSURE CHANGE
TABLE 36.4	CONCRETE MH TESTING FREQUENCY
TABLE 36.5	MINIMUM TEST TIMES FOR CONCRETE STRUCTURES
TABLE 38.1	SEWER GRADE TOLERANCES
TABLE G1	PROVER OUTSIDE DIAMETER FOR PVC AND GRP PIPES
TABLE G2	MAXIMUM ALLOWABLE SHORT-TERM PIPE DEFLECTIONS



WATER SERVICES ASSOCIATION
of Australia

Sewage Pumping Station Code of Australia

WSA 04—2005

Part 4: Standard Drawings

Second Edition Version 2.1

CONTENTS

40 INTRODUCTION

40.1 GENERAL

40.2 DRAWING COMMENTARY

41 LISTING OF STANDARD DRAWINGS

41 LISTING OF STANDARD DRAWINGS

DRAWING NUMBER	ACTIVITY	TITLE
PLANNING AND CONCEPT DESIGN		
SPS-1100	Concept Plan	Typical Catchment Plan
SPS-1101	Pumping Station Concept Design	Site Layout
SPS-1102	Pumping Station Concept Design	Site Plan
SPS-1103	Pumping Station Concept Design	Power and Control Cubicle, Base and Conduit Details
SPS-1104	Pressure Main Concept Design	Sections and Mean Static Head Calculation
PUMPING STATION LAYOUT		
SPS-1200	Typical Site Plan – Sydney Water	Fronting and Not Fronting Adjacent Roadway
SPS-1201	Typical Site Plan – SA Water	Fronting Adjacent Roadway
SPS-1202	Typical Site Plan – SA Water	Not Fronting Adjacent Roadway
SPS-1203	Typical Site Plan – Brisbane Water	Fronting Adjacent Roadway
SPS-1204	Typical Site Plan – Water Corporation	Fronting Adjacent Roadway
SPS-1205	Access Roadway	Cross Section and Drainage Details
PUMPING STATION ARRANGEMENT		
SPS-1300	General Arrangement	Inlet MH, Wet-Well and Valve Chamber
SPS-1301	Detailed Arrangement	Wet-Well, Buried Valves, DN 100 Pipework
SPS-1302	Civil Plan	Wet-Well and Valve Chamber
SPS-1303	Wet-Well Construction	Pre-Cast Concrete Components
SPS-1304	Wet-Well Construction	Cover and Access Hole Details
SPS-1305	Electrical and Telemetry	Conduit Details
SPS-1306	Valve Chamber Adjacent to Wet-Well	Plan, Section and Cover – Non-Trafficable
SPS-1307	Valve Chamber Adjacent to Wet-Well	Pipework
SPS-1308	Water Supply	Reduced Pressure Zone Arrangement
SPS-1309	Mobile Pump Connection Arrangement	Pumping Stations ≤40 L/s
SPS-1310	Mobile Pump Connection Arrangement	Pumping Stations >40 L/s
STRUCTURES		
SPS-1400	Grit Collection MH	Detailed Arrangement
SPS-1401	Grit Collection MH	Detailed Arrangement
SPS-1402	Emergency Storage	Typical Arrangement and Levels Configuration 1
SPS-1403	Emergency Storage Details	Shallow and Deep Installations and Brickwork
SPS-1404	Emergency Relief System	Arrangement and Cross Section for DN 150 to DN 375 Overflow Pipes
SPS-1405	Discharge MH	Arrangement and Cross Section for Pressure Mains ≤ DN 300
SEW-1300	Maintenance Holes	Sewers ≤ DN 300 Precast Types P1 & P2

DRAWING NUMBER	ACTIVITY	TITLE
SEW-1301	Maintenance Holes	Sewers \leq DN 300 Cast Insitu Types C1 & C2
SEW-1302	Maintenance Holes	Pipe Connection Details
SEW-1303	Maintenance Holes	Sewers \leq DN 300 Changes in Level Details
SEW-1304	Maintenance Holes	For Sewers \leq DN 300 Typical Channel Arrangements
SEW-1305	Maintenance Holes	Typical Channel Details
SEW-1306	Maintenance Holes	Alternative Drop Connections
SEW-1307	Maintenance Holes	Step Irons & Ladders
SEW-1308	Maintenance Holes	Typical MH Cover Arrangements
SEW-1313	Maintenance Holes	MH Connection Details DN 110 to DN 450 PE Pipe
SEW-1314	Maintenance Shafts	Typical Installation
SEW-1315	Maintenance Shafts	MS & Variable Bend Installations
SEW-1316	Maintenance Shafts	TMS and Connection Installations
SEW-1317	Maintenance Holes	Typical MS Cover Arrangements
WET-WELL APPURTENANCES		
SPS-1500	Pump to Pressure Main Connection	Hose Connection Bend Assemblies
SPS-1501	Pump to Pressure Main Connection	Wall Pipe Bracket Assemblies
SPS-1502	Pump to Pressure Main Connection	Wall Pipe Bracket Details
SPS-1503	Pump to Pressure Main Connection	Hose Connection Bends
SPS-1504	Pump to Pressure Main Connection	Hose Connection Bend Quick Coupling Details
SPS-1505	Hydraulic Level Sensor	Stilling Tube
SPS-1506	External Hinged Covers	Opening Grate Type
SPS-1507	External Hinged Covers	Opening Grate Type
SPS-1508	Miscellaneous Details	Survey Plate, Pump Label Plate, Valve Spindle Access
PRESSURE MAINS		
SPS-1600	Design	Typical Pressure Main Characteristic Curve
SPS-1601	Pipe Installation, Support and Trench Fill	Pressure Mains \leq DN 300
SPS-1602	Scour Arrangement	Pump and Gravity
SPS-1603	Scour Arrangement	Pressure Mains \leq DN 300 \leq 2.2 m to Invert
SPS-1604	Scour Arrangement	Pressure Mains \leq DN 300 $>$ 2.2 m to Invert
SPS-1605	Gas Release Arrangement	Pressure Mains \leq DN 300
SPS-1606	Gas Release Arrangement	Pressure Mains $>$ DN 300

DRAWING NUMBER	ACTIVITY	TITLE
EMBEDMENT / TRENCHFILL AND SUPPORT SYSTEMS		
SEW-1200	Soil Classification Guidelines And	Allowable Bearing Pressures for Bulkheads
SEW-1201	Embedment and Trenchfill	Typical Arrangements
SEW-1202	Standard Embedment	Flexible & Rigid Pipes
SEW-1203	Special Embedment	Inadequate Foundations Requiring Over Excavation & Replacement
SEW-1204	Special Embedment	Support Utilising Piles
SEW-1206	Trench Drainage	Bulkheads & Trenchstop
SEW-1207	Trench Drainage	Typical Systems
SEW-1208	Verticals & Near Verticals	Exposed & Concealed Methods
WAT-1201	Embedment & Trenchfill	Typical Arrangement
WAT-1202	Standard Embedment	All Pipe Types
WAT-1203	Special Embedments	Inadequate and Poor Foundation
WAT-1204	Special Embedments	Concrete, Geotextile and Cement Stabilised Systems
WAT-1205	Thrust Block Details	Concrete Blocks
WAT-1206	Thrust Block Details	Timber & Recycled Plastic Blocks
WAT-1207	Thrust and Anchor Blocks	Gate Valves and Vertical Bends
WAT-1208	Restrained Joint System	DN 100 to DN 375 DI Mains
WAT-1209	Trench Drainage	Bulkheads and Trenchstop
WAT-1210	Trench Drainage	Typical Systems
WAT-1211	Buried Crossings	Under Obstructions
WAT-1212	Buried Crossings	Major Roadways
WAT-1213	Buried Crossings	Railways
WAT-1214	Buried Crossings	Bored & Jacked Encasing Pipe Details
SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS		
SEW-1400	Buried Crossings	Syphon Arrangement
SEW-1401	Buried Crossings	Railways
SEW-1402	Buried Crossings	Major Roadways
SEW-1403	Buried Crossings	Bored & Jacked Encasing Pipe Details
SEW-1406	Aerial Crossings	Bridge Crossing Concepts
SEW-1407	Ventilation Systems	Induct Vent
SEW-1408	Ventilation Systems	Educt Vent

DRAWING NUMBER	ACTIVITY	TITLE
INSTALLATION PRACTICES/ STRUCTURES		
WAT-1300	Valve and Hydrant Identification	Identification Markers & Marker Posts
WAT-1303	Typical Surface Fitting Installation	Gate Valve Surface Boxes Non Trafficable
WAT-1304	Typical Surface Fitting Installation	Gate Valve Surface Boxes Trafficable
WAT-1307	Typical Appurtenance Installation	Scour Arrangements
WAT-1310	Aerial Crossings	Aqueduct
WAT-1311	Aerial Crossings	Aqueduct Protection Grille
WAT-1312	Aerial Crossings	Bridge Crossing Concepts
WAT-1313	Flanged Joints	Bolting Details
FABRICATION DETAILS		
WAT-1400	Typical Steel Pipe Jointing	Butt Welding of Joints
WAT-1401	Typical Steel Pipe Jointing	Rubber Ring Joint Spigot Bands
WAT-1402	Typical Steel Pipe Jointing	Welded Pipe Collars
WAT-1403	Typical Steel Fabrication	Bends
WAT-1408	Joint Corrosion Protection	Cement Mortar Lined Steel Pipe DN 300 to DN 1200
WAT-1409	Hydrant Installation Fittings	PE Assemblies