



WATER SERVICES
ASSOCIATION OF AUSTRALIA

SEWAGE PUMPING STATION CODE OF AUSTRALIA

Version 3.1

WSA 04-2022

Contents

| | |
|--|----|
| List of Figures..... | 36 |
| List of Tables..... | 40 |
| FRONTMATTER..... | 2 |
| GENERAL..... | 2 |
| ACKNOWLEDGEMENTS..... | 2 |
| PUBLICATION HISTORY..... | 2 |
| ABOUT WSAA..... | 2 |
| ACKNOWLEDGEMENT OF COUNTRY..... | 3 |
| DISCLAIMER..... | 3 |
| COPYRIGHT..... | 3 |
| ALL RIGHTS RESERVED | 3 |
| FOREWORD..... | 3 |
| PREFACE..... | 4 |
| THE NEED FOR TECHNICAL DOCUMENTATION..... | 4 |
| THE BENEFITS OF NATIONAL CODES..... | 4 |
| INNOVATION..... | 5 |
| HYPOTHETICAL EXAMPLE OF THE USE OF THE GRAVITY SEWERAGE AND SEWAGE PUMPING STATION CODES..... | 6 |
| Concept Plan..... | 6 |
| Agency/Development Agreement..... | 6 |
| Project Manager..... | 6 |
| Design..... | 6 |
| Specification..... | 6 |
| Constructor..... | 6 |
| Testing..... | 7 |
| The WSAA Website..... | 7 |
| INTRODUCTION..... | 7 |
| Scope of Code..... | 7 |
| Code Purpose..... | 7 |
| Mandatory and Informative..... | 7 |
| Appendices..... | 8 |
| Standard Drawings and Figures..... | 8 |
| Product Specifications..... | 8 |
| General..... | 8 |
| Quality Assurance..... | 8 |
| Packaging, Transportation and Delivery..... | 9 |
| Products and Material Information and Guidance..... | 9 |
| Water Industry Standards..... | 9 |
| WORK HEALTH AND SAFETY (WHS) LAWS..... | 9 |
| NATIONAL STANDARD FOR CONSTRUCTION WORK..... | 9 |
| SAFE DESIGN OF STRUCTURES..... | 10 |
| PROPOSED AMENDMENTS..... | 11 |
| GLOSSARY, ABBREVIATIONS AND REFERENCES..... | 43 |
| I GLOSSARY OF TERMS..... | 43 |
| II ABBREVIATIONS..... | 49 |
| III REFERENCED DOCUMENTS..... | 55 |
| PART 1: PLANNING AND DESIGN..... | 67 |
| PREFACE..... | 67 |
| 1 GENERAL..... | 69 |
| 1.1 SCOPE..... | 69 |

| | |
|--|----|
| 1.2 PLANNING..... | 69 |
| 1.2.1 General..... | 69 |
| 1.2.2 Pumping alternatives..... | 69 |
| 1.3 SEWAGE PUMPING STATIONS..... | 70 |
| 1.3.1 Pumping philosophy..... | 70 |
| 1.4 PURPOSE AND APPLICATION..... | 70 |
| 1.5 PLANNING AND DESIGN RESPONSIBILITIES AND INTERFACES..... | 71 |
| 1.5.1 General..... | 71 |
| 1.5.2 Planning responsibilities..... | 71 |
| 1.5.3 Design responsibilities..... | 71 |
| 1.5.4 Critical infrastructure protection..... | 73 |
| 1.5.4.1 General..... | 73 |
| 1.5.4.2 Asset categorisation..... | 73 |
| 1.5.4.3 All hazards – infrastructure protection..... | 74 |
| 1.5.5 Consultation with other parties..... | 74 |
| 1.6 SEWER SYSTEM DESIGN APPROACH..... | 74 |
| 1.6.1 Overall objective..... | 74 |
| 1.6.2 System design life..... | 74 |
| 1.6.3 Instrumentation and control systems..... | 75 |
| 1.6.4 Objectives of design..... | 75 |
| 1.6.5 Design output..... | 77 |
| 2 CONCEPT DESIGN..... | 78 |
| 2.1 LIFE CYCLE CONSIDERATIONS..... | 78 |
| 2.2 FUNCTIONALITY..... | 78 |
| 2.3 MAINTAINABILITY..... | 79 |
| 2.4 RELIABILITY..... | 79 |
| 2.5 DUE DILIGENCE REQUIREMENTS..... | 79 |
| 2.6 MATERIALS DESIGN..... | 81 |
| 2.7 STAGING..... | 81 |
| 2.8 SEPTICITY CONTROL..... | 81 |
| 2.8.1 General..... | 81 |
| 2.8.2 Detention time..... | 82 |
| 2.9 ODOUR MANAGEMENT..... | 82 |
| 2.10 NOISE CONTROL..... | 82 |
| 2.11 SERVICES..... | 83 |
| 2.12 ACCESS..... | 83 |
| 2.13 SECURITY..... | 83 |
| 2.14 SIGNAGE..... | 83 |
| 2.15 SUPPORTING SYSTEMS..... | 83 |
| 2.16 HEALTH AND SAFETY..... | 84 |
| 3 GENERAL DESIGN..... | 85 |
| 3.1 GENERAL..... | 85 |
| 3.2 DESIGN ACCURACY..... | 85 |
| 3.3 LEVELS..... | 85 |
| 3.4 UNFORESEEN GROUND CONDITIONS..... | 85 |
| 3.5 IMPACT OF CONSEQUENTIAL DAMAGE..... | 86 |
| 3.6 ENVIRONMENTAL, CULTURAL AND HERITAGE CONSIDERATIONS..... | 86 |
| 3.6.1 General..... | 86 |
| 3.6.2 Urban salinity..... | 87 |
| 3.6.3 Acid sulphate soils..... | 87 |
| 3.6.4 Effect on vegetation..... | 88 |

| | |
|---|-----|
| 3.6.5 Contaminated sites..... | 88 |
| 3.6.6 Climate change impacts..... | 88 |
| 3.6.6.1 Context..... | 88 |
| 3.6.6.2 AdaptWater tool..... | 89 |
| 3.6.6.3 Australian infrastructure adaptation platform, the Cross Dependency Initiative (XDI)..... | 89 |
| 3.6.7 Coastal zones..... | 89 |
| 3.7 EASEMENTS..... | 90 |
| 3.8 CROSSINGS..... | 90 |
| 3.8.1 General..... | 90 |
| 3.8.1.1 Requirements for encased pipe installations..... | 91 |
| 3.8.1.2 Railway reserves..... | 92 |
| 3.8.2 Creeks and drainage reserves..... | 92 |
| 3.8.3 Major roads..... | 92 |
| 3.9 FUTURE MAINTENANCE..... | 92 |
| 3.10 OVERHEAD POWER LINES AND TRANSMISSION TOWERS..... | 92 |
| 3.11 OBSTRUCTIONS AND CLEARANCES..... | 93 |
| 3.11.1 General..... | 93 |
| 3.11.2 Surface obstructions..... | 93 |
| 3.11.3 Clearance from transmission towers..... | 93 |
| 3.11.4 Clearance from structures..... | 93 |
| 3.11.5 Underground obstructions and services..... | 93 |
| 3.11.5.1 General..... | 93 |
| 3.11.5.2 Clearance requirements..... | 93 |
| 3.11.6 Crossing services..... | 95 |
| 3.11.7 Location markers..... | 95 |
| 3.11.8 Marking tape..... | 95 |
| 3.11.8.1 General..... | 95 |
| 3.11.8.2 Pressure mains..... | 95 |
| 3.12 DISUSED OR REDUNDANT ITEMS..... | 96 |
| 3.13 SEWAGE QUALITY..... | 96 |
| 3.13.1 Septicity..... | 96 |
| 3.13.2 ARC Sewer Corrosion and Odour Research (SCORE) Linkage Project..... | 97 |
| 3.13.3 Sewage quality/Trade waste management..... | 97 |
| 3.13.4 Australian Sewage Quality Management Guidelines..... | 97 |
| 3.14 COMMISSIONING PLAN..... | 97 |
| 3.14.1 General..... | 97 |
| 3.14.2 Pre-commissioning..... | 98 |
| 3.14.3 Commissioning..... | 99 |
| 4 MATERIALS DESIGN..... | 101 |
| 4.1 GENERAL..... | 101 |
| 4.2 PROTECTION AGAINST DEGRADATION..... | 101 |
| 4.2.1 General..... | 101 |
| 4.2.2 Protective coatings..... | 101 |
| 4.2.3 Concrete surfaces..... | 101 |
| 4.2.4 Metallic materials..... | 101 |
| 4.2.5 Stainless steels..... | 102 |
| 4.2.5.1 Grade selection..... | 102 |
| 4.2.5.2 Welding..... | 102 |
| 4.2.5.3 Threaded components..... | 102 |
| 4.2.6 Corrosion protection against aggressive environments..... | 103 |

| | |
|--|-----|
| 4.2.7 Cathodic protection..... | 103 |
| 4.2.8 Stray current corrosion..... | 104 |
| 4.2.9 Protection against contaminated ground..... | 104 |
| 4.2.10 Bolted connection..... | 105 |
| 5 PRODUCTS AND MATERIALS..... | 107 |
| 5.1 GENERAL..... | 107 |
| 5.2 IDENTIFICATION OF SEWER SYSTEMS..... | 107 |
| 5.3 SERVICABILITY OF SEWER SYSTEMS..... | 110 |
| 5.4 PVC PIPELINE SYSTEMS..... | 110 |
| 5.4.1 Product Specifications..... | 110 |
| 5.4.2 PVC Pressure Pipeline Systems..... | 111 |
| 5.4.2.1 Sizes and configurations..... | 111 |
| 5.4.3 PVC Non-Pressure Systems..... | 111 |
| 5.4.3.1 Sizes and configurations..... | 111 |
| 5.5 PE PIPELINE SYSTEMS..... | 112 |
| 5.5.1 Product Specifications..... | 112 |
| 5.5.2 Size and Configuration..... | 113 |
| 5.6 PP PIPELINE SYSTEMS..... | 113 |
| 5.6.1 Product Specifications..... | 113 |
| 5.6.2 Sizes and configurations..... | 113 |
| 5.7 DUCTILE IRON PIPE SYSTEMS..... | 114 |
| 5.7.1 Product Specifications..... | 114 |
| 5.7.2 Sizes and configurations..... | 114 |
| 5.7.3 Lining..... | 114 |
| 5.7.4 Coatings..... | 115 |
| 5.7.5 Sleeving..... | 116 |
| 5.7.6 Screw-on flanges for DI pipes..... | 116 |
| 5.7.7 Flanged joints..... | 116 |
| 5.7.8 Pump discharge flanged ductile iron pipework | 117 |
| 5.8 GRP PIPELINE SYSTEMS..... | 117 |
| 5.8.1 Product Specifications..... | 117 |
| 5.8.2 Sizes and configurations..... | 117 |
| 5.9 ABS PRESSURE PIPE SYSTEMS..... | 117 |
| 5.9.1 Product Specifications..... | 117 |
| 5.9.2 Size and configuration..... | 118 |
| 5.10 STEEL PRESSURE PIPE SYSTEMS..... | 118 |
| 5.10.1 Product Specifications..... | 118 |
| 5.10.2 Sizes and configurations..... | 118 |
| 5.10.3 Joints..... | 118 |
| 5.10.4 Lining..... | 119 |
| 5.10.5 Field welding..... | 119 |
| 5.10.6 Flanged joints..... | 119 |
| 5.11 ACCESS COVERS AND FRAMES..... | 120 |
| 5.11.1 Product Specifications..... | 120 |
| 5.11.2 Application..... | 120 |
| 5.11.3 Cast ductile iron access covers and frames..... | 121 |
| 5.11.4 Aluminium checker plate access covers and frames..... | 121 |
| 5.11.5 Stainless steel checker plate access covers and frames..... | 121 |
| 5.11.6 Polymeric access covers and frames..... | 121 |
| 5.11.7 Safety Grates..... | 122 |
| 5.11.8 Size and configuration..... | 122 |

| | |
|--|-----|
| 5.11.9 Marking of access covers and frames..... | 122 |
| 5.12 VENT SHAFTS..... | 122 |
| 5.12.1 Product Specification..... | 122 |
| 5.12.2 Application..... | 122 |
| 6 PUMPING STATION DESIGN..... | 123 |
| 6.1 INTRODUCTION..... | 123 |
| 6.2 SITE SELECTION, LOCATION AND LAYOUT..... | 123 |
| 6.2.1 Site selection..... | 123 |
| 6.2.2 Right of occupancy and access..... | 123 |
| 6.2.3 Location and layout..... | 123 |
| 6.2.4 Site area..... | 124 |
| 6.2.5 Site layout and access..... | 124 |
| 6.2.6 Landscaping..... | 124 |
| 6.3 INLET MH..... | 125 |
| 6.3.1 Location..... | 125 |
| 6.3.2 Design..... | 125 |
| 6.3.3 Pumping station wet-well isolating valve..... | 126 |
| 6.4 WET-WELL DESIGN..... | 126 |
| 6.4.1 General..... | 126 |
| 6.4.2 Sizing..... | 127 |
| 6.4.3 Pumping control volume and pump starts..... | 127 |
| 6.4.4 Control levels..... | 128 |
| 6.4.5 Detention time..... | 128 |
| 6.4.6 Benching..... | 128 |
| 6.4.7 Washers..... | 129 |
| 6.5 WET-WELL VENTILATION..... | 129 |
| 6.5.1 General..... | 129 |
| 6.5.2 Natural ventilation..... | 130 |
| 6.5.3 Forced ventilation..... | 130 |
| 6.6 OVERFLOW CONTAINMENT..... | 131 |
| 6.6.1 General..... | 131 |
| 6.6.2 Emergency storage..... | 131 |
| 6.6.2.1 General..... | 131 |
| 6.6.2.2 Configurations..... | 131 |
| 6.6.2.3 Design..... | 133 |
| 6.6.2.4 Access and cover arrangements for emergency storage structure..... | 142 |
| 6.6.2.5 Type of construction..... | 142 |
| 6.6.3 Future storage provisions..... | 143 |
| 6.6.4 Emergency relief system..... | 143 |
| 6.7 LADDERS AND PLATFORMS..... | 143 |
| 6.8 WET-WELL ACCESS COVERS..... | 144 |
| 6.9 SAFETY SYSTEMS..... | 144 |
| 6.10 GRIT COLLECTION..... | 145 |
| 6.11 SCREENS..... | 145 |
| 6.12 MIXERS..... | 145 |
| 7 PUMPING SYSTEM..... | 146 |
| 7.1 STAGING..... | 146 |
| 7.2 HYDRAULIC DESIGN..... | 146 |
| 7.3 PUMP EQUIPMENT..... | 147 |
| 7.4 PUMP SELECTION..... | 147 |
| 7.5 MULTIPLE-PUMP PUMPING STATIONS..... | 148 |

| | |
|--|-----|
| 7.6 SUBMERSIBLE PUMPS..... | 148 |
| 7.6.1 General..... | 148 |
| 7.6.2 Impeller selection..... | 149 |
| 7.6.3 Motor selection..... | 149 |
| 7.6.4 Standard discharge connection..... | 149 |
| 7.6.5 Motor cables..... | 149 |
| 7.6.6 Pump lifting equipment..... | 150 |
| 7.7 ANCILLARY EQUIPMENT..... | 151 |
| 7.7.1 Flushing valves..... | 151 |
| 7.8 PUMP STARTERS AND VARIABLE SPEED DRIVES..... | 151 |
| 7.8.1 General..... | 151 |
| 7.8.2 Motor starters..... | 151 |
| 7.8.3 Soft starters..... | 152 |
| 7.8.4 Variable speed drives..... | 152 |
| 7.9 HARMONICS AND RADIO FREQUENCY INTERFERENCE..... | 153 |
| 7.10 EMERGENCY STOP..... | 153 |
| 8 POWER SYSTEM..... | 154 |
| 8.1 GENERAL..... | 154 |
| 8.2 POWER SUPPLIES..... | 154 |
| 8.2.1 General..... | 154 |
| 8.2.2 Security of supply..... | 154 |
| 8.2.3 Primary supply..... | 154 |
| 8.2.4 Duplicate supply..... | 155 |
| 8.2.5 Emergency power..... | 155 |
| 8.2.6 On-site generator..... | 155 |
| 8.2.7 Mobile generator..... | 156 |
| 8.2.8 High voltage/Low voltage switching..... | 156 |
| 8.2.9 Power factor correction..... | 156 |
| 8.3 POWER AND CONTROL CUBICLE..... | 156 |
| 8.3.1 Design..... | 156 |
| 8.3.2 Low voltage switchboards..... | 157 |
| 8.3.2.1 Standards..... | 157 |
| 8.3.2.2 Construction..... | 158 |
| 8.3.2.3 Rated diversity factor..... | 158 |
| 8.3.2.4 Degree of protection..... | 158 |
| 8.3.2.5 Rated insulation and operating voltages..... | 158 |
| 8.3.2.6 Creepage distances..... | 159 |
| 8.3.2.7 Rated impulse withstand voltage..... | 159 |
| 8.3.2.8 Rated short-time current..... | 159 |
| 8.3.2.9 Internal arcing fault protection..... | 159 |
| 8.3.3 Meter requirements..... | 159 |
| 8.3.4 Lighting..... | 160 |
| 9 CONTROL AND TELEMETRY SYSTEM..... | 161 |
| 9.1 GENERAL..... | 161 |
| 9.2 OPERATING LEVELS AND SETTINGS..... | 161 |
| 9.3 PUMPING CONTROL..... | 161 |
| 9.3.1 Control design..... | 161 |
| 9.3.2 Control switches..... | 161 |
| 9.3.3 Control systems..... | 162 |
| 9.3.4 Emergency back-up control..... | 162 |
| 9.3.5 Pump starts and interlocks..... | 162 |

| | |
|---|-----|
| 9.4 ALARMS..... | 162 |
| 9.4.1 General..... | 162 |
| 9.4.2 Locally displayed alarms..... | 163 |
| 9.4.3 Remote alarms..... | 163 |
| 9.5 ALARM, STATUS MONITORING AND CONTROL TELEMETRY..... | 163 |
| 9.5.1 General design principles..... | 163 |
| 9.5.2 Reliability..... | 163 |
| 9.5.3 Alarm creation function..... | 164 |
| 9.5.4 Status monitoring function..... | 165 |
| 9.5.5 Control function..... | 166 |
| 9.6 TELEMETRY HARDWARE..... | 166 |
| 9.6.1 General..... | 166 |
| 9.6.2 Software..... | 167 |
| 9.6.3 Inputs and outputs..... | 167 |
| 9.6.4 Telemetry communications..... | 167 |
| 9.6.5 Communication validation..... | 167 |
| 9.7 OPERATING LEVELS AND DEFAULT SETTINGS..... | 168 |
| 9.7.1 General..... | 168 |
| 9.7.2 Cut-in and cut-out levels..... | 168 |
| 9.7.3 Alarm levels..... | 168 |
| 9.8 EQUIPMENT AND DEVICES..... | 169 |
| 9.8.1 General..... | 169 |
| 9.8.2 Flow measurement..... | 169 |
| 9.8.3 Flowmeter cabling..... | 169 |
| 9.8.4 Suction safety switch..... | 169 |
| 9.8.5 Level sensors..... | 170 |
| 9.8.6 Float-switch or fail-safe level probe..... | 170 |
| 9.8.7 Site access monitoring..... | 170 |
| 9.8.8 Protection devices..... | 171 |
| 9.8.8.1 Fuse and fuse-links..... | 171 |
| 9.8.8.2 Moulded-case circuit-breakers..... | 171 |
| 9.8.8.3 Miniature circuit-breakers..... | 171 |
| 9.8.8.4 Residual current devices..... | 171 |
| 9.8.8.5 Thermal-overload relays..... | 172 |
| 9.8.8.6 Electronic motor protection relays..... | 172 |
| 9.8.8.7 Thermistor and RTD motor protection devices..... | 172 |
| 9.8.9 Switching devices..... | 173 |
| 9.8.9.1 Switches..... | 173 |
| 9.8.9.2 Selector switches..... | 173 |
| 9.8.10 Contactors..... | 173 |
| 9.8.11 Push-buttons..... | 173 |
| 9.8.12 Emergency stop-buttons..... | 173 |
| 9.8.13 Time-switches..... | 174 |
| 9.8.14 Control devices..... | 174 |
| 9.8.14.1 Control relays..... | 174 |
| 9.8.14.2 Time-delay relays and timers..... | 174 |
| 9.8.15 ELV control transformers..... | 174 |
| 9.8.16 Current transformers..... | 174 |
| 9.9 INSTRUMENTATION (DISPLAYS)..... | 175 |
| 9.10 WIRE NUMBERING CONVENTION..... | 175 |
| 9.11 SYSTEMS INCORPORATING PROGRAMMABLE CONTROLLER / TELEMETRY RTU..... | 175 |

| | | |
|----------|--|-----|
| 9.11.1 | Digital inputs and outputs..... | 175 |
| 9.11.2 | Analog inputs and outputs..... | 175 |
| 9.11.3 | Address codes for communication link devices..... | 175 |
| 9.12 | SYSTEMS INCORPORATING RELAY CONTROL..... | 175 |
| 9.12.1 | General..... | 175 |
| 9.12.2 | Loop tag definition guidelines..... | 176 |
| 10 | PUMPING STATION PIPEWORK..... | 177 |
| 10.1 | PUMP DISCHARGE PIPEWORK..... | 177 |
| 10.1.1 | General..... | 177 |
| 10.1.2 | Sizing..... | 177 |
| 10.1.3 | Type..... | 177 |
| 10.2 | VALVE APPLICATIONS..... | 177 |
| 10.2.1 | Isolating valves..... | 177 |
| 10.2.2 | Non-return valves..... | 178 |
| 10.3 | VALVE CHAMBER..... | 178 |
| 10.3.1 | General..... | 178 |
| 10.3.2 | Design..... | 179 |
| 10.3.3 | Dismantling joints..... | 179 |
| 10.3.4 | Pipework support..... | 180 |
| 10.3.5 | Pressure main tapping points..... | 180 |
| 10.3.6 | Access covers..... | 180 |
| 10.4 | EMERGENCY PUMPING ARRANGEMENTS..... | 181 |
| 10.4.1 | General..... | 181 |
| 10.4.2 | Temporary pumping from inlet MH into pressure main..... | 181 |
| 10.4.3 | Temporary pumping from wet-well into tanker trucks..... | 182 |
| 10.4.4 | Using on-board tanker truck pumps..... | 182 |
| 10.5 | CONDITION MONITORING AND MAINTENANCE..... | 182 |
| 11 | PRESSURE MAINS..... | 184 |
| 11.1 | DESIGN..... | 184 |
| 11.1.1 | General..... | 184 |
| 11.1.2 | Pressure mains shared by Multiple pump stations..... | 184 |
| 11.2 | LOCATION OF PRESSURE MAINS..... | 184 |
| 11.2.1 | General..... | 184 |
| 11.2.2 | Road reserves..... | 185 |
| 11.2.3 | Railway reserves..... | 185 |
| 11.2.4 | Vertical alignment..... | 185 |
| 11.2.4.1 | Falling Main..... | 186 |
| 11.2.4.2 | Barometric pipe loop..... | 187 |
| 11.2.4.3 | Connecting different pipe dimeters and materials..... | 188 |
| 11.2.5 | Horizontal alignment..... | 188 |
| 11.2.6 | Deviation of pressure mains around structures..... | 188 |
| 11.2.6.1 | General..... | 188 |
| 11.2.6.2 | Methods to deviate pressure mains around structures..... | 189 |
| 11.2.6.3 | Horizontal deviation of pressure mains..... | 189 |
| 11.2.6.4 | Vertical deviation of pressure mains..... | 190 |
| 11.2.6.5 | Curving of pressure mains to avoid obstructions or on curved alignments..... | 193 |
| 11.3 | PUMP HEAD CALCULATIONS..... | 193 |
| 11.3.1 | Total head..... | 193 |
| 11.3.2 | Mean static head..... | 193 |
| 11.3.3 | Friction head loss..... | 194 |
| 11.3.4 | Head loss in fittings and valves..... | 195 |

| | |
|---|-----|
| 11.3.5 System characteristic curves..... | 195 |
| 11.3.6 Velocity in pressure mains (including flush cycles)..... | 195 |
| 11.3.7 Sizing of pressure mains..... | 197 |
| 11.4 DESIGN PRESSURES..... | 198 |
| 11.4.1 General..... | 198 |
| 11.4.2 Design pressure..... | 198 |
| 11.4.3 Surge..... | 198 |
| 11.4.4 Maximum design pressure range..... | 199 |
| 11.5 SELECTION OF PIPE AND FITTINGS PRESSURE CLASS..... | 199 |
| 11.5.1 General..... | 199 |
| 11.5.2 Maximum allowable operating pressure..... | 199 |
| 11.5.3 Maximum cyclic pressure range – Thermoplastics pipes and fittings..... | 200 |
| 11.5.4 Minimum pressure class..... | 200 |
| 11.5.5 Other considerations..... | 200 |
| 11.6 PLASTICS PIPES..... | 200 |
| 11.6.1 Plastics pipes and fittings requirements..... | 200 |
| 11.6.2 Fatigue design for thermoplastics pipes..... | 201 |
| 11.6.3 Fatigue design for thermoplastic fittings..... | 203 |
| 11.6.4 Fatigue design for thermosetting pipes and fittings..... | 203 |
| 11.6.5 Combined effects of fatigue and temperature..... | 203 |
| 11.7 METALLIC PIPES AND FITTINGS..... | 203 |
| 11.8 PIPELINE MATERIALS..... | 203 |
| 11.9 PRESSURE MAIN VALVES..... | 204 |
| 11.9.1 General..... | 204 |
| 11.9.2 Isolating valves..... | 204 |
| 11.9.3 Air release valves..... | 204 |
| 11.9.4 Non-return valves..... | 205 |
| 11.9.5 Scours..... | 205 |
| 11.9.6 Low points without a scour..... | 206 |
| 11.10 ODOUR AND SEPTICITY CONTROL..... | 206 |
| 11.11 RECEIVING SYSTEM..... | 207 |
| 11.11.1 General..... | 207 |
| 11.11.2 Discharge MHs..... | 207 |
| 12 STRUCTURAL DESIGN..... | 209 |
| 12.1 GROUND CONDITIONS..... | 209 |
| 12.1.1 Foundation design and ground water control..... | 209 |
| 12.1.2 Geotechnical assessment..... | 209 |
| 12.2 STRUCTURES..... | 210 |
| 12.2.1 Design loads and forces..... | 210 |
| 12.2.2 Concrete structures..... | 211 |
| 12.2.2.1 General..... | 211 |
| 12.2.2.2 Concrete strength..... | 211 |
| 12.2.2.3 Minimum cover..... | 211 |
| 12.2.2.4 Crack control requirement for serviceability..... | 211 |
| 12.2.2.5 Areas to be designed as liquid retaining surfaces..... | 211 |
| 12.2.3 Steel structures..... | 211 |
| 12.2.4 Foundations..... | 211 |
| 12.2.5 Pumping station walls..... | 212 |
| 12.2.6 Base slab..... | 213 |
| 12.2.7 Top slab..... | 213 |
| 12.2.8 Emergency storage structures..... | 213 |

| | |
|--|-----|
| 12.3 PRESSURE MAINS..... | 213 |
| 12.3.1 General..... | 213 |
| 12.3.2 Structural consideration..... | 213 |
| 12.3.3 Internal forces..... | 214 |
| 12.3.4 External forces..... | 214 |
| 12.3.4.1 General..... | 214 |
| 12.3.4.2 Pipe cover..... | 214 |
| 12.3.4.3 Trench design..... | 215 |
| 12.3.4.4 Pipe embedment..... | 215 |
| 12.3.4.5 Buoyancy..... | 215 |
| 12.3.5 Specific geotechnical considerations..... | 215 |
| 12.3.5.1 Pressure mains in engineered and/or controlled fill..... | 215 |
| 12.3.5.2 Pressure mains in non-engineered fill..... | 216 |
| 12.3.5.3 Filling along route of pressure main..... | 216 |
| 12.3.5.4 Mine subsidence..... | 216 |
| 12.3.5.5 Slip areas..... | 217 |
| 12.3.5.6 Water-changed ground..... | 217 |
| 12.3.6 Concrete encasement..... | 217 |
| 12.3.6.1 General..... | 217 |
| 12.3.6.2 Requirements..... | 218 |
| 12.3.6.3 Encased steel pipelines..... | 219 |
| 12.3.6.4 Existing steel pipelines..... | 219 |
| 12.3.7 Above ground crossings..... | 220 |
| 12.3.8 Bulkheads and trenchstops..... | 221 |
| 12.3.9 Trenchless technology..... | 221 |
| 12.3.9.1 Geotechnical Investigations..... | 222 |
| 12.3.10 Pressure main anchorage..... | 222 |
| 12.3.10.1 General..... | 222 |
| 12.3.10.2 Thrust blocks..... | 223 |
| 12.3.10.3 Anchor blocks..... | 223 |
| 12.3.11 Restrained elastomeric seal joint pressure mains..... | 224 |
| 12.3.12 Restraint requirements for special situations..... | 224 |
| 12.3.12.1 Above ground pressure mains with unrestrained flexible joints..... | 224 |
| 12.3.12.2 Steel mains with welded joints, buried..... | 224 |
| 12.3.12.3 Steel mains with welded joints, above ground..... | 224 |
| 12.3.12.4 Ductile iron or steel mains with flanged joints..... | 224 |
| 12.3.12.5 PE mains..... | 224 |
| 13 SUPPORTING SYSTEMS..... | 225 |
| 13.1 SERVICES..... | 225 |
| 13.1.1 General..... | 225 |
| 13.1.2 Water..... | 225 |
| 13.1.3 Telephone/Telemetry lines..... | 225 |
| 13.1.4 General lighting and power..... | 225 |
| 13.1.5 Drainage..... | 225 |
| 13.1.6 Water closet..... | 226 |
| 13.2 MATERIALS HANDLING..... | 226 |
| 13.2.1 Lifting equipment..... | 226 |
| 13.2.2 Handling and storage of hazardous material..... | 226 |
| 13.3 SECURITY..... | 226 |
| 13.4 FIRE CONTROL..... | 226 |
| 14 DESIGN REVIEW..... | 228 |

| | |
|--|-----|
| 15 DESIGN DOCUMENTATION AND DRAWINGS..... | 229 |
| 15.1 DOCUMENTATION..... | 229 |
| 15.2 DESIGN DRAWINGS..... | 229 |
| 15.2.1 General..... | 229 |
| 15.2.2 Real property information..... | 229 |
| 15.2.3 Pumping station and emergency storage..... | 230 |
| 15.2.4 Structures..... | 230 |
| 15.2.5 Pressure mains and sewers - general..... | 230 |
| 15.2.6 Pressure mains and sewers - longitudinal sections (profiles)..... | 231 |
| 15.2.7 Electrical and telemetry..... | 231 |
| 15.2.8 Title block notation and standard notes..... | 232 |
| 15.2.9 Other..... | 232 |
| 15.3 SPECIFICATIONS..... | 232 |
| 15.4 DRAFTING STANDARDS..... | 233 |
| 15.4.1 General..... | 233 |
| 15.4.2 Scale..... | 233 |
| 15.4.3 Recording of as-constructed information..... | 233 |
| APPENDIX A — GENERIC INFRASTRUCTURE PROTECTION GUIDANCE..... | 234 |
| A1 INFRASTRUCTURE PROTECTION TREATMENTS - SELECTION AND DEFINITION..... | 234 |
| A2 RISK MANAGEMENT - INFRASTRUCTURE PROTECTION RISK ASSESSMENTS..... | 234 |
| A3 INFRASTRUCTURE PROTECTION DESIGN CONSIDERATIONS..... | 234 |
| A4 INFRASTRUCTURE PROTECTION TREATMENTS..... | 235 |
| A5 SECURITY DESIGN CONCEPTS..... | 235 |
| A6 ENVIRONMENTAL DESIGN CONSIDERATIONS..... | 235 |
| A7 SEWER FAILURE IMPACT ASSESSMENT..... | 236 |
| A8 WATER AGENCY'S ENVIRONMENTAL AESTHETICS GUIDANCE..... | 237 |
| APPENDIX B — AC VOLTAGE MITIGATION OF STEEL PIPELINES..... | 246 |
| B1 INTRODUCTION..... | 246 |
| B2 INDUCTIVE COUPLING HAZARD..... | 246 |
| B3 CONDUCTIVE COUPLING HAZARD..... | 246 |
| B4 CAPACITIVE COUPLING HAZARD..... | 246 |
| B5 MITIGATION..... | 246 |
| APPENDIX C — TYPICAL PRECOMMISSIONING SCHEDULE..... | 247 |
| APPENDIX D — TYPICAL COMMISSIONING SCHEDULE..... | 254 |
| APPENDIX E — PROTECTION AGAINST DEGRADATION..... | 256 |
| E1 GENERAL..... | 256 |
| E2 PROTECTION AGAINST INTERNAL CORROSION..... | 256 |
| E3 PROTECTION AGAINST EXTERNAL AGGRESSIVE ENVIRONMENT..... | 256 |
| E4 PROTECTION AGAINST EXTERNAL CONTAMINATED GROUND..... | 257 |
| APPENDIX F — GUIDELINES FOR VENTILATION OF RETICULATION SEWERS..... | 258 |
| F1 INTRODUCTION..... | 258 |
| F1.1 Impact of climate change..... | 259 |
| F1.1.1 Context..... | 259 |
| F1.1.2 Methodology..... | 259 |
| F1.1.3 Application..... | 259 |
| F2 VENTING OF RETICULATION SEWERS..... | 259 |
| F2.1 Location and spacing of educt and induct vents..... | 259 |
| F3 EDUCT VENT SHAFTS..... | 260 |
| F3.1 Types..... | 260 |
| F3.2 Design requirements..... | 260 |
| F3.2.1 Material selection..... | 260 |

| | |
|---|-----|
| F3.3 Educt vent cowls..... | 261 |
| F3.4 Installation limitations..... | 261 |
| F3.4.1 Guy-wire vents..... | 261 |
| F3.4.2 Post type vents..... | 261 |
| F3.4.3 Wall vents..... | 261 |
| F4 INDUCT VENT SHAFTS..... | 261 |
| F5 STANDARD DRAWINGS..... | 261 |
| APPENDIX G — PRESSURE MAIN CALCULATIONS..... | 263 |
| G1 NOMENCLATURE..... | 263 |
| G2 PRINCIPLES AND CRITERIA..... | 263 |
| G2.1 Design flows..... | 263 |
| G2.2 Detention time..... | 264 |
| G2.3 Minimum internal diameter of pressure main..... | 264 |
| G2.4 Maximum internal diameter of pressure main..... | 264 |
| G2.5 Minimum pumping rate..... | 264 |
| G2.6 Maximum pumping rate..... | 264 |
| G2.7 Pump control volume (cut-in / cut-out volume) and pump starts..... | 264 |
| APPENDIX H — PIPELINES IN SLIP AND POTENTIALLY UNSTABLE AREAS..... | 266 |
| H1 INTRODUCTION..... | 266 |
| H2 SLIP AND UNSTABLE AREAS..... | 266 |
| H2.1 FACTORS INFLUENCING STABILITY OF SLOPES..... | 267 |
| H2.1.1 Soil and rock condition..... | 267 |
| H2.1.2 Angle of slope..... | 267 |
| H2.1.3 Groundwater and surface water..... | 267 |
| H2.1.4 Domestic development..... | 267 |
| H2.1.5 Vegetation..... | 267 |
| H2.1.6 Road construction..... | 267 |
| H3 IDENTIFICATION OF POTENTIALLY UNSTABLE AREAS..... | 267 |
| H4 PRECAUTIONS..... | 268 |
| H4.1 GRAVITY SEWERS AND RISING MAINS..... | 269 |
| Gravity sewers..... | 269 |
| Rising mains..... | 269 |
| H4.2 ALTERNATIVE SEWERAGE SYSTEMS AND CONSTRUCTION TECHNIQUES..... | 271 |
| H4.3 SHALLOW TRENCH OR ABOVE-GROUND CONSTRUCTION..... | 271 |
| H4.4 DESIGN FOR POSSIBLE GROUND MOVEMENT..... | 272 |
| H4.5 CONSIDER GROUNDWATER AND DRAINAGE..... | 272 |
| H4.6 PRECAUTIONS DURING CONTRUCTION..... | 274 |
| APPENDIX I — TRENCHLESS TECHNOLOGIES..... | 276 |
| I1 GENERAL..... | 276 |
| I2 HORIZONTAL DIRECTIONAL DRILLING (HDD)..... | 276 |
| I3 MICRO-TUNNELLING..... | 276 |
| I4 UNGUIDED BORING/THRUST BORING/AUGER BORING..... | 277 |
| I5 PIPE JACKING..... | 277 |
| I6 MINI-TUNNELLING..... | 277 |
| APPENDIX J — DETAILED DESIGN CHECKLIST..... | 281 |
| PART 2: CONSTRUCTION..... | 290 |
| 16 GENERAL..... | 290 |
| 16.1 SCOPE..... | 290 |
| 16.2 INTERPRETATION..... | 290 |
| 17 GENERAL CONSTRUCTION..... | 293 |
| 17.1 GENERAL..... | 293 |

| | |
|--|-----|
| 17.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING..... | 293 |
| 17.2.1 Pumping stations..... | 293 |
| 17.2.2 Inlet works, emergency storage and ERS..... | 293 |
| 17.2.3 Pressure mains..... | 294 |
| 17.3 CONTRACT INTERFACES..... | 294 |
| 17.4 CUSTOMER FOCUS..... | 294 |
| 17.4.1 General..... | 294 |
| 17.4.2 Resolution of complaints..... | 294 |
| 17.5 PROTECTION OF PEOPLE, PROPERTY AND ENVIRONMENT..... | 294 |
| 17.5.1 Protection of other services..... | 294 |
| 17.5.2 Road reserves or other thoroughfares..... | 295 |
| 17.5.2.1 Road Opening Permits..... | 295 |
| 17.5.2.2 Treatment of pavements and other surfaces..... | 295 |
| 17.5.2.3 Cleanliness of roads, paths, accesses and drainage paths..... | 295 |
| 17.5.2.4 Storage of products, materials and equipment..... | 296 |
| 17.5.2.5 Obstruction of street drainage..... | 296 |
| 17.5.3 Private and public properties..... | 296 |
| 17.5.4 Protection of the environment and heritage areas..... | 296 |
| 17.5.4.1 General..... | 296 |
| 17.5.4.2 Collection and disposal of wastes..... | 296 |
| 17.5.4.3 Protection of adjacent lands and vegetation..... | 297 |
| 17.5.4.4 Control of water pollution..... | 297 |
| 17.5.4.5 Contaminated soils..... | 299 |
| 17.5.4.6 Control of noise and atmospheric pollution..... | 299 |
| 17.5.4.7 Equipment and machinery use in bush fire prone areas..... | 299 |
| 17.5.4.8 Recycled, reused and waste materials..... | 299 |
| 17.6 DISUSED / REDUNDANT SEWERS AND PRESSURE MAINS..... | 300 |
| 17.7 ALTERATION OF EXISTING SERVICES..... | 300 |
| 17.8 SURVEY MARKS..... | 300 |
| 17.9 CONSTRUCTION TOLERANCES..... | 300 |
| 17.10 LATENT CONDITIONS..... | 300 |
| 18 PRODUCTS, MATERIALS AND EQUIPMENT..... | 302 |
| 18.1 AUTHORISED PRODUCTS, MATERIALS AND EQUIPMENT..... | 302 |
| 18.2 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS..... | 302 |
| 18.3 ELECTRICAL EQUIPMENT..... | 302 |
| 18.4 PUMPS..... | 303 |
| 18.5 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS..... | 303 |
| 18.5.1 General..... | 303 |
| 18.5.2 Transportation..... | 303 |
| 18.5.3 Unloading and handling..... | 303 |
| 18.5.4 On-site storage..... | 303 |
| 18.5.5 Plastics-lined concrete products..... | 304 |
| 18.5.6 Coiled plastics pipe..... | 304 |
| 18.6 FASTENERS..... | 305 |
| 18.7 WORKS INSPECTION AND TESTING..... | 305 |
| 18.7.1 Switchboards..... | 305 |
| 18.7.2 Pumps..... | 306 |
| 18.7.3 Motors..... | 306 |
| 18.8 CONCRETE WORKS..... | 306 |
| 18.9 SUPPLY OF WATER TO THE WORKS..... | 307 |
| 19 ELECTRICAL WORKS..... | 308 |

| | |
|--|-----|
| 19.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS..... | 308 |
| 19.2 SCOPE OF WORK..... | 308 |
| 19.3 SUPPLY AUTHORITY REQUIREMENTS AND METERING..... | 308 |
| 19.4 CONSUMER MAINS..... | 309 |
| 19.4.1 Point of supply..... | 309 |
| 19.4.2 Cable size..... | 309 |
| 19.4.3 Maximum demand..... | 309 |
| 19.4.4 Calculations to be submitted..... | 309 |
| 19.4.5 Mains in reserves..... | 309 |
| 19.4.6 Mains requirements..... | 309 |
| 19.4.7 Lead-in pole and overhead mains construction..... | 310 |
| 19.4.7.1 Lead-in pole..... | 310 |
| 19.4.7.2 Poles..... | 310 |
| 19.4.7.3 Installation of poles..... | 310 |
| 19.4.7.4 Aerial cables..... | 311 |
| 19.4.8 Underground cable installation..... | 311 |
| 19.4.8.1 General..... | 311 |
| 19.4.8.2 Location..... | 311 |
| 19.4.8.3 Excavation and bedding..... | 311 |
| 19.4.8.4 Underground cable marking..... | 311 |
| 19.4.8.5 Cable installation on poles..... | 311 |
| 19.4.8.6 Road crossings..... | 312 |
| 19.5 EARTHING..... | 312 |
| 19.5.1 General..... | 312 |
| 19.5.2 Earth circuits..... | 312 |
| 19.5.3 Labelling..... | 313 |
| 19.6 SWITCHBOARD INSTALLATION..... | 313 |
| 19.6.1 General..... | 313 |
| 19.6.2 Equipment mounting..... | 313 |
| 19.6.3 Thermal derating of equipment..... | 314 |
| 19.6.4 Labelling..... | 314 |
| 19.6.4.1 General..... | 314 |
| 19.6.4.2 Incoming mains and pump and motor detail labels..... | 314 |
| 19.6.4.3 Main labels..... | 314 |
| 19.6.4.4 Cubicle labels..... | 314 |
| 19.6.4.5 Danger notices..... | 315 |
| 19.6.4.6 Asset and equipment number labels..... | 315 |
| 19.7 CIRCUITS..... | 315 |
| 19.7.1 Main circuits..... | 315 |
| 19.7.2 Control circuit wiring..... | 315 |
| 19.8 CABLING..... | 316 |
| 19.8.1 General..... | 316 |
| 19.8.2 Conduits..... | 317 |
| 19.8.3 Cable protection..... | 317 |
| 19.8.4 Cable trays..... | 317 |
| 19.8.5 Junction boxes..... | 318 |
| 19.9 INSTALLATION OF PUMP CABLES..... | 318 |
| 19.9.1 Numbering of pumps..... | 318 |
| 19.9.2 Installation..... | 318 |
| 19.10 INSTALLATION OF LEVEL SENSORS..... | 318 |
| 19.10.1 General..... | 318 |

| | |
|--|-----|
| 19.10.2 Wet-well level sensor probes..... | 318 |
| 19.11 TERMINATIONS..... | 319 |
| 19.11.1 General..... | 319 |
| 19.11.2 Glands..... | 319 |
| 19.11.3 Mains and pump terminations..... | 319 |
| 19.12 PAINTING..... | 320 |
| 19.12.1 General..... | 320 |
| 19.12.2 Paint materials..... | 320 |
| 19.12.3 Surface preparation..... | 320 |
| 19.12.4 Painting and finish..... | 320 |
| 19.13 INSTALLATION IN VALVE PITS..... | 320 |
| 19.13.1 General..... | 320 |
| 19.13.2 Cables..... | 320 |
| 19.14 NOTIFICATION OF ELECTRICAL WORK..... | 321 |
| 20 TELEMETRY SYSTEM..... | 322 |
| 20.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS..... | 322 |
| 20.2 SCOPE OF WORK..... | 322 |
| 20.3 HARDWARE INSTALLATION..... | 322 |
| 20.4 PLC PROGRAMMING..... | 322 |
| 20.5 SCADA DATABASE CONFIGURATION..... | 322 |
| 21 ODOUR CONTROL SYSTEM..... | 324 |
| 22 MECHANICAL INSTALLATION OF PUMPS, VALVES AND FITTINGS..... | 325 |
| 22.1 GENERAL..... | 325 |
| 22.2 FLANGED JOINTS..... | 325 |
| 22.3 INSTALLATION OF PUMPING UNITS..... | 325 |
| 22.3.1 General..... | 325 |
| 22.3.2 Machinery alignment..... | 325 |
| 22.3.3 Unit members..... | 325 |
| 22.3.4 Test tapping points..... | 326 |
| 22.4 GAUGES AND RECORDERS..... | 326 |
| 22.4.1 Pressure gauges..... | 326 |
| 22.4.2 Pressure recorder..... | 326 |
| 23 METALWORK..... | 327 |
| 23.1 STEELWORK..... | 327 |
| 23.2 ALUMINIUM ALLOY COMPONENTS..... | 327 |
| 23.3 STAINLESS STEEL COMPONENTS..... | 327 |
| 23.4 FASTENERS..... | 327 |
| 24 ACCESS ROAD AND HARDSTAND AREAS..... | 329 |
| 24.1 GENERAL..... | 329 |
| 24.2 SUBGRADE..... | 329 |
| 24.3 BASECOURSE..... | 329 |
| 24.4 SPRAYED BITUMINOUS SEALING..... | 329 |
| 24.5 ASPHALTIC CONCRETE..... | 330 |
| 24.6 TIMBER GUARDRAIL..... | 330 |
| 24.7 REINFORCED CONCRETE..... | 330 |
| 25 RETAINING WALLS..... | 331 |
| 25.1 RETAINING WALLS - TIMBER CANTILEVER..... | 331 |
| 25.1.1 General..... | 331 |
| 25.1.2 Handrails..... | 331 |
| 25.2 RETAINING WALLS - CONCRETE - CRIB WALL..... | 331 |
| 25.2.1 General..... | 331 |

| | |
|---|-----|
| 25.2.2 Foundations..... | 332 |
| 25.2.3 Cribfill and backfill..... | 332 |
| 25.2.4 Drainage..... | 332 |
| 25.2.5 Handrails..... | 333 |
| 25.3 RETAINING WALLS – CONCRETE – BLOCK-WORK..... | 333 |
| 25.4 RETAINING WALLS – CONCRETE – CAST IN-SITU..... | 333 |
| 26 EXCAVATION..... | 334 |
| 26.1 SAFETY..... | 334 |
| 26.2 LIMITS OF CLEARING AND EXCAVATION..... | 334 |
| 26.3 EXCAVATION ACROSS IMPROVED SURFACES..... | 334 |
| 26.4 PROTECTION OF TREES..... | 334 |
| 26.4.1 General precautions..... | 334 |
| 26.4.2 Protection of roots..... | 334 |
| 26.5 BLASTING..... | 335 |
| 26.6 SUPPORT OF EXCAVATIONS..... | 335 |
| 26.7 DRAINAGE AND DEWATERING..... | 335 |
| 26.8 TRENCH EXCAVATION..... | 336 |
| 26.8.1 General..... | 336 |
| 26.8.2 Construction of embankment..... | 336 |
| 26.8.3 Clearances for on-site works..... | 336 |
| 26.9 REFILL OF EXCESSIVE EXCAVATION..... | 336 |
| 26.10 FOUNDATIONS AND FOUNDATION STABILISATION..... | 337 |
| 26.11 SURPLUS EXCAVATED MATERIAL..... | 337 |
| 26.12 EXCAVATION AND PIPELAYING USING TRENCHLESS TECHNIQUES..... | 337 |
| 27 BEDDING FOR PIPES, BENDS, WET-WELLS AND MAINTENANCE STRUCTURES..... | 339 |
| 27.1 TRENCH FLOOR PREPARATION..... | 339 |
| 27.2 BEDDING MATERIALS..... | 339 |
| 27.3 PLACEMENT OF BEDDING..... | 339 |
| 27.4 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS..... | 339 |
| 27.5 BEDDING FOR PIPES, VALVES AND FITTINGS..... | 340 |
| 27.6 BEDDING FOR CONCRETE STRUCTURES..... | 340 |
| 27.7 BEDDING FOR MAINTENANCE CHAMBERS, MAINTENANCE SHAFTS, INSPECTION SHAFTS AND VARIABLE BENDS..... | 340 |
| 28 PIPE LAYING AND JOINTING..... | 341 |
| 28.1 INSTALLATION OF PIPES..... | 341 |
| 28.1.1 General..... | 341 |
| 28.1.2 Cleaning, inspection and joint preparation..... | 341 |
| 28.1.3 Polyethylene..... | 341 |
| 28.1.4 Laying..... | 341 |
| 28.2 HORIZONTAL AND VERTICAL DEFLECTION OF GRAVITY SEWERS AND PRESSURE MAINS..... | 342 |
| 28.2.1 General..... | 342 |
| 28.2.2 Methods of deflection for Gravity Sewers..... | 342 |
| 28.2.3 Horizontal curves for Gravity Sewers..... | 342 |
| 28.2.4 Vertical curves for Gravity Sewers..... | 343 |
| 28.2.5 Compound curves for Gravity Sewers..... | 343 |
| 28.2.6 Methods of deflection at the pipe joint for Pressure mains..... | 344 |
| 28.2.7 Horizontal curves and deviations for Pressure Mains..... | 344 |
| 28.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES..... | 344 |
| 28.4 FLOTATION CONTROL..... | 344 |
| 28.5 THRUST AND ANCHOR BLOCKS AND RESTRAINED JOINTS FOR PRESSURE MAINS..... | 344 |

| | |
|---|-----|
| 28.6 MARKING TAPES / TRACER WIRES..... | 345 |
| 28.6.1 Non-detectable marking tape..... | 345 |
| 28.6.2 Detectable marking tape..... | 345 |
| 28.6.3 Tracer wire..... | 346 |
| 28.7 VALVES AND SURFACE FITTINGS..... | 346 |
| 28.7.1 Installation..... | 346 |
| 28.7.2 Scours for pressure mains..... | 346 |
| 28.8 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE..... | 346 |
| 28.9 BRIDGE CROSSINGS..... | 347 |
| 28.10 TRENCH STOPS FOR PRESSURE MAINS..... | 347 |
| 28.11 BULKHEADS FOR PRESSURE MAINS..... | 347 |
| 28.12 CORROSION PROTECTION OF CAST IRON FOR PRESSURE MAINS..... | 347 |
| 28.13 AQUEDUCTS..... | 347 |
| 28.14 LOCATION MARKERS..... | 348 |
| 28.15 FLANGED JOINTS..... | 348 |
| 28.16 WELDING OF STEEL PRESSURE MAINS..... | 348 |
| 28.16.1 General..... | 348 |
| 28.16.2 Field welding of flanges..... | 348 |
| 28.16.3 Reinstatement of cement mortar lining..... | 349 |
| 28.16.4 Reinstatement of external corrosion protection at joints using a tape system..... | 349 |
| 28.16.4.1 General..... | 349 |
| 28.16.4.2 Surface preparation..... | 349 |
| 28.16.4.3 Priming surfaces..... | 349 |
| 28.16.4.4 Mastic filler..... | 350 |
| 28.16.4.5 Tape application..... | 350 |
| 28.16.5 Reinstatement of external corrosion protection at joints using a heat-shrinkable sleeve system..... | 351 |
| 28.16.5.1 Surface preparation..... | 351 |
| 28.16.5.2 Priming surfaces..... | 352 |
| 28.16.5.3 Priming surfaces..... | 352 |
| 28.16.5.4 Mastic filler..... | 352 |
| 28.16.5.5 Heat-shrinkable sleeve preparation..... | 352 |
| 28.16.5.6 Heat-shrinkable sleeve application..... | 352 |
| 28.17 WELDING OF PE PIPELINES..... | 352 |
| 28.17.1 General..... | 352 |
| 28.17.2 Welder qualifications..... | 353 |
| 28.17.3 Connections to pipes of other materials..... | 353 |
| 29 WET-WELLS AND MAINTENANCE HOLES (MHS)..... | 354 |
| 29.1 GENERAL..... | 354 |
| 29.2 WET-WELL AND MH BASES..... | 354 |
| 29.3 TRENCH DRAINAGE AROUND WET-WELLS AND MHs..... | 354 |
| 29.4 PRECAST CONCRETE SYSTEMS..... | 354 |
| 29.5 CAST IN-SITU CONCRETE WET-WELLS AND MHs..... | 355 |
| 29.6 BENCHING AND CHANNELS..... | 355 |
| 29.7 INTERNAL COATING OF CONCRETE WET-WELLS AND MHs..... | 355 |
| 29.8 GLASS REINFORCED PLASTICS (GRP) MHs..... | 355 |
| 29.9 POLYETHYLENE (PE) MHs..... | 355 |
| 29.10 POLYPROPYLENE (PP) MHs..... | 355 |
| 29.11 COVERS..... | 355 |
| 29.12 CONNECTIONS TO WET-WELLS AND MHs..... | 355 |
| 29.13 MH DROPS..... | 356 |

| | |
|--|-----|
| 29.14 MAINTENANCE CHAMBERS (MC), MAINTENANCE SHAFTS (MS AND TMS) AND INSPECTION OPENINGS (IO) OR INSPECTION SHAFTS (IS)..... | 356 |
| 29.14.1 General..... | 356 |
| 29.14.2 Sealing caps..... | 356 |
| 29.14.3 Covers..... | 356 |
| 29.14.4 Connections to MCs, MSs and TMSs..... | 356 |
| 30 PIPE EMBEDMENT AND SUPPORT..... | 357 |
| 30.1 GENERAL..... | 357 |
| 30.2 EMBEDMENT MATERIALS..... | 357 |
| 30.2.1 General..... | 357 |
| 30.2.2 Recycled, reused and waste materials..... | 357 |
| 30.3 COMPACTION OF EMBEDMENT..... | 357 |
| 30.3.1 General..... | 357 |
| 30.3.2 Methods..... | 358 |
| 30.3.3 Compaction trials/Pre-qualification of embedment compaction method..... | 358 |
| 30.3.3.1 Pressure mains..... | 358 |
| 30.3.3.2 Gravity Sewers..... | 358 |
| 30.3.3.3 Test Method..... | 358 |
| 30.3.3.4 Interpretation and applicability..... | 359 |
| 30.3.4 Compaction control..... | 359 |
| 30.4 SPECIAL BEDDING AND EMBEDMENTS/GEOTEXTILE SURROUND AND PILLOW..... | 359 |
| 30.5 REMOVAL OF TRENCH SUPPORTS..... | 359 |
| 30.6 CONCRETE EMBEDMENT AND ENCASEMENT..... | 359 |
| 31 FILL..... | 360 |
| 31.1 TRENCH FILL..... | 360 |
| 31.1.1 Material requirements..... | 360 |
| 31.1.1.1 Trafficable areas..... | 360 |
| 31.1.1.2 Non-trafficable areas..... | 360 |
| 31.1.2 Placement..... | 361 |
| 31.1.3 Compaction of trench fill..... | 361 |
| 31.2 EMBANKMENT FILL..... | 361 |
| 31.3 DRIVES AND TUNNEL FILL..... | 362 |
| 32 CONNECTION TO EXISTING GRAVITY SEWERS..... | 363 |
| 33 RESTORATION..... | 364 |
| 33.1 GENERAL..... | 364 |
| 33.2 PAVEMENTS..... | 364 |
| 33.3 LAWNS..... | 364 |
| 33.4 GRASSED AREAS..... | 365 |
| 33.5 BUSHLAND..... | 365 |
| 33.6 PROVISION FOR SETTLEMENT..... | 365 |
| 33.7 MAINTENANCE OF RESTORED SURFACES..... | 365 |
| 34 ACCEPTANCE TESTING..... | 366 |
| 34.1 PIPELINES..... | 366 |
| 34.2 VISUAL EXTERNAL INSPECTION..... | 366 |
| 34.3 COMPACTION TESTING..... | 367 |
| 34.3.1 General..... | 367 |
| 34.3.2 Compaction testing requirements..... | 368 |
| 34.3.2.1 General..... | 368 |
| 34.3.3 Embedment compaction testing..... | 369 |
| 34.3.3.1 Applicable pipe sizes..... | 369 |
| 34.3.3.2 Frequency and location of embedment tests..... | 369 |

| | |
|--|-----|
| 34.3.3.3 Retesting..... | 369 |
| 34.3.4 Trench fill compaction testing..... | 369 |
| 34.3.4.1 Trafficable test zone..... | 369 |
| 34.3.4.2 Non-trafficable test zone..... | 369 |
| 34.3.4.3 Test method..... | 369 |
| 34.3.4.4 Frequency and location of tests..... | 369 |
| 34.3.4.5 Retesting..... | 370 |
| 34.3.5 Other fill compaction testing..... | 370 |
| 34.3.5.1 General..... | 370 |
| 34.3.5.2 Trafficable test zone..... | 370 |
| 34.3.5.3 Non-trafficable test zone..... | 370 |
| 34.3.5.4 Frequency and location of tests..... | 370 |
| 34.3.5.5 Retesting..... | 370 |
| 34.4 AIR PRESSURE AND VACUUM TESTING OF GRAVITY SEWERS..... | 371 |
| 34.4.1 General..... | 371 |
| 34.4.2 Air testing methods for sewers..... | 371 |
| 34.4.2.1 Vacuum testing..... | 371 |
| 34.4.2.2 Low pressure air testing..... | 372 |
| 34.4.3 Testing of sewers >DN 1500..... | 373 |
| 34.4.3.1 General..... | 373 |
| 34.4.3.2 Method of test..... | 373 |
| 34.4.3.3 Testing of non-pressure PE sewers..... | 373 |
| 34.4.4 Watertightness of wet-well..... | 373 |
| 34.4.5 Testing of concrete emergency storage and maintenance holes..... | 374 |
| 34.4.5.1 General..... | 374 |
| 34.4.5.2 Test method..... | 374 |
| 34.5 HYDROSTATIC PRESSURE TESTING OF PRESSURE MAINS..... | 375 |
| 34.6 INFILTRATION TESTING..... | 376 |
| 34.7 DEFLECTION (OVALITY) TESTING OF FLEXIBLE GRAVITY SEWERS..... | 376 |
| 34.7.1 General..... | 376 |
| 34.7.2 Ovality proving tools..... | 376 |
| 34.7.3 Flexible sewers ≤DN 300..... | 377 |
| 34.7.4 Flexible sewers >DN 300..... | 377 |
| 34.7.4.1 General..... | 377 |
| 34.7.4.2 Flexible sewers >DN 300 and <DN 750..... | 378 |
| 34.7.4.3 Flexible sewers ≥DN 750..... | 378 |
| 34.8 MEASUREMENT OF SEWER GRADE..... | 378 |
| 34.9 INTERNAL INSPECTION..... | 378 |
| 34.10 INSPECTION AND TESTING OF THERMOPLASTICS LINED CONCRETE SEWERS AND MHs..... | 379 |
| 34.10.1 Visual inspection..... | 379 |
| 34.10.2 Spark testing..... | 379 |
| 34.10.3 Locking key pull-out tests..... | 379 |
| 34.11 PRESSURE TESTING OF INVERTED SYPHONS..... | 380 |
| 34.11.1 General..... | 380 |
| 34.11.2 Hydrostatic system test pressure..... | 380 |
| 34.11.3 Satisfactory pressure test..... | 380 |
| 34.11.4 WELD TESTING OF PE PIPES..... | 380 |
| 34.12 ELECTRICAL WORKS..... | 381 |
| 35 COMMISSIONING..... | 382 |
| 35.1 GENERAL..... | 382 |

| | |
|--|-----|
| 35.2 PUMPING STATION..... | 382 |
| 35.2.1 Requirements..... | 382 |
| 35.2.2 Pre-commissioning..... | 382 |
| 35.2.2.1 Commissioning..... | 382 |
| 35.2.3 Handover..... | 382 |
| 35.3 ODOUR CONTROL SYSTEM..... | 383 |
| 35.4 COMMISSIONING REPORT..... | 383 |
| 36 TOLERANCES ON AS-CONSTRUCTED WORK..... | 384 |
| 36.1 HORIZONTAL TOLERANCES..... | 384 |
| 36.1.1 Sewers, mains, valves, in-line structures, pumping stations, roads..... | 384 |
| 36.2 VERTICAL TOLERANCES..... | 384 |
| 36.2.1 Sewers, pressure mains, structures, pumping stations, roads..... | 384 |
| 36.2.2 Grade..... | 384 |
| 36.3 VERTICALITY (“PLUMB”)..... | 385 |
| 36.4 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS..... | 385 |
| 36.5 CAST IN-SITU CONCRETE STRUCTURES AND SLABS..... | 385 |
| 37 WORK AS-CONSTRUCTED DETAILS..... | 386 |
| 37.1 GENERAL..... | 386 |
| 37.2 ELECTRICAL WORKS..... | 386 |
| 37.2.1 Electrical Contractors Installation Drawings..... | 386 |
| 37.2.2 Principal Supplied Installation Drawings and Equipment Schedules..... | 386 |
| APPENDIX K — OVALITY TESTING OF GRAVITY SEWERS..... | 387 |
| K1 GENERAL..... | 387 |
| K2 REQUIREMENTS..... | 387 |
| APPENDIX L — SPECIFICATION FOR INTERNAL INSPECTION..... | 389 |
| L1 INTRODUCTION..... | 389 |
| L2 INSPECTION REQUIREMENTS..... | 389 |
| L3 QUALIFICATIONS OF INSPECTORS..... | 389 |
| L4 WORK AS CONSTRUCTED..... | 390 |
| L5 REPORTING SUMMARIES..... | 390 |
| L6 MATERIALS..... | 390 |
| APPENDIX M — MAXIMUM DEPTH TO INVERT FOR STANDARD SUPPORT TYPES..... | 398 |
| M1 GENERAL..... | 398 |
| M2 STRUCTURAL DESIGN..... | 398 |
| M2.1 Flexible buried pipelines..... | 398 |
| M2.2 Precast concrete pipes pipelines..... | 398 |
| M2.3 Trench width dimensions..... | 398 |
| M3 EMBEDMENT MATERIAL..... | 399 |
| M4 TRENCH FILL..... | 399 |
| M5 COMPACTION..... | 399 |
| M6 MAXIMUM DEPTH TO INVERT FOR SUPPORT TYPES..... | 400 |
| PART 3: STANDARD DRAWINGS..... | 406 |
| 38 INTRODUCTION..... | 406 |
| 38.1 GENERAL..... | 406 |
| 38.2 DRAWING COMMENTARY..... | 406 |
| 38.3 COMMENTARY ON SPS-1100 SERIES – PLANNING AND CONCEPT DESIGN..... | 406 |
| 38.3.1 General..... | 406 |
| 38.3.2 SPS-1100 Concept Plan - Typical Catchment Plan..... | 407 |
| 38.3.3 SPS-1101 and SPS-1102 Pumping Station Concept Design - Site Layout..... | 407 |
| 38.3.4 SPS-1103 Pumping Station Concept Design - Power and Control Cubicle, Base and Conduit Details..... | 407 |

| | |
|--|-----|
| 38.3.5 SPS-1104-1 and SPS 1104-2 shows a Static Head Calculation..... | 408 |
| 38.3.5.1 SPS–1104–1..... | 408 |
| 38.3.5.2 SPS–1104–2..... | 408 |
| 38.3.5.3 SPS-1105 Typical Hydraulic Profile..... | 409 |
| 38.4 COMMENTARY ON SPS–1200 SERIES – PUMPING STATION LAYOUT..... | 409 |
| 38.4.1 SPS–1200, SPS–1201, SPS–1202, SPS–1203 and SPS–1204 Typical Site Plan Fronting and Not Fronting Adjacent Roadway..... | 409 |
| 38.4.2 SPS–1205 Access Roadway Cross Section and Drainage Details..... | 410 |
| 38.4.3 SPS–1206 Typical Site Plan Conceptual Site Layout and SPS–1207 Typical Site Access Arrangements..... | 410 |
| 38.5 COMMENTARY ON SPS–1300 SERIES – PUMP STATION ARRANGEMENT..... | 410 |
| 38.5.1 SPS–1300 General Arrangement - Inlet MH, Wet-Well and Valve Chamber..... | 410 |
| 38.5.2 SPS–1301 Detailed Arrangement - Wet-Well, Buried Valves, DN100 Pipework..... | 410 |
| 38.5.3 SPS–1302 Civil Plan - Wet-Well and Valve Chamber..... | 410 |
| 38.5.4 SPS–1303 Wet Well Construction - Precast Concrete Components..... | 410 |
| 38.5.5 SPS–1304 Wet Well Construction - Cover and Access Hole Details..... | 411 |
| 38.5.6 SPS–1305 Electrical and Telemetry Conduit Details..... | 411 |
| 38.5.7 SPS–1306 Valve Chamber Adjacent to Wet-well - Plan Section and Cover - Non- Trafficable..... | 411 |
| 38.5.8 SPS–1307 Valve Chamber Adjacent to Wet-Well Pipework..... | 411 |
| 38.5.9 SPS–1308 Water Supply DN50 Reduced Pressure Zone Device arrangement & details..... | 411 |
| 38.5.10 SPS–1309 Mobile Pump Connection Arrangement - Pumping Stations < 40 L/s and SPS– 1310 Mobile Pump Connection Arrangement - Pumping Stations > 40 L/s..... | 411 |
| 38.5.11 SPS–1350 and SPS–1351 Wet Well, Valve Chamber & Inlet Maintenance Hole general arrangement and section..... | 411 |
| 38.5.12 SPS–1352 and SPS–1353 Valve Chamber and Cover - general and typical arrangement..... | 411 |
| 38.5.13 SPS–1354, SPS–1355, and SPS–1356 Valve Chamber Covers - Support Beam Details, Cover & Hinge Details, and Additional Details..... | 411 |
| 38.5.14 SPS–1357 Inlet Maintenance Hole - Hinged Access Cover (Non Trafficable Areas) Typical Arrangement..... | 411 |
| 38.6 COMMENTARY ON SPS–1400 SERIES – STRUCTURES..... | 412 |
| 38.6.1 SPS–1400 and SPS–1401 Grit Collection MH - Detailed Arrangement..... | 412 |
| 38.6.2 SPS–1402 Emergency Storage - Typical Arrangement and Levels - Configuration 1..... | 412 |
| 38.6.3 SPS–1403 Emergency Storage Details - Shallow and Deep Installations and Brickwork..... | 412 |
| 38.6.4 SPS–1404 Emergency Relief System - Arrangement and Cross Section for DN150 to DN375 Overflow Pipes..... | 412 |
| 38.6.5 SPS–1405 Discharge Maintenance Hole Arrangement & Cross Section Pressure Mains < DN375..... | 412 |
| 38.6.6 SPS–1406 and SPS–1408 Emergency Storage Structure (ESS) in Trafficable and Non- Trafficable Areas - General Arrangement..... | 412 |
| 38.6.7 SPS–1407 and SPS–1409 Emergency Storage Structure (ESS) in Trafficable and Non- Trafficable Areas - Details..... | 412 |
| 38.6.8 SPS–1410 and SPS–1411 Inlet Maintenance Hole (IMH) (Up to 6m Depth to Invert Plans/ Section)..... | 412 |
| 38.6.9 SPS–1412 and SPS–1413 Emergency Relief System for Wet Well Inlet Sewers..... | 412 |
| 38.6.10 SPS–1414 Inlet Maintenance Hole with Grit Collection - General Arrangement..... | 413 |
| 38.6.11 SPS–1415 and SPS–1416 Emergency By-Pass Connection Security Enclosure Arrangement including Details..... | 413 |

| | |
|--|-----|
| 38.6.12 SPS–1417 Emergency By-Pass Connection with Bunded Area Arrangements & Details..... | 413 |
| 38.7 COMMENTARY ON SPS–1500 SERIES - WET-WELL APPURTENANCES..... | 413 |
| 38.7.1 SPS–1500, SPS–1501, SPS–1503, SPS–1504 Pump to Pressure Main Connection..... | 413 |
| 38.7.2 SPS–1505 Hydrostatic Level Sensor - Stilling Tube..... | 413 |
| 38.7.3 SPS–1506 and SPS–1507 External Hinged Covers - Opening Grate Type..... | 413 |
| 38.7.4 SPS–1508 Miscellaneous Labels - Survey Label Plate, Pump Label Plate, Valve Spindle Access & Signage..... | 413 |
| 38.7.5 SPS–1550 and SPS–1551 Wet Well Access Hatches Typical Arrangement - Plan & Section..... | 413 |
| 38.8 COMMENTARY ON SPS–1600 SERIES – PRESSURE MAINS..... | 413 |
| 38.8.1 SPS–1600 Design Typical Pressure Main Characteristic Curve..... | 413 |
| 38.8.2 SPS–1601 Pipe Installation, Support & Trench Fill Pressure Mains < DN300..... | 414 |
| 38.8.3 SPS–1602 Scour Arrangement - Pump & Gravity..... | 414 |
| 38.8.4 SPS–1603 and SPS–1604 Scour Arrangement - Pressure Mains..... | 414 |
| 38.8.5 SPS–1605 and SPS–1606 Gas Release Arrangement - Pressure Mains | 414 |
| 38.8.6 SPS–1607 Pressure Main - Manual Air Release Arrangement..... | 414 |
| 38.8.7 SPS–1608 Pipe Absolute Roughness v. Mean Velocity Chart..... | 414 |
| 38.9 COMMENTARY ON SEW–1200 SERIES – EMBEDMENT / TRENCHFILL & SUPPORT SYSTEMS..... | 414 |
| 38.9.1 General..... | 414 |
| 38.9.2 Maximum Depth to Invert for Standard Support Types..... | 416 |
| 38.9.3 SEW–1200 SOIL CLASSIFICATION GUIDELINES..... | 416 |
| 38.9.4 SEW–1201– Embedment and trenchfill- typical arrangements..... | 416 |
| 38.9.5 SEW–1202 Standard Embedment flexible and rigid pipes..... | 416 |
| 38.9.6 SEW–1203 – SPECIAL EMBEDMENT INADEQUATE FOUNDATIONS..... | 417 |
| 38.9.7 SEW–1204 – SPECIAL EMBEDMENT SUPPORT USING PILES..... | 417 |
| 38.9.8 SEW–1205 – SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS..... | 417 |
| 38.9.9 SEW–1206 – BULKHEADS AND TRENCHSTOP..... | 417 |
| 38.9.10 SEW–1207 – TRENCH DRAINAGE TYPICAL SYSTEMS..... | 417 |
| 38.9.11 SEW–1208 – VERTICALS AND NEAR VERTICALS EXPOSED AND CONCEALED METHODS..... | 418 |
| 38.10 COMMENTARY ON SEW–1300 SERIES – ACCESS STRUCTURES..... | 418 |
| 38.10.1 SEW–1300 – SEWERS ≤DN 300 PRECAST MH TYPES P1 AND P2..... | 418 |
| 38.10.2 SEW–1301 – CAST IN-SITU MH TYPES C1 AND C2..... | 418 |
| 38.10.3 SEW–1302 – MH PIPE CONNECTION DETAILS..... | 418 |
| 38.10.4 SEW–1303 – SEWERS ≤ DN 300 MH CHANGE IN LEVEL ARRANGEMENTS..... | 419 |
| 38.10.5 SEW–1304 AND SEW–1305 – MH CHANNEL ARRANGEMENTS AND DETAILS..... | 419 |
| 38.10.6 SEW–1306 – ALTERNATIVE MH DROP CONNECTIONS..... | 419 |
| 38.10.7 SEW–1307 – STEP IRONS AND LADDERS..... | 419 |
| 38.10.8 SEW–1308 – TYPICAL MH COVER ARRANGEMENTS..... | 419 |
| 38.10.9 SEW–1309 AND SEW–1310 – LARGE AND SPECIAL MHs..... | 420 |
| 38.10.10 SEW–1309 – Sewers DN 375 to DN 750 MHs..... | 420 |
| 38.10.11 SEW–1310 – Special MHs using permanent formwork..... | 420 |
| 38.10.12 SEW–1311 AND SEW–1312 – DEEP MHs..... | 420 |
| 38.10.13 SEW–1313 – MH CONNECTION DETAILS PE AND PP PIPE..... | 421 |
| 38.10.14 SEW–1314, SEW–1315, SEW–1316 AND SEW–1317 – MAINTENANCE CHAMBERS..... | 421 |
| 38.11 COMMENTARY ON SEW–1400 SERIES – SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS..... | 421 |

| | |
|--|-----|
| 38.11.1 GENERAL..... | 421 |
| 38.11.2 SEW-1400 – SYPHON ARRANGEMENT | 421 |
| 38.11.3 SEW-1401, SEW-1402 AND SEW-1403 – BURIED CROSSINGS..... | 422 |
| 38.11.4 SEW-1404, SEW-1405, SEW-1406 AND SEW-1455 – AERIAL CROSSINGS | 422 |
| 38.11.5 SEW-1407, SEW-1408, SEW-1410, SEW-1451 AND SEW- 1456 – VENTILATION SYSTEMS..... | 422 |
| SEW-1409, SEW-1411, SEW-1413 and SEW- 1414 – WATER SEAL ARRANGEMENTS..... | 423 |
| 38.11.6 SEW-1412 – EMERGENCY RELIEF STRUCTURES..... | 423 |
| 38.12 COMMENTARY ON WAT-1200 SERIES – EMBEDMENT / TRENCHFILL AND SUPPORT SYSTEMS..... | 423 |
| 38.12.1 GENERAL..... | 423 |
| 38.12.2 WAT-1200 – SOIL CLASSIFICATION GUIDELINES..... | 425 |
| 38.12.3 WAT-1201 – EMBEDMENT AND TRENCH FILL..... | 425 |
| 38.12.4 WAT-1202 – STANDARD EMBEDMENT – ALL PIPE TYPES..... | 425 |
| 38.12.5 WAT-1203 – SPECIAL EMBEDMENTS – INADEQUATE AND POOR FOUNDATION..... | 426 |
| 38.12.6 WAT-1204 – SPECIAL EMBEDMENTS – CONCRETE, GEOTEXTILE AND CEMENT STABILISED SYSTEMS..... | 426 |
| 38.12.7 WAT-1205 – THRUST BLOCK DETAILS – CONCRETE BLOCKS..... | 426 |
| 38.12.8 WAT-1207 – THRUST AND ANCHOR BLOCKS – GATE VALVES AND VERTICAL BENDS..... | 426 |
| 38.12.9 WAT-1208 – RESTRAINED JOINT SYSTEM – DN 100 TO DN 375 DI MAINS..... | 426 |
| 38.12.10 WAT-1209 – TRENCH DRAINAGE – BULKHEADS AND TRENCHSTOP..... | 427 |
| 38.12.11 28.12 WAT-1210 – TRENCH DRAINAGE – TYPICAL SYSTEMS..... | 427 |
| 38.12.12 WAT-1211, WAT-1212, WAT-1213 AND WAT-1214 – BURIED CROSSINGS..... | 427 |
| 38.12.13 WAT-1250 AND WAT-1251 – STANDARD TRENCH DETAILS..... | 427 |
| 38.12.14 WAT-1252 – THRUST BLOCK DETAILS..... | 427 |
| 38.12.15 WAT-1253 AND WAT-1254 – ANCHORAGE DETAILS – STOP VALVE INSTALLATIONS..... | 427 |
| 38.12.16 WAT-1255 – BURIED CROSSINGS..... | 428 |
| 38.13 COMMENTARY ON WAT-1300 SERIES – INSTALLATION PRACTICES/ STRUCTURES..... | 428 |
| 38.13.1 GENERAL..... | 428 |
| 38.13.2 WAT-1300 – VALVE AND HYDRANT IDENTIFICATION..... | 428 |
| 38.13.3 WAT-1301 AND WAT-1302 – TYPICAL VALVE..... | 428 |
| 38.13.4 WAT-1303 AND WAT-1304 – TYPICAL SURFACE FITTING INSTALLATION..... | 428 |
| 38.13.5 WAT-1307 – TYPICAL APPURTENANCE (SCOUR) INSTALLATION..... | 429 |
| 38.13.6 WAT-1313 – FLANGED JOINTS..... | 429 |
| 38.13.7 WAT-1320, WAT-1321 AND WAT-1322 – AERIAL CROSSINGS..... | 429 |
| 38.14 COMMENTARY ON WAT-1400 SERIES – FABRICATION DETAILS..... | 430 |
| 38.14.1 GENERAL..... | 430 |
| 38.14.2 WAT-1400 – TYPICAL STEEL PIPE JOINTING – BUTT WELDING OF JOINTS..... | 430 |
| 38.14.3 WAT-1401 – TYPICAL STEEL PIPE JOINTING – RRJ SPIGOT BANDS..... | 430 |
| 38.14.4 WAT-1402 – TYPICAL STEEL PIPE JOINTING – WELDED PIPE COLLARS..... | 430 |
| 38.14.5 WAT-1403 – TYPICAL STEEL FABRICATION – BENDS..... | 430 |
| 38.14.6 WAT-1408 – JOINT CORROSION PROTECTION..... | 431 |
| 39 LISTING OF STANDARD DRAWINGS..... | 432 |
| 40 SEWAGE PUMPING STATION DRAWINGS..... | 440 |
| PLANNING AND CONCEPT DESIGN..... | 440 |
| Concept plan..... | 440 |
| Pumping Station Concept Design..... | 441 |
| Pressure Main Concept Design..... | 444 |
| Typical Hydraulic Profile..... | 446 |

| | |
|---|-----|
| PUMPING STATION LAYOUT..... | 447 |
| Typical Site Plan..... | 447 |
| Typical Site Plan..... | 448 |
| Typical Site Plan..... | 450 |
| Typical Site Plan..... | 451 |
| Access Roadway..... | 452 |
| Typical Site Plan..... | 453 |
| PUMPING STATION ARRANGEMENT..... | 455 |
| General Arrangement..... | 455 |
| Detailed Arrangement..... | 456 |
| Civil Plan..... | 457 |
| Wet-Well Construction..... | 458 |
| Electrical and Telemetry..... | 460 |
| Valve Chamber Adjacent to Wet-Well..... | 461 |
| Water Supply..... | 463 |
| Mobile Pump Connection Arrangement..... | 464 |
| Wet-Well, Valve Chamber and Inlet Maintenance Hole..... | 466 |
| Valve Chamber..... | 468 |
| Valve Chamber Covers..... | 469 |
| Inlet Maintenance Hole Hinged Access Cover..... | 473 |
| STRUCTURES..... | 474 |
| Grit Collection MH..... | 474 |
| Emergency Storage..... | 476 |
| Emergency Storage Details..... | 477 |
| Emergency Relief System..... | 478 |
| Discharge MH..... | 479 |
| Emergency Storage Structure..... | 480 |
| Inlet MH..... | 484 |
| Emergency Relief System..... | 486 |
| Inlet MH (Grit Collection)..... | 488 |
| Emergency Bypass Connection Security Enclosure..... | 489 |
| Emergency Bypass Connection With Bunded Area..... | 491 |
| Maintenance Holes..... | 492 |
| Maintenance Shafts..... | 506 |
| WET-WELL APPURTENANCES..... | 510 |
| Pump to Pressure Main Connection..... | 510 |
| Hydraulic Level Sensor..... | 515 |
| External Hinged Covers..... | 516 |
| Miscellaneous Details..... | 518 |
| Wet-Well Access Hatches..... | 519 |
| PRESSURE MAINS..... | 521 |
| Design..... | 521 |
| Pipe Installation, Support and Trench Fill..... | 522 |
| Scour Arrangement..... | 523 |
| Gas Release Arrangement..... | 526 |
| Hydraulic Design..... | 529 |
| EMBEDMENT / TRENCHFILL AND SUPPORT SYSTEMS..... | 530 |
| Soil Classification Guidelines And..... | 530 |
| Embedment and Trenchfill..... | 531 |
| Standard Embedment..... | 532 |
| Special Embedment..... | 533 |

| | |
|--|-----|
| Trench Drainage..... | 536 |
| Verticals and Near Verticals..... | 538 |
| Embedment and Trenchfill..... | 539 |
| Standard Embedment..... | 541 |
| Special Embedment..... | 542 |
| Thrust Block Details..... | 544 |
| Thrust and Anchor Blocks..... | 545 |
| Restrained Joint System..... | 546 |
| Trench Drainage..... | 547 |
| Buried Crossings..... | 549 |
| Standard Trench Details..... | 553 |
| Thrust Block Details..... | 555 |
| Anchorage Details..... | 556 |
| Buried Crossings..... | 558 |
| SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS..... | 559 |
| Buried Crossings..... | 559 |
| Aerial Crossings..... | 563 |
| Ventilation Systems..... | 566 |
| Water Seal Arrangements..... | 568 |
| Emergency Relief Structures..... | 571 |
| Ventilation Systems..... | 572 |
| Aerial Crossings..... | 573 |
| Ventilation Systems..... | 574 |
| INSTALLATION PRACTICES / STRUCTURES..... | 575 |
| Valve and Hydrant Identification..... | 575 |
| Typical Surface Fitting Installation..... | 576 |
| Typical Appurtenance Installation..... | 578 |
| Aerial Crossings..... | 579 |
| Flanged Joints..... | 582 |
| FABRICATION DETAILS..... | 583 |
| Typical Steel Pipe Jointing..... | 583 |
| Typical Steel Fabrication..... | 586 |
| Joint Corrosion Protection..... | 587 |
| Abbreviations..... | 588 |
| Definitions..... | 589 |

List of Figures

| | |
|---|-----|
| FIGURE I SYSTEM DISAGGREGATION DIAGRAM..... | 68 |
| Figure 1.1 CONCEPT DESIGN FLOWCHART (Informative)..... | 76 |
| Figure 2.1 SPS OVERFLOW RISK REDUCTION DECISION DIAGRAM..... | 80 |
| Figure 3.1 TYPICAL PRE-COMMISSIONING AND COMMISSIONING PROCESS..... | 99 |
| Figure 3.2 TYPICAL HANDOVER TO WATER AGENCY..... | 100 |
| Figure 4.1 TYPICAL BOLTED CONNECTION DETAIL FOR FUSION BONDED COATED DUCTILE IRON FLANGES WITH STAINLESS STEEL FASTENERS..... | 105 |
| Figure 4.2 TYPICAL BOLTED CONNECTION DETAIL AND CORROSION PROTECTION PROCEDURE FOR BURIED DUCTILE IRON FLANGES WITH GALVANISED STEEL FASTENERS..... | 106 |
| Figure 4.3 TYPICAL BOLTED CONNECTION DETAIL FOR PE STUB FLANGE AND RAISED DUCTILE IRON FLANGE WITH STAINLESS STEEL FASTENERS AND BACKING PLATE..... | 106 |
| Figure 5.1 FLANGE FASTENER TIGHTENING SEQUENCE..... | 116 |
| Figure 5.2 TYPICAL INSULATED FLANGED JOINT FOR CATHODICALLY PROTECTED STEEL MAINS..... | 120 |
| Figure 6.1 TYPICAL EMERGENCY STORAGE STRUCTURE- CONFIGURATION 1..... | 135 |
| Figure 6.2 TYPICAL EMERGENCY STORAGE STRUCTURE – CONFIGURATION 2..... | 137 |

| | |
|---|-----|
| Figure 6.3 TYPICAL EMERGENCY STORAGE STRUCTURE – CONFIGURATION 3..... | 139 |
| Figure 6.4 TYPICAL EMERGENCY STORAGE STRUCTURE – CONFIGURATION 4..... | 141 |
| Figure 9.1 ALARM LEVEL CONTROL SETTINGS..... | 169 |
| Figure 11.1 HORIZONTAL DEVIATION BY DEFLECTION AT PIPE JOINTS – PLAN VIEW..... | 189 |
| Figure 11.2 HORIZONTAL DEFLECTION USING A DI SOC-SOC CONNECTOR AND PERMITTED JOINT DEFLECTIONS FOR DI PIPES AND OTHER APPLICABLE PIPE TYPES – PLAN VIEW..... | 190 |
| Figure 11.3 DEFLECTION USING DI BENDS WITH DI AND OTHER PERMITTED PIPE TYPES – PLAN VIEW..... | 190 |
| Figure 11.4 VERTICAL DEVIATION BY DEFLECTION AT PIPE JOINTS – SECTION VIEW..... | 191 |
| Figure 11.5 VERTICAL DEVIATION USING DI BENDS – SECTION VIEW..... | 191 |
| Figure 11.6 TYPICAL ANCHOR BLOCK DETAIL FOR VERTICAL BENDS..... | 192 |
| Figure 11.7 VERTICAL DEFLECTIONS USING FABRICATED PIPE AND FLANGES – SECTION VIEW..... | 192 |
| Figure 11.8 VERTICAL DEFLECTIONS USING DOUBLE OFFSET FABRICATED PIPE AND FLANGES – SECTION VIEW..... | 192 |
| Figure 11.9 SELF-CLEANSING FLOW CONDITIONS FOR INVERTED SIPHONS..... | 196 |
| Figure 11.10 TYPICAL SURGE WAVE..... | 199 |
| Figure 11.11 TYPICAL FATIGUE CYCLE..... | 201 |
| Figure 12.1 ALTERNATIVE END TREATMENT FOR CONCRETE ENCASED STEEL PIPELINES..... | 219 |
| FIGURE J1..... | 269 |
| FIGURE J2 POTENTIALLY UNSTABLE/LANDSLIP AREAS MONITORING PITS FOR DN 100 AND DN 150 RETICULATION MAINS IN ROAD RESERVES..... | 270 |
| FIGURE J3..... | 273 |
| FIGURE J4..... | 274 |
| Figure 28.1 BALL AND SOCKET JOINT..... | 350 |
| Figure 28.2 SLIP-IN WELDED JOINT..... | 350 |
| Figure 28.3 PLAIN END WELDED COLLAR JOINT..... | 351 |
| Figure 28.4 PLAIN END BUTT WELDED JOINT..... | 351 |
| Figure 28.5 CML/FBPE WELDED JOINT (CLPEWJ)..... | 351 |
| SPS–1100 Typical Catchment Plan..... | 440 |
| SPS–1101 Site Layout..... | 441 |
| SPS–1102 Site Plan..... | 442 |
| SPS–1103 Power and Control Cubicle, Base and Conduit Details..... | 443 |
| SPS–1104-1 Sections and Mean Static Head Calculation..... | 444 |
| SPS–1104-2 Sections and Mean Static Head Calculation..... | 445 |
| SPS–1105 Typical Hydraulic Profile..... | 446 |
| SPS–1200 Fronting and Not Fronting Adjacent Roadway..... | 447 |
| SPS–1201 Fronting Adjacent Roadway..... | 448 |
| SPS–1202 Not Fronting Adjacent Roadway..... | 449 |
| SPS–1203 Fronting Adjacent Roadway..... | 450 |
| SPS–1204 Fronting Adjacent Roadway..... | 451 |
| SPS–1205 Cross Section and Drainage Details..... | 452 |
| SPS–1206 Conceptual Site Layout..... | 453 |
| SPS–1207 Site Access Arrangements..... | 454 |
| SPS–1300 Inlet MH, Wet-Well and Valve Chamber..... | 455 |
| SPS–1301 Wet-Well, Buried Valves, DN 100 Pipework..... | 456 |
| SPS–1302 Wet-Well and Valve Chamber..... | 457 |
| SPS–1303 Pre-Cast Concrete Components..... | 458 |
| SPS–1304 Cover and Access Hole Details..... | 459 |
| SPS–1305 Conduit Details..... | 460 |
| SPS–1306 Plan, Section and Cover – Non-Trafficable..... | 461 |
| SPS–1307 Pipework..... | 462 |

| | |
|---|-----|
| SPS-1308 DN 50 Reduced Pressure Zone Device – Arrangement & Details..... | 463 |
| SPS-1309 Pumping Stations ≤40 L/s..... | 464 |
| SPS-1310 Pumping Stations >40 L/s..... | 465 |
| SPS-1350 General Arrangement Plan..... | 466 |
| SPS-1351 General Arrangement Section..... | 467 |
| SPS-1352 General Arrangement..... | 468 |
| SPS-1353 Typical Arrangement..... | 469 |
| SPS-1354 Support Beam Details..... | 470 |
| SPS-1355 Cover & Hinge Details..... | 471 |
| SPS-1356 Additional Details..... | 472 |
| SPS-1357 Typical Arrangement (non-trafficable)..... | 473 |
| SPS-1400 Detailed Arrangement..... | 474 |
| SPS-1401 Detailed Arrangement..... | 475 |
| SPS-1402 Typical Arrangement and Levels Configuration 1..... | 476 |
| SPS-1403 Shallow and Deep Installations and Brickwork..... | 477 |
| SPS-1404 Arrangement and Cross Section for DN 150 to DN 375 Overflow Pipes..... | 478 |
| SPS-1405 Arrangement and Cross Section for Pressure Mains ≤ DN 300..... | 479 |
| SPS-1406 General Arrangement (Trafficable)..... | 480 |
| SPS-1407 Details (Trafficable)..... | 481 |
| SPS-1408 General Arrangement (Non-Trafficable)..... | 482 |
| SPS-1409 Details (Non-Trafficable)..... | 483 |
| SPS-1410 Plans ≤6m Depth..... | 484 |
| SPS-1411 Section ≤6m Depth..... | 485 |
| SPS-1412 Wet-Well Inlet Sewers DN 150 to DN 250..... | 486 |
| SPS-1413 Wet-Well Inlet Sewers DN 300 to DN 450..... | 487 |
| SPS-1414 General Arrangement..... | 488 |
| SPS-1415 General Arrangement..... | 489 |
| SPS-1416 Details..... | 490 |
| SPS-1417 Arrangement and Details..... | 491 |
| SEW-1300 Sewers ≤ DN 300 Precast Types P1 & P2..... | 492 |
| SEW-1301 Sewers ≤ DN 300 Cast Insitu Types C1 & C2..... | 493 |
| SEW-1302 Pipe Connection Details..... | 494 |
| SEW-1303 Sewers ≤ DN 300 Changes in Level Details..... | 495 |
| SEW-1304 For Sewers ≤ DN 300 Typical Channel Arrangements | 496 |
| SEW-1305 Typical Channel Details..... | 497 |
| SEW-1306 Alternative Drop Connections..... | 498 |
| SEW-1307 Step Irons & Ladders..... | 499 |
| SEW-1308 Typical MH Cover Arrangements..... | 500 |
| SEW-1309 Sewers DN 375 to DN 750..... | 501 |
| SEW-1310 Permanent Formwork > DN 375..... | 502 |
| SEW-1311 Depth to Invert 6m to 15m..... | 503 |
| SEW-1312 Depth to Invert >15m..... | 504 |
| SEW-1313 MH Connection Details DN 110 to DN 450 PE Pipe..... | 505 |
| SEW-1314 Typical Installation..... | 506 |
| SEW-1315 MS & Variable Bend Installations..... | 507 |
| SEW-1316 TMS and Connection Installations..... | 508 |
| SEW-1317 Typical MS Cover Arrangements..... | 509 |
| SPS-1500 Hose Connection Bend Assemblies..... | 510 |
| SPS-1501 Wall Pipe Bracket Assemblies..... | 511 |
| SPS-1502 Wall Pipe Bracket Details..... | 512 |
| SPS-1503 Hose Connection Bends..... | 513 |

| | |
|--|-----|
| SPS–1504 Hose Connection Bend Quick Coupling Details..... | 514 |
| SPS–1505 Stilling Tube..... | 515 |
| SPS–1506 Opening Grate Type..... | 516 |
| SPS–1507 Opening Grate Type..... | 517 |
| SPS–1508 Survey Plate, Pump Label Plate, Valve Spindle Access..... | 518 |
| SPS–1550 Typical Arrangement Plan & Section..... | 519 |
| SPS–1551 Typical Arrangement Sections..... | 520 |
| SPS–1600 Typical Pressure Main Characteristic Curve..... | 521 |
| SPS–1601 Pressure Mains \leq DN 300..... | 522 |
| SPS–1602 Pump and Gravity..... | 523 |
| SPS–1603 Pressure Mains \leq DN 300 \leq 2.2 m to Invert..... | 524 |
| SPS–1604 Pressure Mains \leq DN 300 $>$ 2.2 m to Invert..... | 525 |
| SPS–1605 Pressure Mains \leq DN 300..... | 526 |
| SPS–1606 Pressure Mains $>$ DN 300..... | 527 |
| SPS–1607 Manual Air Release Arrangement..... | 528 |
| SPS–1608 Pipe Absolute Roughness Versus Mean Velocity Chart..... | 529 |
| SEW–1200 Allowable Bearing Pressures for Bulkheads..... | 530 |
| SEW–1201 Typical Arrangements..... | 531 |
| SEW–1202 Flexible & Rigid Pipes..... | 532 |
| SEW–1203 Inadequate Foundations Requiring Over Excavation & Replacement..... | 533 |
| SEW–1204 Support Utilising Piles..... | 534 |
| SEW–1205 Concrete & Stabilised Supports..... | 535 |
| SEW–1206 Bulkheads & Trenchstop..... | 536 |
| SEW–1207 Typical Systems..... | 537 |
| SEW–1208 Exposed & Concealed Methods..... | 538 |
| WAT–1200 Soil Classification Guidelines..... | 539 |
| WAT–1201 Typical Arrangement..... | 540 |
| WAT–1202 All Pipe Types..... | 541 |
| WAT–1203 Inadequate and Poor Foundation..... | 542 |
| WAT–1204 Concrete, Geotextile and Cement Stabilised Systems..... | 543 |
| WAT–1205 Concrete Blocks..... | 544 |
| WAT–1207 Gate Valves and Vertical Bends..... | 545 |
| WAT–1208 DN 100 to DN 375 DI Mains..... | 546 |
| WAT–1209 Bulkheads and Trenchstop..... | 547 |
| WAT–1210 Typical Systems..... | 548 |
| WAT–1211 Under Obstructions..... | 549 |
| WAT–1212 Major Roadways..... | 550 |
| WAT–1213 Railways..... | 551 |
| WAT–1214 Bored & Jacked Encasing Pipe Details..... | 552 |
| WAT–1250 Reticulation Mains DN 100 to DN 375..... | 553 |
| WAT–1251 Transfer and Distribution Mains DN 300 to DN 750..... | 554 |
| WAT–1252 DN 450 to DN 750..... | 555 |
| WAT–1253 Stop valves Installations up to DN1200 SCL Mains..... | 556 |
| WAT–1254 Stop valves Installations up to DN 750 DICL Mains..... | 557 |
| WAT–1255 Under Minor Obstructions..... | 558 |
| SEW–1400 Syphon Arrangement..... | 559 |
| SEW–1401 Railways..... | 560 |
| SEW–1402 Major Roadways..... | 561 |
| SEW–1403 Bored & Jacked Encasing Pipe Details..... | 562 |
| SEW–1404 Aqueduct Crossings..... | 563 |
| SEW–1405 Aqueduct Protection Grille..... | 564 |

| | |
|---|-----|
| SEW-1406 Bridge Crossing Concepts..... | 565 |
| SEW-1407 Induct Vent..... | 566 |
| SEW-1408 Educt Vent..... | 567 |
| SEW-1409 Main Type..... | 568 |
| SEW-1410 MAINTENACE HOLE SYSTEM..... | 569 |
| SEW-1411 TWIN MAINTENANCE HOLES..... | 570 |
| SEW-1412 Typical Arrangement DN 150 to DN 375..... | 571 |
| SEW-1451 Educt Vent Shaft Base Block Details..... | 572 |
| SEW-1455 Circular RC Piers in Non-Flood Conditions for DN 150 to DN 750 Sewers..... | 573 |
| SEW-1456 Educt Vent Stack and Holding Down Bolt Details..... | 574 |
| WAT-1300 Identification Markers & Marker Posts..... | 575 |
| WAT-1303 Gate Valve Surface Boxes Non-Trafficable..... | 576 |
| WAT-1304 Gate Valve Surface Boxes Trafficable..... | 577 |
| WAT-1307 Scour Arrangements..... | 578 |
| WAT-1320 Aqueduct..... | 579 |
| WAT-1321 Aqueduct Protection Grille..... | 580 |
| WAT-1322 Bridge Crossing Concepts..... | 581 |
| WAT-1313 Bolting Details..... | 582 |
| WAT-1400 Butt Welding of Joints..... | 583 |
| WAT-1401 Rubber Ring Joint Spigot Bands..... | 584 |
| WAT-1402 Welded Pipe Collars..... | 585 |
| WAT-1403 Bends..... | 586 |
| WAT-1408 Cement Mortar Lined Steel Pipe DN 300 to DN 1200..... | 587 |

List of Tables

| | |
|---|-----|
| Table 1.1 ASSET CATEGORIES..... | 73 |
| Table 1.2 TYPICAL ASSET DESIGN LIFE..... | 75 |
| Table 3.1 CLEARANCES BETWEEN PRESSURE MAINS AND UNDERGROUND SERVICES..... | 94 |
| Table 5.1 COLOUR IDENTIFICATION OF COMPONENTS IN RETICULATION SEWER SYSTEMS..... | 107 |
| Table 6.1 DEFAULT CONTROL LEVELS..... | 128 |
| Table 9.1 DEFAULT ALARM LEVELS..... | 164 |
| Table 9.2 TYPICAL LOCAL AND REMOTE ALARMS (Informative)..... | 164 |
| Table 9.3 TYPICAL REMOTE MONITORED CONDITIONS (Informative)..... | 165 |
| Table 10.1 BYPASS CONNECTION SIZES..... | 181 |
| Table 11.1 PRESSURE RE-RATING FACTORS FOR PLASTIC PIPES AT ELEVATED TEMPERATURES..... | 200 |
| Table 11.2 FATIGUE DE-RATING FACTORS FOR THERMOPLASTIC PIPES..... | 202 |
| Table 11.3 SCOUR SIZES..... | 206 |
| Table 12.1 REQUIREMENT FOR BULKHEADS AND TRENCHSTOPS..... | 221 |
| TABLE A1 ASSET CATEGORISATION AND INDICATIVE PROTECTIVE TREATMENT SCHEDULE..... | 238 |
| TABLE I1 GENERAL PERFORMANCE CHARACTERISTICS OF BOREHOLE AND TUNNELLING TECHNOLOGIES..... | 278 |
| Table 19.1 CONTROL CIRCUIT WIRING INSULATION COLOUR CODING..... | 316 |
| Table 24.1 TIMBER GUARDRAIL DEFAULT CONSTRUCTION DIMENSIONS..... | 330 |
| Table 25.1 RETAINING WALL DEFAULT CONSTRUCTION DIMENSIONS..... | 331 |
| Table 25.2 TIMBER HANDRAIL DEFAULT CONSTRUCTION DIMENSIONS..... | 333 |
| Table 34.1 ORDER OF ACCEPTANCE TESTING OF CIVIL ITEMS..... | 366 |
| Table 34.2 FLEXIBLE PIPES – MINIMUM COMPACTION EMBEDMENT, TRENCH FILL AND EMBANKMENT OF FLEXIBLE PIPES..... | 367 |
| Table 34.3 RIGID PIPES – MINIMUM COMPACTION EMBEDMENT, TRENCH FILL AND EMBANKMENT..... | 368 |

| | | | | | | | |
|--|------|----------|-----|--------|-----|---------|-----|
| Table | 34.4 | PRESSURE | AND | VACUUM | AIR | TESTING | |
| ACCEPTANCE TIMES FOR 7 KPA PRESSURE CHANGE..... | | | | | | | 371 |
| Table 34.5 CONCRETE MH TESTING FREQUENCY..... | | | | | | | 374 |
| Table 34.6 MINIMUM TEST TIMES FOR CONCRETE STRUCTURES..... | | | | | | | 375 |
| Table 34.7 MAXIMUM ALLOWABLE SHORT-TERM PIPE DEFLECTIONS..... | | | | | | | 377 |
| Table 36.1 SEWER GRADE TOLERANCES..... | | | | | | | 385 |
| TABLE K1 PROVER OUTSIDE DIAMETER FOR PVC AND GRP PIPES..... | | | | | | | 387 |
| Table L.1 DEFECT AND FEATURE REPORTING SUMMARY FOR RIGID SEWERS – VITRIFIED CLAY, STEEL REINFORCED CONCRETE WHERE REFERRAL TO WATER AGENCY IS NECESSARY TO ASCERTAIN THE REQUIRED CORRECTIVE ACTION..... | | | | | | | 390 |
| Table L.2 DEFECT AND FEATURE REPORTING SUMMARY FOR FLEXIBLE SEWER PIPES – PLASTICS (PVC, PE, PP, GRP), DUCTILE IRON AND STEEL WHERE REFERRAL TO WATER AGENCY IS NECESSARY TO ASCERTAIN THE REQUIRED CORRECTIVE ACTION..... | | | | | | | 393 |
| Table L.3 REPORTING SUMMARY FOR ITEM CONFIGURATION – ALL SEWERS..... | | | | | | | 396 |
| Table M.1 MAXIMUM DEPTH TO INVERT FOR PVC SEWERS..... | | | | | | | 400 |
| Table M.2 MAXIMUM DEPTH TO INVERT FOR PVC SEWERS (including W7 & T44 wheel loads)..... | | | | | | | 400 |
| Table M.3 MAXIMUM DEPTH TO INVERT FOR PP SEWERS..... | | | | | | | 401 |
| Table M.4 MAXIMUM DEPTH TO INVERT FOR PP SEWERS (including W7 & T44 wheel loads)..... | | | | | | | 401 |
| Table M.5 MAXIMUM DEPTH TO INVERT FOR FW-GRP SEWERS..... | | | | | | | 402 |
| Table M.6 MAXIMUM DEPTH TO INVERT FOR FW-GRP SEWERS (including W7 & T44 wheel loads)..... | | | | | | | 402 |
| Table M.7 MAXIMUM DEPTH TO INVERT FOR PE100 SEWERS..... | | | | | | | 403 |
| Table M.8 MAXIMUM DEPTH TO INVERT FOR PE100 SEWERS (including W7 & T44 wheel loads)..... | | | | | | | 403 |
| Table 38.1 MAXIMUM PARTICLE SIZE..... | | | | | | | 416 |
| Table 38.2 MINIMUM TRENCH DIMENSIONS (Informative)..... | | | | | | | 424 |
| LISTING OF STANDARD DRAWINGS..... | | | | | | | 432 |