



**WATER SERVICES  
ASSOCIATION OF AUSTRALIA**

# **VACUUM SEWERAGE CODE OF AUSTRALIA**

Version 1.3

# CONTENTS

PREFACE

INTRODUCTION

## **PART 0: GLOSSARY OF TERMS AND ABBREVIATIONS**

I Glossary of Terms

II Abbreviations

III Referenced Documents

IV Other References

## **PART 1: PLANNING AND DESIGN**

Contents

Preface

1 General

2 Concept Design

3 General Design

4 Materials Design

5 Hydraulic Design

6 Vacuum Station Design

7 Power System

8 Controls and Telemetry System

9 Vacuum Sewer Design

10 Collection Chambers

11 Pumping System

12 Pump Discharge Pipe Work

13 Pressure Mains

14 Structural Design

15 Site Infrastructure

16 Supporting Systems

17 Health and Safety

18 Design Review

19 Design Documentation and Drawings

## **PART 2: PRODUCTS AND MATERIALS**

Contents

20 Products and Materials Overview

## **PART 3: CONSTRUCTION**

### Contents

- 21 General
- 22 Quality
- 23 General Construction
- 24 Products, Materials and Equipment
- 25 Electrical Works
- 26 Telemetry System
- 27 Odour Control System
- 28 Mechanical Installation of Pumps, Vacuum Generators, Valves and Fittings
- 29 Metalwork
- 30 Access Road and Hardstand Areas
- 31 Retaining Walls
- 32 Excavation
- 33 Bedding For Pipes, Bends, Collection Chambers and Maintenance Structures
- 34 Pipe Laying and Jointing
- 35 Collection Chambers and Maintenance Holes (MHS)
- 36 Maintenance Shafts (MS and TMS) and Inspection Openings (IO)
- 37 Pipe Embedment and Support
- 38 Fill
- 39 Connection to Existing Sewers
- 40 Restoration
- 41 Acceptance Testing
- 42 Commissioning
- 43 Tolerances on As-Constructed Work
- 44 Work As Constructed Details

## **PART 4: STANDARD DRAWINGS**

### Contents

- 45 Introduction
- 46 Listing of Standard Drawings
- 47 Commentary on VAC–1100 Series Drawings - Vacuum Sewers
- 48 Commentary on VAC–1200 Series Drawings – Collection Chambers
- 49 Commentary on VAC–1300 Series Drawings - Vacuum Stations
- 50 Commentary on VAC–1400 Series Drawings - Embedment, Trench Fill and Restraints
- 51 Property Connection Details
- 52 Commentary on SEW–1300 Series Drawings - Access Structures

53 Commentary on SEW–1400 Series Drawings - Special Crossings/  
Structures Arrangements

54 Commentary on WAT–1300 Series Drawings – Installation Practices

55 Commentary on WAT–1400 Series Drawings – Fabrication Details

## **VACUUM SEWERAGE CODE OF AUSTRALIA VERSION 1.3**

### **APPENDICES**

Appendix A	Design Example
Appendix B	Quality Assurance of Products – Quality Assurance Options and Selection
Appendix C	Ovality Testing of PV and GRP Gravity Sewers – Default Prover Diameters
Appendix D	Precommissioning Checklist
Appendix E	Commissioning Schedule



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# PART 1: PLANNING AND DESIGN

Vacuum Sewerage Code of Australia  
Version 1.3

# CONTENTS

## PREFACE

### 1 GENERAL

#### 1.1 PLANNING

#### 1.2 VACUUM SEWER SYSTEMS

##### 1.2.1 Vacuum system philosophy

##### 1.2.2 Application of vacuum sewerage

##### 1.2.3 Description of the system

##### 1.2.3.1 Collection chamber and vacuum pipeline

##### 1.2.3.2 Vacuum station

#### 1.3 SCOPE

#### 1.4 PURPOSE AND APPLICATION

#### 1.5 PLANNING AND DESIGN RESPONSIBILITIES AND INTERFACES

##### 1.5.1 General

##### 1.5.2 Planning responsibilities

##### 1.5.3 Design responsibilities

##### 1.5.4 Consultation with other parties

#### 1.6 SEWER SYSTEM DESIGN APPROACH

##### 1.6.1 Overall objective

##### 1.6.2 System design life

##### 1.6.3 Objectives of the system design

##### 1.6.4 Design output

#### 1.7 DESIGN RESPONSIBILITIES

##### 1.7.1 Concept Plan

##### 1.7.2 Concept Design

##### 1.7.3 Detail Design

### 2 CONCEPT DESIGN

#### 2.1 LIFE CYCLE CONSIDERATIONS

#### 2.2 FUNCTIONALITY

#### 2.3 MAINTAINABILITY

#### 2.4 RELIABILITY

#### 2.5 DUE DILIGENCE REQUIREMENTS

#### 2.6 MATERIALS DESIGN

#### 2.7 STAGING

#### 2.8 SEPTICITY CONTROL

#### 2.9 ODOUR CONTROL

#### 2.10 TERRORISM

#### 2.11 COMMISSIONING PLAN

#### 2.12 OTHER

### 3 GENERAL DESIGN

#### 3.1 GENERAL

#### 3.2 DESIGN TOLERANCES

#### 3.3 LEVELS

- 3.4 UNFORESEEN GROUND CONDITIONS
- 3.5 IMPACT OF CONSEQUENTIAL DAMAGE
- 3.6 ENVIRONMENTAL CONSIDERATIONS
  - 3.6.1 General
  - 3.6.2 Urban salinity
  - 3.6.3 Vegetation
  - 3.6.4 Contaminated sites
  - 3.6.5 Tidal zones
- 3.7 EASEMENTS
- 3.8 SPECIAL DESIGN CONSIDERATIONS
- 3.9 CROSSINGS
  - 3.9.1 General
  - 3.9.2 Creeks and drainage reserves
  - 3.9.3 Major road crossings
  - 3.9.4 Railway reserves
- 3.10 MECHANICAL PROTECTION OF PIPELINES
- 3.11 OVERHEAD POWER LINES AND TRANSMISSION TOWERS
- 3.12 OBSTRUCTIONS AND CLEARANCES
  - 3.12.1 General
  - 3.12.2 Surface obstructions
  - 3.12.3 Clearance from transmission towers
  - 3.12.4 Clearance from structures
  - 3.12.5 Underground obstructions and services
    - 3.12.5.1 General
    - 3.12.5.2 Clearance requirements
  - 3.12.6 Crossing services
  - 3.12.7 Deviation of pipelines around structures
- 3.13 DISUSED OR REDUNDANT PIPELINES
- 3.14 SEWAGE QUALITY
  - 3.14.1 Septicity
  - 3.14.2 Sewage quality / Trade waste management

## **4 MATERIALS DESIGN**

- 4.1 GENERAL
- 4.2 CORROSION PROTECTION
  - 4.2.1 Protective coatings
  - 4.2.2 Concrete surfaces
  - 4.2.3 Metallic materials
  - 4.2.4 Miscellaneous items
  - 4.2.5 Corrosion protection against aggressive environments
  - 4.2.6 Cathodic protection
  - 4.2.7 Stray current corrosion
  - 4.2.8 Protection against contaminated ground

## **5 HYDRAULIC DESIGN**

- 5.1 GENERAL
- 5.2 VACUUM STATION DESIGN INFLOWS
- 5.3 VACUUM SEWER DESIGN FLOWS



5.3.1 General

5.3.2 Air-to-liquid ratios

## **6 VACUUM STATION DESIGN**

### 6.1 INTRODUCTION

### 6.2 SITE SELECTION, LOCATION AND LAYOUT

6.2.1 Site selection

6.2.2 Right of occupancy and access

6.2.3 Location and layout

6.2.4 Site area

6.2.5 External site layout and access

### 6.3 VACUUM STATION LAYOUT

### 6.4 VACUUM VESSEL

6.4.1 Operating volume

6.4.2 Capacity

6.4.3 Design, construction and testing

### 6.5 MOISTURE REMOVAL VESSEL

### 6.6 VACUUM GENERATORS AND PIPE WORK

6.6.1 Vacuum generator capacity

6.6.2 Evacuation time

6.6.3 Vacuum generator types

6.6.4 Vacuum generator selection

6.6.5 Vacuum generator operating vacuum

6.6.6 Vacuum generator motors

6.6.7 Vacuum pipe work and valves

6.6.8 Make-up water tank

### 6.7 EMERGENCY PUMPING ARRANGEMENTS

### 6.8 SEWAGE DISCHARGE PUMPS AND DELIVERY PIPE WORK

6.8.1 General

6.8.2 Electric motors

6.8.3 Shaft seals

6.8.4 Equalisation lines

6.8.5 Total dynamic head (TDH)

6.8.6 Net positive suction head

6.8.7 Delivery pipe work

### 6.9 GAUGES AND RECORDERS

6.9.1 Vacuum gauges

6.9.2 Pressure gauges

6.9.3 Vacuum / Pressure recorder

### 6.10 NOISE

### 6.11 ODOUR CONTROL

6.11.1 General

6.11.2 Biofilters

### 6.12 SKID-MOUNTED PACKAGED STATIONS

## **7 POWER SYSTEM**

### 7.1 ELECTRICAL DESIGN AND INSTALLATION

7.1.1 Scope

- 7.1.2 Compliance
- 7.1.3 Responsibilities

## 7.2 POWER SUPPLY

- 7.2.1 General
- 7.2.2 Security of supply
- 7.2.3 Primary supply
- 7.2.4 Duplicate supply
- 7.2.5 Emergency power
- 7.2.6 On-site generator
- 7.2.7 Mobile generator
- 7.2.8 Power factor correction

## 7.3 POWER AND CONTROL CUBICLE

- 7.3.1 Design
- 7.3.2 Switchboard
- 7.3.3 Meter requirements
- 7.3.4 Lighting

# **8 CONTROLS AND TELEMETRY SYSTEM**

## 8.1 GENERAL

## 8.2 CONTROL SYSTEMS

- 8.2.1 General
- 8.2.2 Vacuum generator control
- 8.2.3 Vacuum vessel control
- 8.2.4 Pumping control

## 8.3 ALARMS

- 8.3.1 General
- 8.3.2 Locally displayed alarms
- 8.3.3 Remote alarms

## 8.4 ALARM, STATUS MONITORING AND CONTROL TELEMETRY

- 8.4.1 General design principles
- 8.4.2 Reliability
- 8.4.3 Alarm creation function

# **9 VACUUM SEWER DESIGN**

## 9.1 STAGING

## 9.2 SEWER LAYOUT

- 9.2.1 General layout
- 9.2.2 Zoning
- 9.2.3 Location
  - 9.2.3.1 Vacuum sewers
  - 9.2.3.2 Vacuum sewers in road reserves
  - 9.2.3.3 Vacuum sewers in easements
- 9.2.4 Sewer depth

## 9.3 HEADLOSS

- 9.3.1 Available vacuum
- 9.3.2 Friction loss
- 9.3.3 Static lift loss

## 9.4 SEWER PROFILES

- 9.4.1 General
- 9.4.2 Profile design
- 9.4.3 Lift design
- 9.4.4 Connection to vacuum vessel
- 9.4.5 Connecting sewers
- 9.4.6 Bends
- 9.4.7 Waterlogging

## 9.5 PIPE WORK AND FITTINGS FOR VACUUM SEWERS

- 9.5.1 General
- 9.5.2 Polyvinylchloride (PVC) pipes and fittings
- 9.5.3 Polyethylene (PE) pipes and fittings
- 9.5.4 Flexible pipes
- 9.5.5 Jointing of PVC pipes and fittings
- 9.5.6 Jointing of PE pipes and fittings

## 9.6 DIVISION VALVES

- 9.6.1 General
- 9.6.2 Division valve chambers
- 9.6.3 Division valve covers
- 9.6.4 Division valve locations

# 10 COLLECTION CHAMBERS

## 10.1 DESIGN CRITERIA

- 10.1.1 General design requirements
- 10.1.2 Location
- 10.1.3 Number of properties connected
- 10.1.4 Maximum flows to collection chambers
- 10.1.5 Flotation
- 10.1.6 Sensor pipes
- 10.1.7 Breather pipes and bells
- 10.1.8 Emergency storage
- 10.1.9 Covers and frames

## 10.2 VACUUM INTERFACE VALVES

- 10.2.1 General
- 10.2.2 Cycle counters

## 10.3 SERVICE CONNECTIONS

- 10.3.1 General
- 10.3.2 Design criteria

# 11 PUMPING SYSTEM

## 11.1 STAGING

## 11.2 HYDRAULIC DESIGN

## 11.3 PUMP EQUIPMENT

## 11.4 PUMP SELECTION

- 11.4.1 General
- 11.4.2 Total dynamic head (TDH)
- 11.4.3 Net positive suction head
- 11.4.4 Impeller selection
- 11.4.5 Electric motors

- 11.4.6 Shaft seals
- 11.4.7 Equalisation lines
- 11.5 PUMP STARTERS AND VARIABLE SPEED DRIVES
  - 11.5.1 General
  - 11.5.2 Single and double speed starters
  - 11.5.3 Soft starters
  - 11.5.4 Variable speed drives
- 11.6 HARMONICS AND RADIO FREQUENCY INTERFERENCE
- 11.7 EMERGENCY STOP

## **12 PUMP DISCHARGE PIPE WORK**

- 12.1 GENERAL
- 12.2 HYDRAULIC DESIGN
- 12.3 SYSTEM CURVES
- 12.4 SIZING
- 12.5 VALVES
  - 12.5.1 General
  - 12.5.2 Non-return valves
  - 12.5.3 Isolating valves
- 12.6 SCOURS
- 12.7 DISMANTLING JOINTS
- 12.8 PIPE WORK SUPPORT
- 12.9 PRESSURE MAIN TAPPINGS
- 12.10 ACCESS COVERS
- 12.11 CONDITION MONITORING AND MAINTENANCE

## **13 PRESSURE MAINS**

- 13.1 GENERAL

## **14 STRUCTURAL DESIGN**

- 14.1 VACUUM STATION
  - 14.1.1 Design loads and forces
  - 14.1.2 Reinforced concrete structures
  - 14.1.3 Steel structures
  - 14.1.4 Foundations
  - 14.1.5 Vacuum station walls
  - 14.1.6 Vacuum station slabs
    - 14.1.6.1 Base slab
    - 14.1.6.2 Ground level slab
- 14.2 PIPELINES
  - 14.2.1 General
  - 14.2.2 Products and materials
  - 14.2.3 Structural computations
  - 14.2.4 Internal forces
  - 14.2.5 External forces
    - 14.2.5.1 General
    - 14.2.5.2 Pipe cover
    - 14.2.5.3 Trench width
    - 14.2.5.4 Pipe embedment

- 14.2.6 Foundation design and ground water control
- 14.2.7 Geotechnical considerations
  - 14.2.7.1 General
  - 14.2.7.2 Pipelines in engineered or controlled fill
  - 14.2.7.3 Pipelines in non-engineered fill
  - 14.2.7.4 Filling along route of pipeline
  - 14.2.7.5 Mine subsidence
  - 14.2.7.6 Slip areas
  - 14.2.7.7 Water-charged ground
- 14.2.8 Above ground crossings
- 14.2.9 Bulkheads and trenchstops
- 14.2.10 Trenchless technology
- 14.2.11 Pipeline anchorage
  - 14.2.11.1 General
  - 14.2.11.2 Thrust blocks
  - 14.2.11.3 Anchor blocks
  - 14.2.11.4 Restrained elastomeric seal joint pressure mains
  - 14.2.11.5 Restraint requirements for special situations

## **15 SITE INFRASTRUCTURE**

- 15.1 ACCESS
  - 15.1.1 General
  - 15.1.2 Site requirements
  - 15.1.3 Access road
  - 15.1.4 Provisions for parking
  - 15.1.5 Pavement design
- 15.2 MAINTENANCE CLEARANCES
- 15.3 DRAINAGE
- 15.4 BUILDINGS
- 15.5 SITE SECURITY
- 15.6 CONSTRUCTION REQUIREMENTS
- 15.7 SIGNAGE
- 15.8 LANDSCAPING

## **16 SUPPORTING SYSTEMS**

- 16.1 SERVICES
  - 16.1.1 General
  - 16.1.2 Water
  - 16.1.3 Telephone / Telemetry lines
  - 16.1.4 General lighting and power
- 16.2 VACUUM STATION FIXTURES
  - 16.2.1 Water closet
  - 16.2.2 Wash trough
  - 16.2.3 Work bench
- 16.3 MATERIALS HANDLING
  - 16.3.1 Lifting equipment
  - 16.3.2 Handling and storage of hazardous material
- 16.4 SECURITY
- 16.5 FIRE CONTROL

## **17 HEALTH AND SAFETY**

### 17.1 GENERAL

### 17.2 HAZARDS

### 17.3 HEALTH AND SAFETY

#### 17.3.1 General

#### 17.3.2 Working at heights

### 17.4 CONFINED SPACES

## **18 DESIGN REVIEW**

## **19 DESIGN DOCUMENTATION AND DRAWINGS**

### 19.1 DOCUMENTATION

#### 19.1.1 General

#### 19.1.2 Risk assessment

#### 19.1.3 Operation and maintenance requirements

#### 19.1.4 Contingency plans

#### 19.1.5 Design records

#### 19.1.6 Resources

#### 19.1.7 Approvals and conditions

### 19.2 DESIGN DRAWINGS

#### 19.2.1 General

#### 19.2.2 Real property information

#### 19.2.3 Sewers

#### 19.2.4 Structures

#### 19.2.5 Vacuum stations

#### 19.2.6 Pressure mains

#### 19.2.7 Longitudinal sections (profiles)

#### 19.2.8 Title block notation and standard notes

#### 19.2.9 Other

#### 19.2.10 Electrical and telemetry

### 19.3 DRAFTING STANDARDS

#### 19.3.1 General

#### 19.3.2 Scale

#### 19.3.3 Recording of as-constructed information

## **TABLES**

Table 1.1 Typical Asset Design Life

Table 3.1 Clearances Between Pipelines and Underground Services

Table 5.1 Design Flows for PN 12 PVC-U Vacuum Sewers

Table 5.2 Design Flows for Series 1 PN 12 PVC-M Vacuum Sewers

Table 5.3 Design Flows for PN 10 80 (SDR 13.6) Vacuum Sewers

Table 5.4 Default Design Air-to-Liquid Ratios

Table 8.1 Typical Local and Remote Alarms

Table 9.1 Lift Lengths, Heights and Falls for PVC-U and PVC-M Vacuum Sewers

Table 9.2 Lift Lengths, Heights and Falls for PE Vacuum Sewers

Table 14.1 Requirements for Bulkheads and Trenchstops

## **FIGURES**

Figure I	Vacuum Sewer System Disaggregation Diagram
Figure II	Vacuum Station Disaggregation Diagram
Figure 1.1	Concept Design Flowchart
Figure 2.1	Overflow Risk Reduction Decision Diagram
Figure 3.1	Deflection at Joints
Figure 3.2	Deflection Using Soc-Soc Bends
Figure 3.3	Deflection Using Soc-Soc Connectors
Figure 6.1	Vacuum Vessel Operating Levels - Schematic Only
Figure 9.1	Typical Vacuum Reticulation System Layout
Figure 9.2	Sewer Profile for Level Ground Vacuum Sewers
Figure 9.3	Sewer Profile for Rising Ground Vacuum Sewers
Figure 9.4	Method of Lifting Main Sewer Into Vacuum Vessel
Figure 9.5	Connections to Sewers Relative to Invert Levels
Figure 9.6	Service Connections and Static Lifts
Figure 9.7	Methods of Joining Service Connections and Branch Sewers to Vacuum Sewers
Figure 10.1	Correct and Incorrect Methods of Servicing Properties at Different Elevations



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# **PART 2: PRODUCTS AND MATERIALS**

Vacuum Sewerage Code of Australia  
Version 1.3



## CONTENTS

### 20 PRODUCTS AND MATERIALS OVERVIEW

20.1 PURPOSE

20.2 SCOPE

20.3 RESPONSIBILITIES

20.3.1 Water Agency

20.3.2 Designer

20.3.3 Constructor

20.3.4 Purchaser

20.4 PRODUCT AND MATERIAL STANDARDS AND SPECIFICATIONS

20.4.1 Product standards

20.4.2 Product specifications

20.5 QUALITY ASSURANCE

20.5.1 Default requirement

20.5.2 Additional information on quality assurance

20.5.3 Innovative products and materials

Disclaimer

20.6 SELECTION GUIDE FOR PIPELINE SYSTEMS

20.7 ADDITIONAL PRODUCT AND MATERIAL INFORMATION

### TABLES

Table 20.1	Principal Gravity Sewer Pipeline Systems Draining to Vacuum Collection Chambers
Table 20.2	Principal Sewerage Gravity Pipeline Systems Draining to Vacuum Collection Systems
Table 20.3	Principal Vacuum Sewer Pipeline Systems and Components
Table 20.4	Principal Vacuum Sewer Pipeline Systems and Components - Precautions, Limitations Advantages and Disadvantages



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# **PART 3: CONSTRUCTION**

Vacuum Sewerage Code of Australia  
Version 1.3

# CONTENTS

- 21 GENERAL
- 21.1 SCOPE
- 21.2 INTERPRETATION
- 22 QUALITY
- 22.1 QUALITY ASSURANCE
  - 22.1.1 General
  - 22.1.2 Quality management system
  - 22.1.3 Quality system
  - 22.1.4 Project management plan
  - 22.1.5 Inspection and test plans
  - 22.1.6 Quality tests
  - 22.1.7 Quality audits
  - 22.1.8 Traceability
  - 22.1.9 Quality records
  - 22.1.10 Inspection
- 22.2 PERSONNEL QUALIFICATIONS
- 23 GENERAL CONSTRUCTION
- 23.1 GENERAL
- 23.2 ORDER OF CONSTRUCTION, TESTING AND COMMISSIONING
  - 23.2.1 Vacuum sewers
  - 23.2.2 Gravity sewers
- 23.2.3 PRESSURE MAINS
- 23.3 CONTRACT INTERFACES
- 23.4 CUSTOMER FOCUS
  - 23.4.1 General
  - 23.4.2 Resolution of complaints
- 23.5 PROTECTION OF PEOPLE, PROPERTY AND ENVIRONMENT
  - 23.5.1 Safety of people
  - 23.5.2 Protection of other services
  - 23.5.3 Disused / Redundant sewers
  - 23.5.4 Road reserves or other thoroughfares
    - 23.5.4.1 TREATMENT OF PAVEMENTS AND OTHER SURFACES
    - 23.5.4.2 TRAFFIC MANAGEMENT
    - 23.5.4.3 CLEANLINESS OF ROADS, PATHS, ACCESSES AND DRAINAGE PATHS
    - 23.5.4.4 STORAGE OF PRODUCTS, MATERIALS AND EQUIPMENT
    - 23.5.4.5 OBSTRUCTION OF STREET DRAINAGE
  - 23.5.5 Private and public properties
  - 23.5.6 Protection of the environment and heritage areas
    - 23.5.6.1 General
    - 23.5.6.2 Collection and disposal of wastes
    - 23.5.6.3 Protection of adjacent lands and vegetation
    - 23.5.6.4 Control of water pollution
    - 23.5.6.5 Acid sulphate and contaminated soils
    - 23.5.6.6 Control of noise and atmospheric pollution
- 23.6 AFFECTED PARTY NOTIFICATIONS
- 23.7 ALTERATION OF EXISTING SERVICES
- 23.8 SURVEY MARKS
- 23.9 CONSTRUCTION TOLERANCES
- 23.10 LATENT CONDITIONS
- 24 PRODUCTS, MATERIALS AND EQUIPMENT
  - 24.1 AUTHORISED PRODUCTS AND MATERIALS

- 24.2 REJECTED PRODUCTS AND MATERIALS
- 24.3 ELECTRICAL EQUIPMENT
- 24.4 VACUUM GENERATORS AND SEWAGE PUMPS
- 24.5 TRANSPORTATION, HANDLING AND STORAGE OF PRODUCTS AND MATERIALS
- 24.6 DELIVERY AND STORAGE OF ELECTRICAL EQUIPMENT
- 24.7 DELIVERY INSPECTION OF PRODUCTS AND MATERIALS
- 24.8 VACUUM VESSELS AND MOISTURE REMOVAL VESSELS
- 24.9 FASTENERS
- 24.10 WORKS INSPECTION AND TESTING
  - 24.10.1 Switchboards
  - 24.10.2 Vacuum generators
  - 24.10.3 Sewage pumps
  - 24.10.4 Motors
  - 24.10.5 Vacuum vessels
  - 24.10.6 Moisture removal vessels
- 24.11 CONCRETE WORKS
  - 24.11.1 Delivery
  - 24.11.2 Transportation of concrete
  - 24.11.3 Formwork
  - 24.11.4 Reinforcement
  - 24.11.5 Placement
    - 24.11.5.1 General
    - 24.11.5.2 Placement in water
  - 24.11.6 Slump
  - 24.11.7 Compaction
  - 24.11.8 Stripping
  - 24.11.9 Curing
  - 24.11.10 Repair of blemishes
- 24.12 SUPPLY OF WATER TO THE WORKS
- 24.13 ON-SITE STOCKPILES
- 25 ELECTRICAL WORKS
  - 25.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS
  - 25.2 SCOPE OF WORK
  - 25.3 SUPPLY AUTHORITY REQUIREMENTS AND METERING
  - 25.4 CONSUMER MAINS
    - 25.4.1 Point of supply
    - 25.4.2 Cable size
    - 25.4.3 Maximum demand
    - 25.4.4 Calculations to be submitted
    - 25.4.5 Mains in reserves
    - 25.4.6 Mains requirements
    - 25.4.7 Lead-in pole and overhead mains construction
      - 25.4.7.1 Lead-in pole
      - 25.4.7.2 Poles
      - 25.4.7.3 Installation of poles
      - 25.4.7.4 Aerial cables
    - 25.4.8 Underground cable installation
      - 25.4.8.1 General
      - 25.4.8.2 Location
      - 25.4.8.3 Excavation and bedding
      - 25.4.8.4 Underground cable marking
      - 25.4.8.5 Cable installation on poles

- 25.4.8.6 Road crossings
- 25.5 EARTHING
  - 25.5.1 General
  - 25.5.2 Earth circuits
  - 25.5.3 Labelling
- 25.6 SWITCHBOARD INSTALLATION
  - 25.6.1 General
  - 25.6.2 Equipment mounting
  - 25.6.3 Thermal derating of equipment
  - 25.6.4 Labelling
    - 25.6.4.1 General
    - 25.6.4.2 Incoming mains and pump and motor detail labels
    - 25.6.4.3 Main labels
    - 25.6.4.4 Cubicle labels
    - 25.6.4.5 Danger notices
    - 25.6.4.6 Asset and equipment number labels
- 25.7 CIRCUITS
  - 25.7.1 Main circuits
  - 25.7.2 Control circuit wiring
- 25.8 CABLING
  - 25.8.1 General
  - 25.8.2 Conduits
  - 25.8.3 Cable protection
  - 25.8.4 Cable trays
  - 25.8.5 Junction boxes
- 25.9 INSTALLATION OF GENERATOR AND PUMP CABLES
  - 25.9.1 Numbering of generators/pumps
  - 25.9.2 Installation
- 25.10 INSTALLATION OF LEVEL SENSORS
  - 25.10.1 General
  - 25.10.2 Collection chamber level sensor probes
  - 25.10.3 Vacuum vessel level sensor probes (at the vacuum station)
- 25.11 TERMINATIONS
  - 25.11.1 General
  - 25.11.2 Glands
  - 25.11.3 Mains and pump terminations
- 25.12 PAINTING
  - 25.12.1 General
  - 25.12.2 Paint materials
  - 25.12.3 Surface preparation
  - 25.12.4 Painting and finish
- 25.13 INSTALLATION IN VALVE PITS
  - 25.13.1 General
  - 25.13.2 Cables
- 25.14 NOTIFICATION OF ELECTRICAL WORK
- 26 TELEMETRY SYSTEM
  - 26.1 COMPLIANCE WITH AUTHORITIES, STATUTES, REGULATIONS AND STANDARDS
  - 26.2 SCOPE OF WORK
  - 26.3 HARDWARE INSTALLATION
  - 26.4 PLC PROGRAMMING
  - 26.5 SCADA DATABASE CONFIGURATION
- 27 ODOUR CONTROL SYSTEM

- 28 MECHANICAL INSTALLATION OF PUMPS, VACUUM GENERATORS, VALVES AND FITTINGS
  - 28.1 GENERAL
  - 28.2 FLANGED JOINTS
  - 28.3 INSTALLATION OF PUMPING AND VACUUM GENERATOR UNITS
    - 28.3.1 General
    - 28.3.2 Machinery alignment
    - 28.3.3 Unit numbers
    - 28.3.4 Test tapping points
  - 28.4 GAUGES AND RECORDERS
    - 28.4.1 Vacuum gauges
    - 28.4.2 Pressure gauges
    - 28.4.3 Vacuum/pressure recorder
- 29 METALWORK
  - 29.1 STEELWORK
  - 29.2 ALUMINIUM ALLOY COMPONENTS
  - 29.3 STAINLESS STEEL COMPONENTS
  - 29.4 FASTENERS
- 30 ACCESS ROAD AND HARDSTAND AREAS
  - 30.1 GENERAL
  - 30.2 SUBGRADE
  - 30.3 BASECOURSE
  - 30.4 SPRAYED BITUMINOUS SEALING
  - 30.5 ASPHALTIC CONCRETE
  - 30.6 TIMBER GUARDRAIL
- 31 RETAINING WALLS
  - 31.1 RETAINING WALLS - TIMBER CANTILEVER
    - 31.1.1 General
    - 31.1.2 Handrails
  - 31.2 RETAINING WALLS - CONCRETE - CRIB WALL
    - 31.2.1 General
    - 31.2.2 Foundations
    - 31.2.3 Cribfill and backfill
    - 31.2.4 Drainage
    - 31.2.5 Handrails
- 32 EXCAVATION
  - 32.1 SAFETY
  - 32.2 LIMITS OF EXCAVATION
  - 32.3 EXCAVATION ACROSS IMPROVED SURFACES
  - 32.4 EXCAVATION IN ROOT ZONES
  - 32.5 BLASTING
  - 32.6 SUPPORT OF EXCAVATIONS
  - 32.7 DRAINAGE AND DEWATERING
  - 32.8 FOUNDATIONS AND FOUNDATION STABILISATION
  - 32.9 SURPLUS EXCAVATED MATERIAL
- 33 BEDDING FOR PIPES, BENDS, COLLECTION CHAMBERS AND MAINTENANCE STRUCTURES
  - 33.1 TRENCH FLOOR PREPARATION
  - 33.2 BEDDING MATERIALS
  - 33.3 PLACEMENT OF BEDDING
  - 33.4 SPECIAL PIPE SUPPORT FOR NON-SUPPORTIVE SOILS
  - 33.5 BEDDING FOR PIPES AND BENDS
  - 33.6 BEDDING FOR COLLECTION CHAMBERS

- 33.7 BEDDING FOR MAINTENANCE SHAFTS AND VARIABLE BENDS
- 33.8 BEDDING FOR MAINTENANCE HOLES
- 34 PIPE LAYING AND JOINTING
  - 34.1 INSTALLATION OF PIPES
    - 34.1.1 General
    - 34.1.2 Cleaning, inspection and joint preparation
    - 34.1.3 Polyethylene
    - 34.1.4 Laying
  - 34.2 HORIZONTAL AND VERTICAL DEFLECTION OF GRAVITY AND VACUUM SEWERS AND PRESSURE MAINS
    - 34.2.1 General
    - 34.2.2 Methods of deflection
  - 34.3 HORIZONTAL AND VERTICAL SEPARATION OF CROSSING PIPELINES
  - 34.4 FLOTATION CONTROL
  - 34.5 THRUST AND ANCHOR BLOCKS AND RESTRAINED JOINTS FOR PRESSURE MAINS
  - 34.6 COLLECTION CHAMBERS, SERVICE CONNECTIONS AND PROPERTY CONNECTION SEWERS
  - 34.7 DEAD ENDS
  - 34.8 MARKING OF PROPERTY CONNECTIONS AND DEAD ENDS
  - 34.9 MARKING TAPES
    - 34.9.1 Non-detectable marking tape
    - 34.9.2 Detectable marking tape
  - 34.10 VALVES AND SURFACE FITTINGS
    - 34.10.1 Installation
    - 34.10.2 Scours for pressure mains
  - 34.11 BORED PIPES UNDER ROADS, DRIVEWAYS AND ELSEWHERE
  - 34.12 BRIDGE CROSSINGS
  - 34.13 TRENCH STOPS FOR PRESSURE MAINS
  - 34.14 BULKHEADS FOR PRESSURE MAINS
  - 34.15 CORROSION PROTECTION OF CAST IRON FOR PRESSURE MAINS
  - 34.16 AQUEDUCTS
  - 34.17 LOCATION MARKERS
  - 34.18 FLANGED JOINTS
  - 34.19 WELDING OF STEEL PRESSURE MAINS
    - 34.19.1 General
    - 34.19.2 Field welding of flanges
- 35 COLLECTION CHAMBERS AND MAINTENANCE HOLES (MHS)
  - 35.1 GENERAL
  - 35.2 COLLECTION CHAMBER AND MH BASES
  - 35.3 TRENCH DRAINAGE AROUND COLLECTION CHAMBERS AND MHS
  - 35.4 PRECAST CONCRETE SYSTEMS
  - 35.5 CAST IN-SITU CONCRETE COLLECTION CHAMBERS AND MHS
  - 35.6 BENCHING AND CHANNELS
  - 35.7 INTERNAL COATING OF CONCRETE COLLECTION CHAMBERS AND MHS
  - 35.8 COVERS
  - 35.9 CONNECTIONS TO COLLECTION CHAMBERS AND MHS
  - 35.10 MH DROPS
- 36 MAINTENANCE SHAFTS (MS AND TMS) AND INSPECTION OPENINGS (IO)
  - 36.1 GENERAL
  - 36.2 SEALING CAPS
  - 36.3 COVERS
  - 36.4 CONNECTIONS TO MSS AND TMSS

- 37 PIPE EMBEDMENT AND SUPPORT
  - 37.1 GENERAL
  - 37.2 EMBEDMENT MATERIALS
  - 37.3 COMPACTION OF EMBEDMENT
    - 37.3.1 General
    - 37.3.2 Methods
      - 37.3.3 Compaction trials/Pre-qualification of embedment compaction method
        - 37.3.3.1 General
        - 37.3.3.2 Test method
        - 37.3.3.3 Interpretation and applicability
      - 37.3.4 Compaction control
  - 37.4 SPECIAL BEDDING AND EMBEDMENTS/GEOTEXTILE SURROUND AND PILLOW
  - 37.5 REMOVAL OF TRENCH SUPPORTS
  - 37.6 CONCRETE EMBEDMENT AND ENCASEMENT
- 38 FILL
  - 38.1 TRENCH FILL
  - 38.2 GENERAL
  - 38.3 MATERIAL REQUIREMENTS
  - 38.4 COMPACTION OF TRENCH FILL
  - 38.5 EMBANKMENT FILL
  - 38.6 DRIVES AND TUNNEL FILL
- 39 CONNECTION TO EXISTING VACUUM AND GRAVITY SEWERS
- 40 RESTORATION
  - 40.1 GENERAL
  - 40.2 PAVEMENTS
  - 40.3 LAWNS
  - 40.4 GRASSED AREAS
  - 40.5 BUSHLAND
  - 40.6 PROVISION FOR SETTLEMENT
  - 40.7 MAINTENANCE OF RESTORED SURFACES
- 41 ACCEPTANCE TESTING
  - 41.1 PIPELINES
  - 41.2 VISUAL EXTERNAL INSPECTION
  - 41.3 COMPACTION TESTING
    - 41.3.1 General
    - 41.3.2 Minimum compaction
    - 41.3.3 Embedment compaction testing
      - 41.3.3.1 Applicable pipe sizes
      - 41.3.3.2 Frequency and location of embedment tests
      - 41.3.3.3 Retesting
    - 41.3.4 Trench fill compaction testing
      - 41.3.4.1 Trafficable Test Zone
      - 41.3.4.2 Non-trafficable test zone
      - 41.3.4.3 Test method
      - 41.3.4.4 Frequency and location of tests
      - 41.3.4.5 Retesting
    - 41.3.5 Other fill compaction testing
      - 41.3.5.1 General
      - 41.3.5.2 Trafficable test zone
      - 41.3.5.3 Non-trafficable test zone
      - 41.3.5.4 Frequency and location of tests
      - 41.3.5.5 Retesting
  - 41.4 VACUUM TESTING OF VACUUM SEWERS AND SERVICE CONNECTIONS



- 41.4.1 General
- 41.4.2 Vacuum test equipment
- 41.4.3 Daily vacuum test
- 41.4.4 Complete sewer vacuum test
- 41.4.5 Identification and repair of leaks and retesting
- 41.5 AIR PRESSURE AND VACUUM TESTING OF GRAVITY SEWERS
  - 41.5.1 General
  - 41.5.2 Air testing methods for sewers
    - 41.5.2.1 Vacuum testing
    - 41.5.2.2 Low pressure air testing
  - 41.5.3 Testing of concrete MHs
    - 41.5.3.1 General
    - 41.5.3.2 Test method
- 41.6 HYDROSTATIC PRESSURE TESTING OF PRESSURE MAINS
  - 41.6.1 General
  - 41.6.2 System test pressure
  - 41.6.3 Maximum allowable loss
  - 41.6.4 Test procedure
  - 41.6.5 Satisfactory pressure test
  - 41.6.6 Failure of test
- 41.7 INFILTRATION TESTING
- 41.8 DEFLECTION (OVALITY) TESTING OF FLEXIBLE GRAVITY SEWERS
  - 41.8.1 General
  - 41.8.2 Ovality proving tools
  - 41.8.3 Flexible sewers  $\leq$ DN 300
- 41.9 CCTV INSPECTION
- 41.10 ELECTRICAL WORKS
- 42 COMMISSIONING
  - 42.1 GENERAL
  - 42.2 VACUUM STATION
    - 42.2.1 Requirements
    - 42.2.2 Pre-commissioning
    - 42.2.3 Commissioning
    - 42.2.4 Handover
  - 42.3 SYSTEM VACUUM TEST
  - 42.4 POWER FAILURE TEST
  - 42.5 ODOUR CONTROL SYSTEM
    - Signed off
    - Signed-Off by Water Agency
- 43 TOLERANCES ON AS-CONSTRUCTED WORK
  - 43.1 HORIZONTAL TOLERANCES
    - 43.1.1 Sewers, mains, valves, in-line structures, vacuum stations, roads
    - 43.1.2 Property connection sewers
  - 43.2 VERTICAL TOLERANCES
    - 43.2.1 Vacuum sewers, pressure mains, structures, vacuum stations, roads
    - 43.2.2 Property connection risers and inspection openings
    - 43.2.3 Grade
  - 43.3 VERTICALITY ("PLUMB")
  - 43.4 TOLERANCES ON FINISHED SURFACE STRUCTURES AND FITTINGS
  - 43.5 CAST IN-SITU CONCRETE STRUCTURES AND SLABS
- 44 WORK AS CONSTRUCTED DETAILS
  - 44.1 GENERAL
  - 44.2 ELECTRICAL WORKS

#### 44.2.1 Electrical contractors installation drawings

#### 44.2.2 Principal supplied installation drawings and equipment schedules

### **TABLES**

Table 25.1	Control Circuit Wiring Insulation Colour Coding
Table 30.1	Timber Guardrail Default Construction Dimensions
Table 31.1	Retaining Wall Default Construction Dimensions
Table 31.2	Timber Handrail Default Construction Dimensions
Table 34.1	Methods of Achieving Curved Pipelines
Table 37.1	Maximum Particle Size
Table 41.1	Order of Acceptance Testing
Table 41.2	Minimum Compaction of Embedment and Trench/ Embankment/Other Fills
Table 41.3	Pressure and Vacuum Air Testing Acceptance Times for 7 kPa Pressure Change
Table 41.4	Concrete MH Testing Frequency
Table 41.5	Minimum Test Times for Concrete MHs
Table 43.1	Sewer Grade Tolerances
Table 43.2	Property Connection Sewer Grade Tolerances

### **FIGURES**

Figure 42.1	Typical Pre-Commissioning and Commissioning Process
Figure 42.2	Typical Handover to Water Agency



WATER SERVICES  
ASSOCIATION OF AUSTRALIA

# PART 4: STANDARD DRAWINGS

Vacuum Sewerage Code of Australia  
Version 1.3

## CONTENTS

### 45 INTRODUCTION

- 45.1 GENERAL
- 45.2 DRAWING COMMENTARY

### 46 LISTING OF STANDARD DRAWINGS

### 47 COMMENTARY ON VAC-1100 SERIES – VACUUM SEWERS

- 47.1 GENERAL
- 47.2 VAC-1100 – VACUUM SEWER PROFILE
- 47.3 VAC-1101 – VACUUM SEWER DETAILS – PVC
- 47.4 VAC-1102 – VACUUM SEWER DETAILS – PE

### 48 COMMENTARY ON VAC-1200 SERIES – COLLECTION CHAMBERS

- 48.1 GENERAL
- 48.2 VAC-1200 – VAC 1203 COLLECTION CHAMBERS WITH SINGLE OR DOUBLE VACUUM INTERFACE VALVES
- 48.3 VAC-1204 – COLLECTION CHAMBERS >2.4 M DEEP – TYPICAL LANDING DETAILS
- 48.4 VAC-1205 – COLLECTION CHAMBER WITH EMERGENCY STORAGE PIPE – TYPICAL ARRANGEMENTS
- 48.5 VAC-1206 – COLLECTION CHAMBER – SERVICE CONNECTION – PIPE PENETRATION - PROPERTY CONNECTION LAYOUT

### 49 COMMENTARY ON -1300 SERIES – VACUUM STATIONS

- 49.1 GENERAL
- 49.2 VAC-1300 – VACUUM STATION LAYOUT – HORIZONTAL VACUUM VESSEL
- 49.3 VAC-1301 – VACUUM STATION LAYOUT – VERTICAL VACUUM VESSEL

### 50 COMMENTARY ON VAC-1400 SERIES DRAWINGS – EMBEDMENT, TRENCH FILL AND RESTRAINTS

- 50.1 GENERAL
- 50.2 MAXIMUM DEPTH TO INVERT FOR STANDARD SUPPORT TYPES
- 50.3 VAC-1400 – SOIL CLASSIFICATION GUIDELINES
- 50.4 VAC-1401 – EMBEDMENT AND TRENCHFILL – TYPICAL ARRANGEMENTS
- 50.5 VAC-1402 – STANDARD EMBEDMENT – FLEXIBLE AND RIGID PIPES
- 50.6 VAC-1403 – SPECIAL EMBEDMENTS – INADEQUATE AND POOR FOUNDATION
- 50.7 VAC-1404 – SPECIAL EMBEDMENT CONCRETE AND STABILISED SUPPORTS
- 50.8 SEW-1204 – SPECIAL EMBEDMENT SUPPORT USING PILES
- 50.9 SEW-1206 – BULKHEADS AND TRENCHSTOP
- 50.10 SEW-1207 – TRENCH DRAINAGE TYPICAL SYSTEMS
- 50.11 SEW-1208 – VERTICALS AND NEAR VERTICALS EXPOSED AND CONCEALED METHODS
- 50.12 WAT-1205 – THRUST BLOCK DETAILS – CONCRETE BLOCKS
- 50.13 WAT-1206 – THRUST BLOCK DETAILS – TIMBER & RECYCLED PLASTIC BLOCKS
- 50.14 WAT-1207 – THRUST AND ANCHOR BLOCKS – GATE VALVES AND VERTICAL BENDS
- 50.15 WAT-1208 – RESTRAINED JOINT SYSTEM – DN 100 TO DN 375 DI MAINS
- 50.16 WAT-1209 – TRENCH DRAINAGE – BULKHEADS AND TRENCHSTOP
- 50.17 WAT-1210 – TRENCH DRAINAGE – TYPICAL SYSTEMS
- 50.18 WAT-1211 TO WAT-1214 – BURIED CROSSINGS

### 51 PROPERTY CONNECTION DETAILS

- 51.1 GENERAL
- 51.2 SEW-1104 AND SEW-1105 – PROPERTY CONNECTION DETAILS
- 51.3 SEW-1106 AND SEW-1107 – PROPERTY CONNECTION DETAILS – METHODS
- 51.4 SEW-1106 – IO INTERFACE METHOD
- 51.5 SEW-1107 – BURIED INTERFACE METHOD

- 51.6 SEW-1108 – PROPERTY CONNECTION DETAILS – Y BRANCH AND AROUND OBSTRUCTIONS
- 51.7 SEW-1109 – PROPERTY CONNECTION DETAILS – PRIVATE PROPERTY & MARKING SYSTEMS

## **52 COMMENTARY ON SEW-1300 SERIES – ACCESS STRUCTURES**

- 52.1 GENERAL
- 52.2 SEW-1300 – SEWERS  $\leq$ DN 300 PRECAST MH TYPES P1 AND P2
- 52.3 SEW-1301 – CAST IN-SITU MH TYPES C1 AND C2
- 52.4 SEW-1302 – MH PIPE CONNECTION DETAILS
- 52.5 SEW-1303 – SEWERS  $\leq$ DN 300 MH CHANGE IN LEVEL ARRANGEMENTS
- 52.6 SEW-1304 AND SEW-1305 – MH CHANNEL ARRANGEMENTS AND DETAILS
- 52.7 SEW-1306 – ALTERNATIVE MH DROP CONNECTIONS
- 52.8 SEW-1307 – STEP IRONS AND LADDERS
- 52.9 SEW-1308 – TYPICAL MH COVER ARRANGEMENTS
- 52.10 SEW-1313 TO SEW-1316 INCLUSIVE – MAINTENANCE SHAFTS
- 52.11 SEW-1317 – MH CONNECTION DETAILS PE PIPE

## **53 COMMENTARY ON SEW-1400 SERIES – SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS**

- 53.1 GENERAL
- 53.2 SEW-1400 – SYPHON ARRANGEMENT
- 53.3 SEW-1401 TO SEW-1403 INCLUSIVE – BURIED CROSSINGS
- 53.4 SEW-1406 – BRIDGE CROSSING

## **54 COMMENTARY ON WAT-1300 SERIES – INSTALLATION PRACTICES**

- 54.1 GENERAL
- 54.2 WAT-1303 TO WAT-1306 – TYPICAL SURFACE FITTING INSTALLATION
- 54.3 WAT-1307 – TYPICAL APPURTENANCE (SCOUR) INSTALLATION
- 54.4 WAT-1308 AND WAT-1309 – TYPICAL APPURTENACE (VALVE) INSTALLATION
- 54.5 WAT-1310 TO WAT-1312 – AERIAL CROSSINGS
- 54.6 WAT-1313 – FLANGED JOINTS

## **55 COMMENTARY ON WAT-1400 SERIES – FABRICATION DETAILS**

- 55.1 GENERAL
- 55.2 WAT-1400 – TYPICAL STEEL PIPE JOINTING – BUTT WELDING OF JOINTS
- 55.3 WAT-1401 – TYPICAL STEEL PIPE JOINTING – RRJ SPIGOT BANDS
- 55.4 WAT-1402 – TYPICAL STEEL PIPE JOINTING – WELDED PIPE COLLARS
- 55.5 WAT-1403 – TYPICAL STEEL FABRICATION – BENDS
- 55.6 WAT-1404 – TYPICAL STEEL FABRICATION – ACCESS OPENINGS
- 55.7 WAT-1408 – JOINT CORROSION PROTECTION
- 55.8 WAT-1409 – HYDRANT INSTALLATION FITTINGS – PE ASSEMBLIES

## **TABLES**

- Table 50.1 Maximum Depth to Invert for PVC Sewers
- Table 50.2 Maximum Depth to Invert for GRP Sewers
- Table 50.3 Maximum Depth to Invert for VC Sewers
- Table 50.4 Maximum Particle Size
- Table 51.1 Minimum Reticulation and Property Connection Sewer Sizes
- Table 51.2 Equivalent Stiffness Classes for PVC Sewers

## 45 LISTING OF STANDARD DRAWINGS

DRAWING NUMBER	ACTIVITY	TITLE
<b>VACUUM SYSTEM</b>		
VAC-1100	Vacuum Sewer Profile	Typical Example with Design Detail
VAC-1101	Vacuum Sewer Details	PVC
VAC-1102	Vacuum Sewer Details	PE
<b>COLLECTION CHAMBERS</b>		
VAC-1200	DN 1050 Collection Chamber with Single Vacuum Interface Valve	DN 150 & DN 225 Sewers, 1.8 & 2.4 metres deep – Typical example with design detail
VAC-1201	DN 1500 Collection Chamber with Single Vacuum Interface Valve	DN 150 & DN 225 Sewers, 1.8 & 2.4 metres deep – Typical example with design detail
VAC-1202	DN 1500 Collection Chamber with Two Vacuum Interface Valves	DN 150 & DN 225 Sewers, 1.8 & 2.4 metres deep – Typical example with design detail
VAC-1203	DN 1800 Collection Chamber with Two Vacuum Interface Valves	DN 150 & DN 225 Sewers, 1.8 & 2.4 metres deep – Typical example with design detail
VAC-1204	Collection Chambers deeper than 2.4 m	Typical Landing Details
VAC-1205	Collection Chamber	Emergency Storage Pipe – Typical Arrangements
VAC-1206	Collection Chamber	Service Connection, Pipe Penetration through Collection Chamber Walls and Typical Property Connection Layout
<b>VACUUM PUMPING STATIONS</b>		
VAC-1300	Vacuum Station Layout	Horizontal Vacuum Vessel
VAC-1301	Vacuum Station Layout	Vertical Vacuum Vessel
<b>EMBEDMENT / TRENCHFILL AND RESTRAINTS</b>		
VAC-1400	Soil Classification Guidelines	And Allowable Bearing Pressures for Anchors and Thrust Blocks
VAC-1401	Embedment & Trenchfill	Typical Arrangement
VAC-1402	Standard Embedment	Flexible & Rigid Pipes
VAC-1403	Special Embedment	Inadequate Foundations requiring Over Excavation & Replacement
VAC-1404	Special Embedment	Concrete & Stabilised Supports
SEW-1204	Special Embedment	Support Utilising Piles
SEW-1206	Trench Drainage	Bulkheads & Trenchstop
SEW-1207	Trench Drainage	Typical Systems
SEW-1208	Verticals & Near Verticals	Exposed & Concealed Methods
WAT-1205	Thrust Block Details	Concrete Blocks
WAT-1206	Thrust Block Details	Timber & Recycled Plastic Blocks
WAT-1207	Thrust and Anchor Blocks	Gate Valves and Vertical Bends
WAT-1208	Restrained Joint System	DN 100 to DN 375 DI Mains
WAT-1209	Trench Drainage	Bulkheads and Trenchstop
WAT-1210	Trench Drainage	Typical Systems
WAT-1211	Buried Crossings	Under Obstructions

DRAWING NUMBER	ACTIVITY	TITLE
WAT-1212	Buried Crossings	Major Roadways
WAT-1213	Buried Crossings	Railways
WAT-1214	Buried Crossings	Bored & Jacked Encasing Pipe Details
<b>PROPERTY CONNECTION DETAILS</b>		
SEW-1104	Property Connection Details	Sewer in Road Reserve
SEW-1105	Property Connection Details	Sewer in Easements & Inside Property
SEW-1106	Property Connection Details	IO Interface Method
SEW-1107	Property Connection Details	Buried Interface Method
SEW-1108	Property Connection Details	"Y" Branch & Around Obstructions
SEW-1109	Property Connection Details	Private Property & Marking Systems
<b>ACCESS STRUCTURES</b>		
SEW-1300	Maintenance Holes	Sewers $\leq$ DN 300 Precast Types P1 & P2
SEW-1301	Maintenance Holes	Sewers $\leq$ DN 300 Cast In-situ Types C1 & C2
SEW-1302	Maintenance Holes	Pipe Connection Details
SEW-1303	Maintenance Holes	Sewers $\leq$ DN 300 Changes in Level Details
SEW-1304	Maintenance Holes	For Sewers $\leq$ DN 300 Typical Channel Arrangements
SEW-1305	Maintenance Holes	Typical Channel Details
SEW-1306	Maintenance Holes	Alternative Drop Connections
SEW-1307	Maintenance Holes	Step Irons & Ladders
SEW-1308	Maintenance Holes	Typical MH Cover Arrangements
SEW-1313	Maintenance Shafts	Typical Installation
SEW-1314	Maintenance Shafts	MS & Variable Bend Installations
SEW-1315	Maintenance Shafts	TMS and Connection Installations
SEW-1316	Maintenance Shafts	Typical MS Cover Arrangements
SEW-1317	Maintenance Holes	MH Connection Details DN 110 to DN 450 PE Pipe
<b>SPECIAL CROSSINGS / STRUCTURES ARRANGEMENTS</b>		
SEW-1400	Buried Crossings	Syphon Arrangement
SEW-1401	Buried Crossings	Railways
SEW-1402	Buried Crossings	Major Roadways
SEW-1403	Buried Crossings	Bored & Jacked Encasing Pipe Details
SEW-1404	Aerial Crossings	Aqueduct
SEW-1405	Aerial Crossings	Aqueduct Protection Grille
SEW-1406	Aerial Crossings	Bridge Crossing Concepts

<b>INSTALLATION PRACTICES</b>		
<a href="#">WAT-1300</a>	Valve and Hydrant Identification	Identification Markers and Marker Posts
<a href="#">WAT-1303</a>	Typical Surface Fitting Installation	Gate Valve Surface Boxes Non Trafficable
<a href="#">WAT-1304</a>	Typical Surface Fitting Installation	Gate Valve Surface Boxes Trafficable
<a href="#">WAT-1305</a>	Typical Surface Fitting Installation	Hydrant Surface Boxes Trafficable and Non Trafficable
<a href="#">WAT-1306</a>	Typical Surface Fitting Installation	Hydrant Surface Boxes Trafficable
<a href="#">WAT-1307</a>	Typical Appurtenance Installation	Scour Arrangements
<a href="#">WAT-1308</a>	Typical Appurtenance Installation	Valve Chambers
<a href="#">WAT-1309</a>	Typical Appurtenance Installation	Pressure Reducing Valves (PRV)
<a href="#">WAT-1310</a>	Aerial Crossings	Aqueduct
<a href="#">WAT-1311</a>	Aerial Crossings	Aqueduct Protection Grille
<a href="#">WAT-1312</a>	Aerial Crossings	Bridge Crossing Concepts
<a href="#">WAT-1313</a>	Flanged Joints	Bolting Details
<b>FABRICATION DETAILS</b>		
<a href="#">WAT-1400</a>	Typical Steel Pipe Jointing	Butt Welding of Joints
<a href="#">WAT-1401</a>	Typical Steel Pipe Jointing	Rubber Ring Joint Spigot Bands
<a href="#">WAT-1402</a>	Typical Steel Pipe Jointing	Welded Pipe Collars
<a href="#">WAT-1403</a>	Typical Steel Fabrication	Bends
<a href="#">WAT-1404</a>	Typical Steel Fabrication	Access Opening for Pipes $\geq$ DN 750
<a href="#">WAT-1408</a>	Joint Corrosion Protection	Cement Mortar Lined Steel Pipe DN 300 to DN 1200
<a href="#">WAT-1409</a>	Hydrant Installation Fittings	PE Assemblies